

PROFESSIONAL BOOK

-PRODUCTS FOR CERAMIC INSTALLATION-



This catalogue is protected under the Spanish Intellectual Property Act (Royal Decree 1/1996).
Any reproduction of its contents, in whole or in part, without the express consent of PORCELANOSA Grupo
will be subject to punitive action under the Spanish Criminal Code.



ÍN DEX

- 5 Decorative and technical profiles
- 73 Tile installation adhesives
- 87 Grouting material and elastic joint sealants
- 109 Substrate preparation products
- 121 Waterproofing
- 129 Concept systems



Profiles

Decorative profiles

Crystal collection	7
Pearls collection	15
Elegance collection	17
Gold collection	25
Metal collection	27
Chrome collection	43
Wood collection	45
pro-telo collection	46

Corner profiles and trims for wall tiles

pro-mate 2	49
pro-mate 3	50
pro-mate 5	51
pro-part Li	52
pro-part	53
pro-mate 45	55
pro-corner	57
XLIGHT profiles	58

Technical profiles

pro-T	61
pro-level	62
pro-shower	63
pro-balcony	64
pro-dilata	65
Expansion joints	67
pro-step	68
pro-flex	69
pro-sanit	70
pro-plint	71
pro-skirting	72

Graphic index

Decorative profiles



Crystal collection
Page 7



Pearls collection
Page 15



Elegance collection
Page 17



Gold collection
Page 25



Metal collection
Page 27



Chrome collection
Page 43



Wood collection
Page 45



pro-telo collection
Page 46

Corner profiles and trims for wall tiles



pro-mate 2
Page 49



pro-mate 3
Page 50



pro-mate 5
Page 51



pro-part Li
Page 52



pro-part
Page 53




pro-mate 45
Page 55




pro-corner
Page 57


Technical profiles




pro-T
Page 61



pro-level
Page 62




pro-shower
Page 63




pro-balcony
Page 64




pro-dilata
Page 65



Expansion joints
Page 67



pro-step
Page 68



pro-flex
Page 69



pro-sanit
Page 70



pro-plint
Page 71



pro-skirting
Page 72



Decorative profiles

Crystal collection

High-end decorative profile for ceramic wall tiling, made with Swarovski crystals.
Replaces the traditional decorative ceramic listellos by new design metallic lines.



pro-part Li Crystal SW Galaxy

pro-part Li Crystal SW Galaxy

Chromed brass profile. Made with Swarovski Elements



pro-part Li Crystal SW Galaxy 11 mm
11x11x 2500 mm

B71342657 100171653
278.09 p/u

Crystal collection


High-end decorative profile for ceramic wall tiling, made with Swarovski crystals.
Replaces the traditional decorative ceramic listellos by new design metallic lines.



pro-part Li Crystal rock SW Silver

pro-part Li Crystal rock SW Silver

Chromed brass profile. Made with Swarovski Elements




pro-part Li Crystal rock SW Silver 11 mm
11x11x2500 mm

873141325
382.81 p/u

pro-part Li Crystal rock SW Graphite

Brass profile with dark metallic finish. Made with Swarovski Elements



pro-part Li Crystal rock SW Graphite 11 mm
11x11x 2500 mm

873141326
429.02 p/u

Crystal collection


High-end decorative profile for ceramic wall tiling, made with Swarovski crystals.
Replaces the traditional decorative ceramic listellos by new design metallic lines.



pro-part Li chromed brass SW 1500

pro-part Crystal SW Gold

24 k gold plated. Made with Swarovski Elements



pro-part Crystal SW Gold 11 mm
8 x 11 x 2500 mm

B71342629
478.34 p/u

pro-part Crystal SW Silver

Chromed brass profile. Made with Swarovski Elements




pro-part Crystal SW Silver 11 mm
8 x 11 x 2500 mm

B71342631
425.15 p/u

pro-part Crystal SW Graphite

Chromed brass profile. Made with Swarovski Elements



pro-part Crystal SW Graphite 11 mm
8x11x2500 mm

B71342630
481.47 p/u

Crystal collection

High-end decorative profile for ceramic wall tiling, made with Swarovski crystals.
Replaces the traditional decorative ceramic listellos by new design metallic lines.



pro-part Li Crystal sand SW Silver

pro-part Li Crystal sand SW Gold

24 k gold plated. Made with Swarovski Elements




pro-part Li Crystal sand SW Gold 11 mm
11x11x2500 mm

B73141323
319.15 p/u

pro-part Li Crystal sand SW Silver

Chromed brass profile. Made with Swarovski Elements



pro-part Li Crystal sand SW Silver 11 mm
11x11x2500 mm

B73141322
272.06 p/u

Pearls collection


High-end decorative profile for ceramic wall tiling, made with Swarovski pearls.
Replaces the traditional decorative ceramic listellos by new design metallic lines.



pro-part Li Pearls SW Silver

pro-part Li Pearls SW Gold

24 carat gold plated profile. Made with Swarovski elements



pro-part Li Pearls SW Gold 11 mm
11x11x2500 mm

B71342632
454.38 p/u

pro-part Li Pearls SW Silver

Chromed brass profile. Made with Swarovski Elements



pro-part Li Pearls SW Silver 11 mm
11x11x2500 mm

B71342628
433,31 p/u

Elegance collection

High-end decorative profile for ceramic wall tiling, made with Swarovski crystals.
Replaces the traditional decorative ceramic listellos by new design metallic lines.



pro-part Li chromed brass SW 1500

pro-part Li Gold SW 1500

24 k gold plated. Made with Swarovski Elements



pro-part Li Gold SW 1500 11 mm
11 x 11 x 2500 mm

873141324
466,52 p/u

pro-part Li Chrome SW 1500

Chromed brass profile. Made with Swarovski Elements



pro-part Li chromed brass SW 1500 11 mm
11 x 11 x 2500 mm

871342597
416,09 p/u

Elegance collection

High-end decorative profile for ceramic wall tiling, made with Swarovski crystals.
Replaces the traditional decorative ceramic listellos by new design metallic lines.



pro-mate 5 Gold SW 168

pro-mate 5 Gold SW 500

24 k gold plated. Made with Swarovski Elements



pro-mate 5 Gold SW 500 11 mm
5x11x2500 mm

B71342585
310.30p/u

pro-mate 5 Chrome SW 500

Chromed brass profile. Made with Swarovski Elements




pro-mate 5 chromed brass SW 500 11 mm
5x11x2500 mm

B71342584
288.13 p/u

Elegance collection

High-end decorative profile for ceramic wall tiling, made with Swarovski crystals.
Replaces the traditional decorative ceramic listellos by new design metallic lines.



pro-mate 5 Chrome SW 500

pro-mate 5 Gold SW 168

24 k gold plated. Made with Swarovski Elements



pro-mate 5 Gold SW 168 11 mm
5x11x2500 mm

B71342587
218.23 p/u

pro-mate 5 Chrome SW 168

Chromed brass profile. Made with Swarovski Elements



pro-mate 5 chromed brass SW 168 11 mm
5x11x2500 mm

B71342586
161.59 p/u

Elegance collection


High-end decorative profile for ceramic wall tiling, made with Swarovski crystals.
Replaces the traditional decorative ceramic listellos by new design metallic lines.



pro-mate 5 chrome SW glass

pro-mate 5 Gold SW Glass

24 k gold plated. Made with Swarovski Elements




pro-mate 5 Gold SW Glass 11 mm
5x11x2500 mm

B71342639
278.05 p/u

pro-mate 5 chrome SW glass

Chromed brass profile. Made with Swarovski Elements



pro-mate 5 chromed brass SW glass 11 mm
5x11x2500 mm

B71342603
288.59 p/u

Gold collection

High-end decorative profile for wall tiles, 24K gold plated.
It substitutes the traditional ceramic frieze by a metallic line with an exclusive design.



pro-part Gold

pro-part Li Gold

24 carat gold plated profile. 11 mm decorative trim.



pro-part Li gold 24 K 12,5 mm	B71342578
12,5x11,5x2500 mm	89.23 p/u
pro-part Li gold 24 K 11 mm	B71342574
11x10x2500 mm	85.27 p/u

pro-part Gold

24 carat gold plated profile. 8 mm decorative trim.



pro-part gold 24 K 12,5 mm	B71342575
8x12,5x2500 mm	82.21 p/u
pro-part gold 24 K 11 mm	B71342577
8x11x2500 mm	80.13 p/u

pro-mate 5 Gold

24 carat gold plated profile. 5 mm decorative trim.



pro-mate 5 gold 24 K 12,5 mm	B71342573
5x12,5x2500 mm	77.59 p/u
pro-mate 5 gold 24 K 11 mm	B71342572
5x11x2500 mm	76.61 p/u

Metal collection


Metallic finish decorative profiles for ceramic wall tiles. It substitutes the traditional ceramic frieze.



pro-part Rose

pro-part rose

Brass profile with metallic covering, 8 mm decorative trim.



pro-part latón rose 11 mm
8x11x2500 mm

B71342651
64.41 p/u

Metal collection

Metallic finish decorative profiles for ceramic wall tiles. It substitutes the traditional ceramic frieze.



pro-part Antique

pro-part antique

Brass profile with metallic covering, 8 mm decorative trim.



pro-part antique 11 mm
8x11x2500 mm

B71342650
62.00 p/u

Metal collection

Metallic finish decorative profiles for ceramic wall tiles. It substitutes the traditional ceramic frieze.



pro-part Ocean

pro-part ocean


Brass profile with metallic covering. 8 mm decorative trim.



pro-part brass ocean 7 mm	B71342680
8x7x2500 mm	55,62 p/u
pro-part brass ocean 11 mm	B71342595
8x11x2500 mm	65.98 p/u
pro-part brass ocean 12,5 mm	B71342675
8x12,5x2500 mm	56,66 p/u

pro-part ocean line

Brass profile with metallic covering. 8 mm decorative trim.



pro-part brass ocean line 7 mm	B71342677
8x7x2500 mm	56,83 p/u
pro-part brass ocean line 11 mm	B71342635
8x11x2500 mm	64.84 p/u
pro-part brass ocean line 12,5 mm	B71342666
8x12,5x2500 mm	58,26 p/u

Metal collection

Metallic finish decorative profiles for ceramic wall tiles. It substitutes the traditional ceramic frieze.



pro-part brass moon line

pro-part moon

Brass profile with metallic covering. 8 mm decorative trim.



pro-part brass moon 7 mm	B71342681
8x7x2500 mm	55.62 p/u
pro-part brass moon 11 mm	B71342591
8x11x2500 mm	67.89 p/u
pro-part brass moon 12,5 mm	B71342673
8x12,5x2500 mm	58.26 p/u

pro-part moon line

Brass profile with metallic covering. 8 mm decorative trim.



pro-part brass moon line 7 mm	B71342683
8x7x2500 mm	56.83 p/u
pro-part brass moon line 11 mm	B71342634
8x11x2500 mm	64.84 p/u
pro-part brass moon line 12,5 mm	B71342674
8x12,5x2500 mm	58.26 p/u

Metal collection

Metallic finish decorative profiles for ceramic wall tiles. It substitutes the traditional ceramic frieze.



pro-part Line

pro-part line

Brass profile with metallic covering, 8 mm decorative trim.



pro-part brass line 7 mm	B71342684
8x7x2500 mm	53.06 p/u
pro-part brass line 11 mm	B71342593
8x11x2500 mm	64.20 p/u
pro-part brass line 12,5 mm	B71342678
8x12,5x2500 mm	58.26 p/u

pro-part line matt

Brass profile with metallic covering, 8 mm decorative trim.



pro-part brass line matt 7 mm	B71342682
8x7x2500 mm	53.06 p/u
pro-part brass line matt 11 mm	B71342633
8x11x2500 mm	60.41 p/u
pro-part brass line matt 12,5 mm	B71342676
8x12,5x2500 mm	55.48 p/u

Metal collection

Metallic finish decorative profiles for ceramic wall tiles. It substitutes the traditional ceramic frieze.



pro-part Oxyde

pro-mate 5 oxyde

Brass profile with metallic covering. 5 mm decorative trim.



pro-mate 5 brass oxyde 11 mm
8x11x2500 mm

B71342599
74.98 p/u

pro-part oxyde

Brass profile with metallic covering. 8 mm decorative trim.



pro-part antique 11 mm
8x11x2500 mm

B71342601
79.91 p/u

Metal collection

Metallic finish decorative profiles for ceramic wall tiles. It substitutes the traditional ceramic frieze.



pro-part Graphite

pro-part graphite


Brass profile with metallic covering. 5 mm decorative trim.



pro-part brass graphite 7 mm	B71342671
8x7x2500 mm	53.70 p/u
pro-part brass graphite 11 mm	B71342590
8x11x2500 mm	67.17 p/u
pro-part brass graphite 12,5 mm	B71342667
8x12,5x2500 mm	58.04 p/u

pro-mate 5 graphite

Brass profile with metallic covering. 8 mm decorative trim.



pro-mate 5 graphite 7 mm	B71342670
5x7x2500 mm	50.92 p/u
pro-mate 5 graphite 11 mm	B71342598
5x11x2500 mm	62.75 p/u
pro-mate 5 graphite 12,5 mm	B71342665
5x12,5x2500 mm	53.70 p/u

Metal collection

Metallic finish decorative profiles for ceramic wall tiles. It substitutes the traditional ceramic frieze.



pro-part Graphite matt

pro-part graphite matt

Brass profile with metallic covering, 8 mm decorative trim.



pro-part brass graphite matt 7 mm	B71342672
8x7x2500 mm	59.97 p/u
pro-part brass graphite matt 11 mm	B71342636
8x11x2500 mm	66.64 p/u
pro-part brass graphite matt 12,5 mm	B71342668
8x12,5x2500 mm	59.54 p/u

pro-part graphite matt line

Brass profile with metallic covering, 8 mm decorative trim.




pro-part brass graphite matt line 7 mm	B71342679
8x7x2500 mm	59.96 p/u
pro-part brass graphite matt line 11 mm	B71342637
8x11x2500 mm	66.64 p/u
pro-part brass graphite matt line 12,5 mm	B71342669
8x12,5x2500 mm	59.74 p/u

Chrome collection


Chromed brass decorative profile for wall tiles. It substitutes the traditional decorative ceramic frieze. Typical LIFESTYLE by PROCELANOSA profile.

Suitable for trimming corners and transitions between ceramic tiles.




pro-mate 3

Chromed brass			h (mm)	P/UK
KEA				
B71342608	XLIGHT		6	42.31 p/u
B71133001			8	38.84 p/u
B71133002			9	38.17 p/u
B71133003			10	38.63 p/u
B71133004			12.5	39.57 p/u





pro-mate 5

Chromed brass			h (mm)	P/UK
KEA				
B71342611	XLIGHT		7	49.32 p/u
B71132003			9	44.19 p/u
B71132004			11	45.81 p/u
B71134004			12.5	47.42 p/u




pro-part

Chromed brass			h (mm)	P/UK
KEA				
B73134001	XLIGHT		7	47.86 p/u
B73134002			9	49.75 p/u
B71342552			10	57.39 p/u
B73134003			11	51.62 p/u
B73141319	Porcelanosa		11	60.96 p/u
B73134004			12.5	53.28 p/u
B73141312	Shade 2		12.5	53.28 p/u
B73134005			15	56.11 p/u



Chromed brass corner

KEA	SAP		h (mm)	P/UK
B73134301	100005373	XLIGHT	7	17.92 p/u
B73134302	100005374		9	17.92 p/u
B71342554	100091065		10	19.48 p/u
B73134303	100005375		11	17.92 p/u
B73134304	100005376		12.5	17.92 p/u
B71342541	100067718		15	22.08 p/u



pro-part Li

Chromed brass			h (mm)	a (mm)	P/UK
KEA					
B71342618	XLIGHT		4,5	5,5	56.07 p/u
B71342542			11	12	68.85 p/u
B71342543			12,5	13,5	72.52 p/u
B71342545			15	16	72.90 p/u

Chromed brass corner

KEA	SAP		h (mm)	P/UK
B72141343	100098464		11	22.23 p/u
B71342550	100085153		12.5	24.79 p/u



pro-telo mosaic


Chromed brass			h (mm)	P/UK
KEA				
B72141345	Mosaic 25		4	58.46 p/u



Wood collection

Wood profiles for wall and floor tile coverings. Page Excellent solution for the design of ceramic settings with either contemporary or traditional style.

Available as a decorative line for ceramic wall tiles and as special pieces for steps.



pro-telo W

pro-telo W 15 chromed brass

KEA		h (mm)	P/UK
B72141306	Caoba 15	12.5	106,39 p/u
B72141309	Wenge 15	12.5	113,86 p/u
B72141314	Nogal 15	12.5	108,24 p/u

pro-telo W 25 chromed brass

KEA		h (mm)	P/UK
B72141305	Caoba 25	12.5	108,24 p/u
B72141312	Wenge 25	12.5	115,72 p/u
B72141310	Nogal 25	12.5	111,99 p/u

pro-telo carbono

pro-telo 11x30 carbono

KEA	h (mm)	P/UK
B72141321	11	77,46 p/u

pro-step W Toscana

KEA	SAP		h (mm)	P/EU
B76211008	100158280	wenge	12,5	89,64 p/u
B76211007	100158269	caoba	12,5	89,64 p/u

pro-step W

KEA	h (mm)	P/UK
B76211006	12.5	84,99 p/u

pro-step W

KEA	h (mm)	P/UK
B76211001	10	68,7 p/u

Do not use **pro-telo W** profiles in coverings which come into direct contact with water.
pro-step W profiles are supplied untreated so that the final user can choose the finishing of the step.


Profile length: 2500 mm

Minimum packaging: 10 profiles

pro-telo collection

Metal decorative profile for ceramic wall tiles. Flangeless metallic line for tiles of any thickness.

Available in a wide variety of materials, finishes and dimensions, they represent an excellent solution for the design of contemporary style ceramic settings.



pro-telo stainless 8x40

Stainless Steel 8x40

KEA		h (mm)	P/UK
B72141110	Gloss	8	52.59 p/u
B72141210	Brushed	8	58.95 p/u

pro-telo stainless 8x25

Stainless Steel 8x25

KEA		h (mm)	P/UK
B72141101	Gloss	8	29.35 p/u
B72141201	Brushed	8	38.64 p/u
B72141320	Squared chrome	8	68.85 p/u

pro-telo stainless 8x10

KEA		h (mm)	P/UK
B72141005	Matt URBATEK	8	25.02 p/u
B72141006	Gloss URBATEK	8	24.43 p/u

pro-telo aluminium

Aluminium 8x10 gloss

KEA		h (mm)	P/UK
B72124001	Gold	10	20.04 p/u
B72124002	Silver	10	20.04 p/u

Aluminium 8x10 anodized

KEA		h (mm)	P/UK
B72122001	Gold	10	13.78 p/u
B72122002	Silver	10	12.76 p/u

pro-telo recto


Aluminium 8x10

KEA		h (mm)	P/UK
B72141318	High gloss	8	17.44 p/u
B72141348	Silver anodized	8	13.49 p/u
B72141346	Titanium	8	14.80 p/u
B72141350	Cosmos	8	16.80 p/u

Profile length: 2500 mm

pro-telo titanium profile length: 2400 mm

Minimum packaging: 10 profiles




Corner profiles and trims for wall tiles

pro-mate 2

Right angle, stainless steel profile for corners and wall and floor tile coverings.

Right angle, stainless steel profiles for trimming the non-glazed edge of the tile. Suitable for separating tiles in walls as well as in floors.



pro-mate 2

V2A Stainless steel

KEA		h (mm)	P/UK
B71342617	XLIGHT	6	20.47 p/u
B71141001		8	17.61 p/u
B71141002		10	18.45 p/u
B71141003		12.5	19.08 p/u
B71141004		15	32.05 p/u
B71141005		20	34.40 p/u

Gloss stainless steel

KEA		h (mm)	P/UK
B71142001		8	26.51 p/u
B71142002		10	27.57 p/u
B71142003		12.5	28.42 p/u
B71142004		15	39.57 p/u



V4A Stainless steel

KEA		h (mm)	P/UK
B71141008		8	19.51 p/u
B71141009		10	21.25 p/u
B71141010		12.5	26.32 p/u

pro-mate 3

Right angle profile for corners and wall and floor tile coverings. Decorative use as a metallic line.

Right angle, 3 mm thick profiles for trimming the non-glazed edge of the tile. Available in a wide variety of materials, they are also suitable for separating wall tiles.



pro-mate 3

Chromed brass

KEA		h (mm)	P/UK
B71342608	XLIGHT	6	42.31 p/u
B71133001		8	38.84 p/u
B71133002		9	38.17 p/u
B71133003		10	38.63 p/u
B71133004		12.5	39.57 p/u

Anodized aluminium silver

KEA		h (mm)	P/UK
B71342616	XLIGHT	6	14.32 p/u
B71122001		8	7.89 p/u
B71122002		9	8.10 p/u
B71122003		10	8.30 p/u
B71122004		12.5	8.91 p/u
B71122005		15	10.12 p/u

Lacquered aluminium

KEA		h (mm)	P/UK
B71342609	White XLIGHT	6	12.03 p/u
B71123001	White	8	10.93 p/u
B71123003	White	10	11.54 p/u
B71123004	White	12.5	12.56 p/u
B71123005	Beige	8	10.93 p/u
B71123007	Beige	10	11.54 p/u
B71123008	Beige	12.5	12.56 p/u
B71123009	Negro	8	10.93 p/u
B71123011	Negro	10	11.54 p/u
B71123012	Negro	12.5	12.56 p/u

High gloss aluminium


KEA		h (mm)	P/UK
B71124003		10	17.64 p/u
B71124004		12.5	18.17 p/u

PVC

KEA		h (mm)	P/UK
B71111009	White	10	4.32 p/u
B71111017	White	12.5	4.66 p/u
B71111010	Jazmín	10	4.32 p/u
B71111018	Jazmín	12.5	4.66 p/u
B71111011	Beige	10	4.32 p/u
B71111019	Beige	12.5	4.66 p/u
B71111012	Negro	10	4.32 p/u
B71111020	Negro	12.5	4.66 p/u
B71111013	Grey	10	4.32 p/u
B71111021	Grey	12.5	4.66 p/u
B71111014	Marfil	10	4.32 p/u
B71111022	Marfil	12.5	4.66 p/u

pro-mate 5

Right angle profile for corners and wall and floor tile coverings. Decorative use as a metallic line.
Right angle and 5 mm edge profiles for trimming the non-glazed edge of the tile. Suitable for transitions between floor coverings at the same level.



pro-mate 5

Chromed brass



KEA		h (mm)	P/UK
B71342611	XLIGHT	7	49.32 p/u
B71132003		9	44.19 p/u
B71132004		11	45.81 p/u
B71134004		12.5	47.42 p/u

Gloss polished brass

KEA		h (mm)	P/UK
B71132002		11	34.01 p/u

Anodized aluminium silver


KEA		h (mm)	P/UK
B71125003		11	12.38 p/u



pro-part Li

Decorative profile for ceramic wall tiles. Suitable for trimming corners and transitions between ceramic tiles.

Right angle, corner shaped profiles, with both sides of the same length. Specially recommended for rectified tiles corners and for tiles with relief decoration.



pro-part Li

Chromed brass

KEA		h (mm)	a (mm)	P/UK
B71342618	XLIGHT	4,5	5,5	56.07 p/u
B71342542		11	12	68.85 p/u
B71342543		12,5	13,5	72.52 p/u
B71342545		15	16	74.36 p/u

Anodized aluminium silver

KEA		h (mm)	a (mm)	P/UK
B71342619	XLIGHT	4,5	5,5	12.55 p/u
B71342539		11	12	18.50 p/u
B71342537		12,5	13,5	20.25 p/u

High gloss aluminum

KEA		a (mm)	h (mm)	P/UK
B71342535		11	10	34.27 p/u
B71342538		12,5	11,5	36.85 p/u



Chromed brass corner

KEA		h (mm)	P/UK
B72141343		11	22.23 p/u
B71342550		12,5	24.79 p/u

Anodized aluminium silver corner

KEA		h (mm)	P/UK
B71342557		11	19.85 p/u
B71342556		12,5	19.85 p/u


High gloss aluminum corner

KEA		h (mm)	P/UK
B71342581		11	8.90 p/u
B71342580		12,5	10.83 p/u


pro-part

Decorative profile for ceramic wall tiles. Suitable for trimming corners and transitions between ceramic tiles.

Right angle, corner shaped profiles, with an 8 mm edge and a variable width edge. Excellent solution for a wide variety of ceramic installations.



pro-part



Chromed brass			
KEA		h (mm)	P/UK
B73134001	XLIGHT	7	47.86 p/u
B73134002		9	49.75 p/u
B71342552		10	57.39 p/u
B73134003		11	51.62 p/u
B73134004	Shade 1	12.5	53.28 p/u
B73141312	Shade 2	12.5	53.28 p/u
B73134005		15	56.11 p/u

Chromed brass corner			
KEA		h (mm)	P/UK
B73134301	XLIGHT	7	17.92 p/u
B73134302		9	17.92 p/u
B71342554		10	19.48 p/u
B73134303		11	17.92 p/u
B73134304		12.5	17.92 p/u
B71342541		15	22.08 p/u

Stainless steel			
KEA		h (mm)	P/UK
B73141009		9	24.17 p/u
B73141010		11	25.88 p/u
B73141011		12.5	28.00 p/u

Stainless steel corner			
KEA		h (mm)	P/UK
B73141309		9	17.81 p/u
B73141310		11	17.81 p/u
B73141311		12.5	19.24 p/u

Anodized aluminium silver			
KEA		h (mm)	P/UK
B73122001	XLIGHT	7	11.33 p/u
B73122002		9	11.94 p/u
B73122003		11	12.56 p/u
B73122004		12.5	13.76 p/u
B73122005		15	14.98 p/u
B73122006		20	16.20 p/u
B73122007		25	16.80 p/u

Anodized aluminium silver corner			
KEA		h (mm)	P/UK
B73122301	XLIGHT	7	13.76 p/u
B73122302		9	13.76 p/u
B73122303		11	13.76 p/u
B73122304		12.5	13.76 p/u


Anodized aluminium gold			
KEA		h (mm)	P/UK
B73122009		9	12.56 p/u
B73122010		11	13.15 p/u
B73122011		12.5	14.17 p/u
B73122014		25	17.61 p/u

High gloss aluminum			
KEA		h (mm)	P/UK
B73141317		11	51.77 p/u
B73124004		12.5	49.97 p/u

Black matt aluminium			
KEA	SAP	h (mm)	P/EU
B71342659	100171975	11	22.98 p/u



pro-part





Lacquered aluminium			
KEA		h (mm)	P/UK
B71342551	Black	11	25.90 p/u
B71342547	Black	12.5	29.07 p/u
B71342576	White	11	25.41 p/u
B71342549	White	12.5	29.07 p/u

Gloss polished brass			
KEA		h (mm)	P/UK
B73132003		11	42,56 p/u
B73132004		12.5	43,95 p/u

pro-mate 45

Rounded profile for protecting wall tiles corners.

These profiles are the classic solution for protecting corners in wall tile coverings. Available in a wide variety of materials, its main feature is being shock-resistant.



pro-mate 45 TOP

Chromed brass

KEA		h (mm)	P/UK
B71342614	TOP XLIGHT	6	51.05 p/u
B71342565	TOP	10	51.04 p/u
B71342620	TOP	12,5	61.35 p/u

Anodized aluminium silver

KEA		h (mm)	P/UK
B71342612	TOP XLIGHT	6	16.62 p/u

pro-mate 45 brass

Chromed brass

KEA		h (mm)	P/UK
B71342615	XLIGHT	6	53.64 p/u
B71342566		10	59.46 p/u
B71342567		12,5	63.55 p/u

Chromed brass corner

KEA	h (mm)	P/UK
B71342606	10	26.12 p/u

Gloss polished brass

KEA	h (mm)	P/UK
B71332003	12,5	40.48 p/u

pro-mate 45 stainless steel

Stainless steel V2A

KEA		h (mm)	P/UK
B71342613	XLIGHT	6	23.73 p/u
B71341001		8	29.20 p/u
B71341002		10	37.55 p/u
B71341003		12,5	33.36 p/u

Gloss stainless steel

KEA	h (mm)	P/UK
B71342001	8	28.00 p/u
B71342002	10	29.26 p/u
B71342003	12,5	30.97 p/u

Stainless steel corner

KEA	h (mm)	P/UK
B71341501	8	15.97 p/u

Gloss stainless steel corner

KEA	h (mm)	P/UK
B71342504	8	19.00 p/u
B71342505	10	19.00 p/u
B71342506	12,5	19.00 p/u

pro-mate 45 aluminium

Anodized aluminium silver

KEA		h (mm)	P/UK
B71342607	XLIGHT	6	10.47 p/u
B71322001		8	9.32 p/u
B71322003		10	10.12 p/u
B71322005		12,5	11.14 p/u

Anodized aluminium gold

KEA	h (mm)	P/UK
B71322002	8	10.12 p/u
B71322004	10	10.12 p/u
B71322006	12,5	11.14 p/u

pro-mate 45 aluminio

Lacquered aluminium

KEA		h mm	P/UK
B71342610	White XLIGHT	6	12.98 p/u
B71323005	White	10	11.57 p/u
B71323009	White	12,5	12.54 p/u
B71323006	Beige	10	11.57 p/u
B71323010	Beige	12,5	12.54 p/u
B71323007	Pergamon	10	11.91 p/u
B71323011	Pergamon	12,5	12.54 p/u

High gloss aluminium

KEA	h (mm)	P/UK
B71342562	10	21.76 p/u
B71342570	12,5	21.83 p/u

Anodized aluminium gloss gold

KEA	h (mm)	P/UK
B71342571	12,5	21.83 p/u

pro-mate 45 PVC gloss

PVC

KEA		h (mm)	P/UK
B71211007	White	10	6.65 p/u
B71211025	White	12.5	5.16 p/u
B71211026	Jazmín	12.5	5.16 p/u
B71211008	Marfil	10	6.65 p/u
B71211031	Marfil	12.5	5.16 p/u
B71211009	Beige	10	6.65 p/u
B71211027	Beige	12.5	5.16 p/u
B71211010	Grey	10	6.65 p/u
B71211028	Grey	12.5	5.16 p/u

Lacquered aluminium corner

KEA		h mm	P/UK
B71323505	White	10	8.89 p/u
B71323516	Beige	12,5	8.89 p/u
B71323507	Pergamon	10	8.89 p/u
B71323517	Pergamon	12,5	9.61 p/u

High gloss aluminum corner

KEA	h (mm)	P/UK
B71342563	10	21.24 p/u

PVC corner

KEA		h (mm)	P/UK
B71211325	White blister	12.5	2.73 p/u
B71211317	Jazmín blister	10	2.93 p/u
B71211326	Jazmín blister	12.5	2.73 p/u
B71211308	Marfil blister	10	2.93 p/u
B71211331	Marfil blister	12.5	2.73 p/u
B71211309	Beige blister	10	2.93 p/u
B71211327	Beige blister	12.5	2.73 p/u
B71211310	Grey blister	10	2.93 p/u
B71211328	Grey blister	12.5	2.73 p/u

pro-mate 45 PVC matt

PVC Closed

KEA		h (mm)	P/UK
B71311010	White	10	4.82 p/u
B71311011	Jazmín	10	4.82 p/u
B71311014	Marfil	10	4.82 p/u

pro-mate 45 PVC II

PVC II

KEA		h (mm)	P/UK
B71342512	White	10	1.05 p/u
B71342510	White	12.5	1.15 p/u
B71342514	Grey	10	1.05 p/u
B71342513	Grey	12.5	1.15 p/u
B71342515	Marfil	10	1.05 p/u
B71342511	Marfil	12.5	1.15 p/u



PVC II corner

KEA		h (mm)	P/UK
B71342526	White	10	5.97 p/u
B71342531	White	12.5	5.85 p/u
B71342527	Grey	10	5.85 p/u
B71342522	Grey	12.5	5.85 p/u
B71342524	Marfil	10	5.97 p/u
B71342529	Marfil	12.5	5.85 p/u

pro-corner

Metallic profile for protecting corners.


Right angle, metallic profiles for protecting corners. Most of the pro-corner models are installed after the tile, which implies a small lip over the tile surface.



pro-corner P

Aluminium					
KEA	SAP		h1 (mm)	h2 (mm)	P/EU
B78141126	100158001	high gloss	15	12	71.94 p/u
B78141127	100158002	silver	15	12	63.50 p/u


Profile length: 2500 mm



pro-corner mosaic


Aluminium				
KEA			h (mm)	P/UK
B78141122	high gloss		4.4	36.41 p/u
B78141123	anodized silver		4.4	21.68 p/u

Profile length: 2700 mm



pro-corner R

Stainless steel				
KEA			h (mm)	P/UK
B78141107			25	45.14 p/u
B78141109			40	66.95 p/u



Gloss stainless steel

KEA	h (mm)	P/UK
B78141112	25	42.80 p/u
B78141113	30	53.74 p/u
B78141114	40	66.16 p/u

Profile length: 2500 mm

Brushed stainless steel

KEA	h (mm)	P/UK
B78141117	25	46.11 p/u
B78141118	30	53.74 p/u

Longitud del perfil: 2500 mm



pro-corner aluminium

pro-corner B				
KEA			h (mm)	P/UK
B78122001			25	17.76 p/u
B78122003			50	37.55 p/u

Profile length: 2500 mm


pro-corner angled				
KEA			h (mm)	P/UK
B78122005			20	13.17 p/u
B78122006			25	14.18 p/u
B78122008			40	23.81 p/u

Profile length: 3000 mm

XLIGHT Profiles


Corner profiles for wall tiles less than 6 mm thick. Specially recommended for mosaics and large format and thin ceramic slabs, such as XLIGHT.

Available in different shapes, from right-angled profiles for straight trims to rounded shape profiles. Decorative use.




pro-mate 2

KEA		h (mm)	P/UK
B71342617	V2A stainless steel	6	20.47 p/u




pro-mate 3

KEA		h (mm)	P/UK
B71342608	chrome	6	42.31 p/u
B71342616	silver anodized	6	9.53 p/u
B71342609	white lacquer	6	12.03 p/u




pro-mate 5

KEA		h (mm)	P/UK
B71342611	XLIGHT	7	49.32 p/u




pro-part

KEA		h (mm)	P/UK
B73134001	chrome	7	47.86 p/u
B73122001	silver anodized	7	11.33 p/u



pro-part Li

KEA		h (mm)	a (mm)	P/UK
B71342618	chrome	4.5	5.5	56.07 p/u
B71342619	silver anod	4.5	5.5	12.55 p/u



pro-mate 45 TOP

KEA		h (mm)	P/UK
B71342614	chrome	6	51.05 p/u
B71342612	silver anodized	6	16.62 p/u



pro-mate 45

KEA		h (mm)	P/UK
B71342615	chrome	6	53.64 p/u
B71342607	silver anodized	6	10.47 p/u
B71342610	white lacquer	6	12.98 p/u
B71342613	V2A stainless steel	6	23.73 p/u







Technical profiles

pro-T

Profile for transitions between floor coverings.

Profiles for transitions between tiles or slabs with slightly different heights. Available in two widths: 14 and 25 mm

Specially recommended for transitions between ceramic tiles and wooden floors.



pro-T

Chromed brass		
KEA	h (mm)	P/UK
B75133401	14	32.35 p/u
B75133402	25	39.48 p/u

Gloss stainless steel		
KEA	h (mm)	P/UK
B75141003	14	32.35 p/u
B75141004	25	41.04 p/u

Anodized aluminium silver		
KEA	h (mm)	P/UK
B75122001	14	5.87 p/u
B75122002	25	10.73 p/u



Gloss polished brass		
KEA	h (mm)	P/UK
B75132001	14	19.21 p/u
B75132002	25	29.15 p/u

Brushed stainless steel		
KEA	h (mm)	P/UK
B75141005	14	38.17 p/u
B75141006	25	49.19 p/u

pro-level

Transition profile between floor coverings at different levels. It covers the non-glazed edge of the tile and protects it from shocks.

Technical profiles for small height differences between floor coverings. Available in rounded finish and sloped finish. Specially recommended for high transit floors.



pro-level C

Anodized aluminium silver		
KEA	h (mm)	P/UK
B74122001	9	12.16 p/u
B74122002	11	14.16 p/u
B74122003	12.5	18.93 p/u

Gloss polished brass		
KEA	h (mm)	P/UK
B74132004	9	48.29 p/u
B74132006	12.5	51.13 p/u



pro-level R

Anodized aluminium silver		
KEA	h (mm)	P/UK
B74122004	11	38.86 p/u
B74122005	12.5	42.71 p/u
B74122006	15	45.95 p/u
B74122007	20	61.81 p/u



pro-level M


Anodized aluminium		
KEA	h (mm)	P/UK
B74132007	11	19.66 p/u



pro-shower

New range of profiles for shower trays. Designed to cover the sides of shower trays; specially for shower with only one direction slope. There are also special trims for installing glass screens.

These profiles are made of stainless steel and are available in two different finishings: gloss and brushed.



pro-shower floor

Chromed stainless steel

KEA	SAP		h (mm)	L (m)	P/UK
B77199022	100159068	Left side	12,5	0,98	61.48 p/u
B77199038	100160219	Right side	12,5	0,98	59.16 p/u
B77199025	100159069	Left side	12,5	1,48	97.09 p/u
B77199044	100160280	Right side	12,5	1,48	93.44 p/u

Brushed stainless steel

KEA	SAP		h (mm)	L (m)	P/UK
B77199021	100159066	Left side	12,5	0,98	52.53 p/u
B77199041	100160217	Right side	12,5	0,98	50.55 p/u
B77199020	100159067	Left side	12,5	1,48	80.82 p/u
B77199040	100160218	Right side	12,5	1,48	77.79 p/u

pro-shower wall

Chromed stainless steel

KEA	SAP		h (mm)	L (m)	P/UK
B77199033	100159089	Left side	12,5	0,98	61.48 p/u
B77199036	100160247	Right side	12,5	0,98	59.16 p/u
B77199034	100159100	Left side	12,5	1,48	97.09 p/u
B77199037	100160248	Right side	12,5	1,48	93.44 p/u

Brushed stainless steel

KEA	SAP		h (mm)	L (m)	P/UK
B77199031	100159087	Left side	12,5	0,98	52.53 p/u
B77199042	100160285	Right side	12,5	0,98	50.55 p/u
B77199032	100159088	Left side	12,5	1,48	80.82 p/u
B77199035	100160246	Right side	12,5	1,48	77.79 p/u

pro-shower glass

Chromed stainless steel

KEA	SAP		h (mm)	L (m)	P/UK
B77199028	100159092	Left side	12,5	0,98	114.32 p/u
B77199039	100160283	Right side	12,5	0,98	110.02 p/u
B77199023	100159093	Left side	12,5	1,48	161.77 p/u
B77199045	100160284	Right side	12,5	1,48	155.68 p/u
B77199027	100159095	Front side		2,10	242.80 p/u



Brushed stainless steel

KEA	SAP		h (mm)	L (m)	P/UK
B77199026	100159090	Left side	12,5	34	102.40 p/u
B77199043	100160281	Right side	12,5	34	98.54 p/u
B77199024	100159091	Left side	12,5	42	143.12 p/u
B77199046	100160282	Right side	12,5	42	137.72 p/u
B77199029	100159094	Front side		2,10	220.01 p/u

pro-balcony

Profiles for edging ceramic tile floors in terraces, balconies and other outdoor flooring. They protect the tile edges and avoid water filtrations both in floors and façades.

They have been designed to be used with lamitech n, the butech outdoor waterproofing and decoupling membrane. It also can be used as coping in bonded façades



pro-balcony P

Anodized aluminum

KEA	SAP		h (mm)	P/UK
B79241146	100159112	Profile	11	36.03 p/u
B79241153	100159114	Outer corner	11	35.62 p/u
B79241152	100159116	Vertical inner corner	11	35.78 p/u
B79241151	100159113	Horizontal outer corner	11	13.60 p/u
B79241147	100159115	Vertical outer corner	11	16.51 p/u

pro-balcony G

Anodized aluminum

KEA	SAP		h (mm)	P/UK
B79241145	100159110	Profile	10,5	89.05 p/u
B79241148	100159111	corner	10,5	44.52 p/u

pro-balcony R



Anodized aluminum

KEA	SAP		h (mm)	P/UK
B79241150	100159117	Profile	12,5	82.57 p/u
B79241149	100159119	corner 90°	12,5	43.71 p/u
B79241154	100159118	corner 135°	12,5	52.21 p/u

pro-dilata

Profile for movement joints in ceramic floor coverings.

PVC or metal profiles with a central elastic joint for the absorption of tensions in the ceramic floor. Available in several colours and joint widths, they are the best solution for creating intermediate movement joints.



pro-dilata CFC

CFC 8 mm

KEA		h (mm)	P/UK
B79211037	Grey	8	5.20 p/u
B79211041	Grey	10	5.61 p/u
B79211045	Grey	12.5	5.81 p/u
B79211049	Grey	15	6.41 p/u

pro-dilata CFL

CFL 8 mm

KEA		h (mm)	P/UK
B79211058	White	12.5	11.41 p/u
B79211055	Beige	10	10.82 p/u
B79211059	Beige	12.5	11.41 p/u
B79211063	Beige	15	12.22 p/u
B79211056	Negro	10	10.82 p/u
B79211060	Negro	12.5	11.41 p/u
B79211064	Negro	15	12.22 p/u
B79211057	Grey	10	10.82 p/u
B79211061	Grey	12.5	11.41 p/u
B79211065	Grey	15	12.22 p/u


CFL 5 mm

KEA		h (mm)	P/UK
B79211067	Grey	10	9.41 p/u
B79211068	Grey	12.5	9.81 p/u

pro-dilata CFI

PVC 5 mm


KEA		h (mm)	P/UK
B79241142	light grey	11	10.12 p/u
B79241134	light grey	12.5	10.40 p/u
B79241143	grey	11	10.12 p/u
B79241136	grey	12.5	10.40 p/u
B79241135	Black	11	10.12 p/u
B79241133	Black	12.5	10.40 p/u
B79241144	ivory	11	10.12 p/u
B79241140	ivory	12.5	10.40 p/u



pro-dilata

New pro-dilata is a 5mm wide precast expansion joint for indoor ceramic floors.

Pro-dilata corner in a precast expansion joint for the perimeter of ceramic tile floors. It's only 5mm wide and specially designed for fitting with the skirting pieces.



pro-dilata CFP

PVC CFP 5 mm

KEA	SAP		h (mm)	P/UK
B79241137	100159071	light gray	10	13.68 p/u
B79241138	100159070	grey	10	13.68 p/u
B79241139	100159073	black	10	13.68 p/u
B79241141	100159072	beige	10	13.68 p/u

pro-dilata stainless steel





CFM 8 mm

KEA	h (mm)	P/UK
B79241089	8	53.21 p/u
B79241090	10	58.53 p/u
B79241091	12.5	63.40 p/u
B79241093	20	93.64 p/u
B79241094	25	89.70 p/u

pro-dilata aluminium

CFM 10 mm



KEA	h (mm)	P/UK
B79221071	12.5	37.09 p/u
B79221072	15	42.00 p/u
B79221074	20	48.49 p/u



Expansion joints


Profile for structural joints in ceramic floor coverings.

Metallic profiles with a central elastic joint that absorbs the structural movements of the support. Available with deformable polypropylene joint for pedestrian transit and moving metallic joint for wheeled transit.




structural joints BT

BT-40			
KEA		h (mm)	P/UK
B79241098	grey	18	89.72 p/m
B79241099	grey	40	107.67 p/m
B80106001	negro	18	89.72 p/m
B80106003	negro	40	107.67 p/m



structural joints AT

AT-75		
KEA	h (mm)	P/UK
B80106004	18	126.69 p/m
B79241105	35	129.39 p/m
B80106002	50	200.41 p/m




pro-dilata CK

CK Anodized aluminium		
KEA	A (mm)	P/UK
B79241126	50	46.13 p/ud
B79241122	60	55.37 p/ud
B79241123	70	58.57 p/ud

Corner pro-dilata CK


CK Anodized aluminium		
KEA	A (mm)	P/UK
B79241128	50	49.34 p/ud
B79241131	60	58.57 p/ud
B79241129	70	64.46 p/ud



pro-step

Profile for the making of stair steps. It substitutes the traditional step ceramic piece by a combination of ceramic tile and profile.

Metallic profiles that cover the non-glazed edge of the tile, protect it from shocks and reduce the risk of slipping.



pro-step

Chromed brass M1		
KEA	h (mm)	P/UK
B76334003	11	56.98 p/u

Stainless steel M2		
KEA	h (mm)	P/UK
B76341001	9	35.2 p/u
B76341002	11	38.6 p/u


Anodized aluminium silver M1		
KEA	h (mm)	P/UK
B76322001	7	14.99 p/u
B76322002	9	14.65 p/u
B76322003	11	15.42 p/u
B76342003	13.5	18.69 p/u

Gloss stainless steel M2		
KEA	h (mm)	P/UK
B76342002	11	45.81 p/u

pro-step

PVC 25			
KEA		h (mm)	P/UK
B76111026	White	11	21.81 p/u
B76111027	Beige	11	21.81 p/u
B76111028	Negro	11	21.81 p/u
B76111030	Grey	11	21.81 p/u



PVC 35			
KEA		h (mm)	P/UK
B76111011	White	11	27.96 p/u
B76111013	Negro	11	27.96 p/u
B76111014	marrón	11	27.96 p/u
B76111015	Grey	11	27.96 p/u



pro-flex

Flexible profiles for curve lines in floors.

Flexible profiles are available for installation in floor and wall tiles that form curves. They can be shaped with the **pro-curve** machine.



pro-flex



pro-mate 2 stainless steel V2A

KEA	h (mm)	P/UK
B71441002	10	21.00 p/u
B71441003	12.5	21.63 p/u

pro-mate 2 stainless steel gloss V2A

KEA	h (mm)	P/UK
B71442001	8	29.06 p/u
B71442002	10	30.12 p/u

pro-mate 3 anodized aluminium silver

KEA	h (mm)	P/UK
B71422001	8	9.51 p/u
B71422002	9	9.91 p/u
B71422003	10	10.12 p/u
B71422004	12.5	10.73 p/u
B71422005	15	11.75 p/u

pro-part gloss polished brass

KEA	h (mm)	P/UK
B73232003	11	44.65 p/u

pro-part anodized aluminium silver

KEA	h (mm)	P/UK
B73222001	7	13.15 p/u
B73222003	11	14.37 p/u
B73222004	12.5	15.59 p/u
B73222005	15	16.80 p/u
B73222006	20	18.01 p/u

pro-mate 45 anodized aluminium silver

KEA	h (mm)	P/UK
B71422106	10	11.94 p/u

pro-level C gloss polished brass

KEA	h (mm)	P/UK
B74232002	11	43.95 p/u

pro-part anodized aluminium gold

KEA	h (mm)	P/UK
B73222011	12.5	15.99 p/u

pro-mate 45 anodized aluminium gold

KEA	h (mm)	P/UK
B71422107	10	11.94 p/u
B71422112	12.5	12.96 p/u


pro-level flex anodized aluminium

KEA	h (mm)	P/UK
B74222002	11	16.20 p/u

pro-sanit

Concave profile for installation where walls and floors meet or between wall coverings and bathtubs, shower trays or other bath elements. It substitutes the traditional curve ceramic piece.

It reduces the risk of water leakage and eases cleaning and preservation of angles between floor and wall coverings.



pro-sanit U1

Aluminium gloss silver

KEA	h (mm)	P/UK
B77199014	16	23.73 p/u
B77199018	22	27.07 p/u

Lacquered aluminium

KEA		h (mm)	P/UK
B77199013	White	16	14.39 p/u
B77199016	White	22	18.00 p/u

PVC

KEA		h (mm)	P/UK
B77111005	White	9	5.49 p/u
B77111008	Marfil	9	5.49 p/u

pro-sanit U2

Stainless steel

KEA		h (mm)	P/UK
B77141001	gloss	12.5	38.38 p/u
B77142001	brushed	12.5	49.67 p/u

PVC

KEA		h (mm)	P/UK
B77111013	White	9	13.14 p/u
B77111017	White	11	14.54 p/u

pro-sanit S3

PVC

KEA		h (mm)	P/UK
B77111035	White	23	4.60 p/u

Anodized aluminium silver

KEA	h (mm)	P/UK
B77199017	16	10.25 p/u
B77199015	22	12.83 p/u

Stainless steel corner

KEA		h (mm)	P/UK
B77141501	Gloss Outer	12.5	7.21 p/u
B77141502	Gloss Inner	12.5	7.21 p/u
B77142501	Brushed outer	12.5	7.21 p/u
B77142502	Brushed internal	12.5	7.21 p/u


Side cap

KEA		h (mm)	P/UK
B77111038	White (4 u)	32	2.73 p/u

pro-plint

Metallic skirting for floor tile coverings.

Metallic profiles for skirtings. They have a high mechanical resistance with a functional, modern design. Specially recommended for office floors and raised access floors.



pro-plint stainless

Stainless steel

KEA		h (mm)	P/UK
B79141001	Gloss	80	30,04 p/u
B79141002	Brushed	80	35,32 p/u

pro-plint aluminium

Anodized aluminium

KEA		h (mm)	P/UK
B79141508	Silver	80	32,02 p/u

Special pieces

KEA		h (mm)	P/UK
B79141510	Profile joining piece	80	5,61 p/u
B79141511	Right trim	80	5,58 p/u
B79141512	Left trim	80	3,59 p/u

pro-plint aluminium R

Anodized aluminium

KEA		h (mm)	P/UK
B79123001	Base	80	36,94 p/u
B79123002	Top	80	20,97 p/u

pro-plint R consists of a base and a top profile.

Special pieces

KEA		h (mm)	P/UK
B79141507	Cap set	80	4,77 p/u

Includes right and left caps.



pro-plint corner

KEA		h (mm)	P/UK
B79141509	Inner	80	5,80 p/u
B79141513	Outer	80	4,80 p/u




pro-plint R corner

KEA		h (mm)	P/UK
B79141505	Outer	80	5,01 p/u
B79141506	Internal	80	5,01 p/u

pro-skirting

Metallic skirting for floor tile coverings.

Metal profiles in five finishes and straight trims. They replace traditional ceramic skirting. Specially recommended for shops and public buildings.



pro-skirting

Chromed aluminium

KEA	h (mm)	P/UK
B79141522	60	67,89 p/u

Profile length: 2500 mm

White lacquered aluminium

KEA	h (mm)	P/UK
B79141521	60	42,25 p/u

Profile length: 2500 mm

Anodized aluminium

KEA	h (mm)	P/UK
B79141527	60	41,61 p/u

Profile length: 2400 mm

graphite aluminium

KEA	SAP	h (mm)	P/EU
B71342627	100155326	60	80.20 p/u

Profile length: 2500 mm

Chromed aluminium corner

KEA	h (mm)	P/UK
B79141525	60	11,22 p/u

White lacquered aluminium corner


KEA	h (mm)	P/UK
B79141524	60	9,56 p/u

Anodized aluminium corner

KEA	h (mm)	P/UK
B79141526	60	8,04 p/u

graphite aluminium corner

KEA	SAP	h (mm)	P/EU
B71342626	100155327	60	10,29 p/u





Adhesives for ceramic tile fixing

Cement-based adhesives

one-flex n	75
super-one n	76
super-flex S2	77
tile to wood	78
porce-quick	79
rapimax	80

Dispersion adhesives

bt-2000 n	81
bt-3000 n	82

Reactive resins adhesive

politech n	83
------------	----

Additives for cement-based adhesives

unilax	84
--------	----

Façade fixings

concealed facade fixings	85
visible facade fixings	86

one-flex n

one-flex n, flexible floor and wall tile adhesive, is a cement-based, highly polymer modified, high strength, flexible tile adhesive available in white or grey. It is non-slip, water and frost-resistant and suitable for fixing a wide range of ceramic, vitrified, fully vitrified, porcelain and natural stone tiles and mosaics in interior and exterior situations. It provides enhanced adhesion to fully vitrified and porcelain tiles and to low porosity substrates.

Ideal for tiled areas which are subject to limited movement or vibration such as partition walling and plywood overlaid floors. **one-flex n** is suitable for use in dry or wet duty areas, such as bathrooms, showers and swimming pools.

The adhesive exceeds the requirements of BS EN 12004:2007 for a C2TE cement based adhesive, with improved performance, excellent non-slip properties and an extended open time.



☒

ston-ker

☒

glass mosaic

☒

large format

☒

plasterboard

☒

high traffic

☒

pools

one-flex n

Features:

- Cement-based, single component adhesive.
- Excellent adherence. Flexible.
- Fine texture mortar, with excellent mixing and application features.
- High initial adherence and no sagging.
- Extended working times. Open time higher than 30 min.
- Application thickness up to 6 mm.
- Frost-resistant.

Mixing water: 5,5 l per 20 Kg bag

Coverage:

• 20 x 30 cm tile	3 kg / m²
• 30 x 30 cm tile	3 kg / m²
• 30 x 60 cm tile	4 kg / m²
• 44 x 44 cm tile	4 kg / m²
• 30 x 90 cm tile	5 kg / m²
• 44 x 66 cm tile	5 kg / m²
• 60 x 60 cm tile	6 kg / m²
• 60 x 120 cm tile	6 kg / m²

Materials:

- Large format ceramics.
- Porcelain tiles with a water absorption < 0.5% as per EN-ISO 10545-3.
- Glass mosaic.
- Natural stone and marble not prone to staining.

Certifications/Standards:

BS EN 12004:2007 C2 TE

one-flex n

KEA		P/UK
B00000002	one-flex n white	24.70 p/bag
B00000001	one-flex n grey	20.50 p/bag

Recommended uses:

- Indoor large format ceramic tile coverings.
- Indoor and outdoor porcelain tile coverings.
- Floor tiles on radiant heating.
- Pools and damp environments.
- On bonded facades, replace mixing water with **unilax** additive.
- Especially recommended for meshed glass mosaics from L'ANTIC COLONIAL in dry areas.

Suitable surfaces:

Walls

- Sand:cement renderings
- Concrete
- Lightweight blocks
- Brickwork, dense concrete blockwork and stonework
- Plasterboard, moisture resistant plasterboard, tilebacker boards
- Gypsum plaster primed with **universal bonding agent**
- Glazed bricks and tiles primed with **universal bonding agent**
- External tiling

Floors

- Concrete
- Sand: cement screeds
- Anhydrite / hemi-hydrate screeds primed with **universal bonding agent**
- Heated sand:cement screeds
- Plywood overlay primed with **universal bonding agent**
- Existing floor tiles*.
- Flooring grade asphalt – internal use primed with **universal bonding agent**
- Vinyl tiles primed with **universal bonding agent**

Packaging

Presentation	Europallet
20 kg bag	48 bags/pallet
20 kg bag	48 bags/pallet



* **super-prim** improves the adherence on polished ceramics and glossy finishing tiles

Before using this product in any application not indicated in this catalogue, please perform a test or refer to the product's technical sheet.at

super-one n

super-one n is a type C2 FTE S1 high-performance cement-based adhesive, as per EN 12004, ready for traffic after 4 hours. Specially recommended for quick installation and use of ceramic tiles and natural stone.

It solves the need of quick installation of any kind of format and ceramic tile, including porcelain tiles. Ready for traffic in just 4 hours, this adhesive can be used to lay ceramic tiles and natural stone in environments where high mechanical performance is needed, such as commercial or industrial flooring or flooring with radiant heating. Waterproof and frost-resistant.



☒

ston-ker

☒

natural stone

☒

large format

☒

plasterboard

☒

plywood

☒

tiles existing

super-one n

Features:

- Cement-based, single component adhesive.
- Ready for traffic in just 4 hours.
- Excellent adherence. Flexible.
- Fine texture mortar, with excellent mixing and application features.
- High initial adherence and no sagging.
- Extended working times. Open time higher than 30 min.
- Application thickness up to 10 mm.
- Frost-resistant.
- Mixing water: 6.0 - 6.50 l per 25 kg bag

Coverage:

• 20 x 30 cm tile	3 kg / m²
• 30 x 30 cm tile	3 kg / m²
• 30 x 60 cm tile	4 kg / m²
• 44 x 44 cm tile	4 kg / m²
• 30 x 90 cm tile	5 kg / m²
• 44 x 66 cm tile	5 kg / m²
• 60 x 60 cm tile	6 kg / m²
• 60 x 120 cm tile	6 kg / m²

Certifications/Standards:

BS EN 12004 C2 FTE S1

super-one n

KEA		P/UK
B12909010	super-one n white	27,71 p/bag
B12909011	super-one n grey	19,13 p/bag

* **super-prim** improves the adherence on polished ceramics and glossy finishing tiles

Recommended uses:

- Laying of ceramics in refurbishing jobs.
- Indoor large format ceramic tile coverings.
- Indoor and outdoor porcelain tile coverings.
- Plywood substrates.
- High traffic floor tiles.
- Floor tiles on radiant heating.
- Pools and damp environments.
- On bonded facades, replace mixing water with **unilax** additive.
- Especially recommended for white marble tiles from L'ANTIC COLONIAL

Materials:

- Large format ceramics.
- Porcelain tiles with a water absorption < 0.5% as per EN-ISO 10545-3.
- Glass mosaic.
- Natural stones and marble without risk of deformation by water absorption.
- In installations of DQS slabs and other kinds of marble agglomerate, mix with **unilax** latex.

Suitable surfaces:

- Cement covered floors and walls .
- Concrete slabs.
- Plasterboards.
- WBP plywood boards.
- On **fonopac r** replace mixing water with **fonolax**.
- Existing wall tiles*.
- On anhydrite or plaster substrates apply **universal bonding agent**.

Packaging

Presentation	Europallet
25 kg bag	1,000 kg/pallet
25 kg bag	1,000 kg/pallet



Before using this product in any application not indicated in this catalogue, please perform a test or refer to the product's technical sheet.at

super-flex S2

super-flex S2 is a type C2 TE S2 high-performance no dust cement-based adhesive, as per EN 12004, for laying all kinds of ceramic tiles on the most used substrates in the building industry. Specially recommended for laying large format, thin porcelain tiles like XLIGHT from URBATEK.

This adhesive features excellent performance in adherence and deformability with no need for mixing with additives and excellent conditions of use: low dust generation and an only 15 kg package. This state-of-the-art adhesive includes additives and polymers which increase performance. This means that with a 15 kg bag of super-flex S2 you can lay the same tiles surface than with a 25 kg bag of regular adhesive.



- ☒ston-ker
- ☒XLIGHT
- ☒glass mosaic
- ☒large format
- ☒existing ceramics
- ☒high traffic

super-flex S2

Features:

- Cement-based, single component adhesive.
- Lightened adhesive. Low consumption onsite.
- Low emission of dust and other airborne particles.
- Maximum adherence and deformability.
- High initial adherence and no sagging. Thixotropic.
- Extended working times. Open time higher than 30 min.
- Application thickness up to 10 mm.
- Frost-resistant.
- Mixing water: 8 l per 15 kg bag

Recommended uses:

- Indoor coverings with ceramic sheets like XLIGHT.
- Laying of ceramics in refurbishing jobs.
- Indoor large format ceramic tile coverings.
- Indoor and outdoor porcelain tile coverings.
- High traffic floor tiles.
- Floor tiles on radiant heating.
- Pools and damp environments.
- Especially recommended for XLIGHT tiles from URBATEK.
- Suitable for DQS from L'ANTIC COLONIAL in areas not exposed to direct sunlight.

Coverage:

• 20 x 30 cm tile	2.00 kg / m²
• 30 x 30 cm tile	2.00 kg / m²
• 30 x 60 cm tile	2.50 kg / m²
• 44 x 44 cm tile	2.50 kg / m²
• 30 x 90 cm tile	3.00 kg / m²
• 44 x 66 cm tile	3.00 kg / m²
• 60 x 60 cm tile	3.50 kg / m²
• 60 x 120 cm tile	3.50 kg / m²
• 100 x 100 cm tile	3.50 kg / m²
• 100 x 300 cm tile	3.50 kg / m²

Certifications/Standards:

EN 12004 C2 TE S2

super-flex S2

KEA			P/UK
B12909017	100142757	super-flex S2 white	2.33 p/kg

Materials:

- Large format ceramics.
- Porcelain tiles (water absorption < 0.5% as per EN-ISO 10545-3).
- Large format, thin porcelain tiles like XLIGHT.
- Glass mosaic.
- Natural stone and marble not prone to staining.
- DQS slabs and other kinds of marble agglomerate.

Suitable surfaces:

- Cement covered floors and walls .
- Concrete slabs.
- Plasterboards.
- Existing wall tiles*.
- On anhydrite or plaster substrates apply primed with **universal bonding agent**.

Packaging

Presentation	Europallet
15 kg bag	600 kg/pallet



* **super-prim** improves the adherence on polished ceramics and glossy finishing tiles

Before using this product in any application not indicated in this catalogue, please perform a test or refer to the product's technical sheet.at

tile to wood

tile to wood, highly flexible floor tile adhesive, is a grey cement-based, fast setting highly polymer modified tile adhesive specially designed for use on timber floors. It is suitable for fixing a wide range of ceramic, vitrified, fully vitrified, porcelain and dark natural stone tiles and mosaics in interior situations. It provides enhanced adhesion to fully vitrified and porcelain tiles and to low porosity substrates.

Ideal for tiling to timber substrates which are subject to limited movement or vibration such as floating floors. **tile to wood** is suitable for use in bathrooms, kitchens, utility rooms etc.

The adhesive exceeds the requirements of BS EN 12004:2007 for a C2FTS2 highly deformable, fast setting cement-based adhesive, with improved performance and excellent non-slip properties.



- ☒ston-ker
- ☒natural stone
- ☒large format
- ☒flexible
- ☒timber floors
- ☒ceramics existing

tile to wood

Features:

- Cement-based, two component adhesive.
- Ready for traffic in just 3 hours.
- Excellent adherence. Flexible.
- Fine texture mortar, with excellent mixing and application features.
- High initial adherence and no sagging.
- Extended working times. Open time higher than 30 min.
- Application thickness up to 10 mm.
- Frost-resistant.

Coverage:

• 20 x 30 cm tile	3 kg / m²
• 30 x 30 cm tile	3 kg / m²
• 30 x 60 cm tile	4 kg / m²
• 44 x 44 cm tile	4 kg / m²
• 30 x 90 cm tile	5 kg / m²
• 44 x 66 cm tile	5 kg / m²
• 60 x 60 cm tile	6 kg / m²
• 60 x 120 cm tile	6 kg / m²

Certifications/Standards:

BS EN 12004:2007 C2 FT S2

tile to wood

KEA		P/UK
B00000006	tile to wood white	38.10 p/tub

Recommended uses:

- Laying of ceramics in refurbishing jobs.
- Indoor large format ceramic tile coverings.
- Indoor and outdoor porcelain tile coverings.
- Plywood substrates.
- High traffic floor tiles.
- Floor tiles on radiant heating.
- Pools and damp environments.

Materials:

- Large format ceramics.
- Porcelain tiles with a water absorption < 0.5% as per EN-ISO 10545-3.
- Glass mosaic.
- Natural stones and marble without risk of deformation by water absorption.

Suitable surfaces:

Floors

- Plywood overlay
- Chipboard / timber floorboards
- Concrete
- Sand:cement screeds
- Anhydrite / hemi-hydrate screeds
- Heated sand:cement screeds
- Existing floor tiles
- Flooring grade asphalt – internal use
- Vinyl tiles

Packaging

Presentation	Europallet
6.5 kg tub	312 kg/pallet




Before using this product in any application not indicated in this catalogue, please perform a test or refer to the product's technical sheet.at

porce-quick

porce-quick is a new rapid set flexible cement-based adhesive, class C2 FT as per EN 12004. Ready for traffic after 3 hours, specially recommended for quick installation and use of ceramic tiles and natural stone.

It solves the need of quick installation of any size of ceramic tile, including porcelain tiles. Ready for traffic in just 3 hours, this adhesive can be used to lay ceramic tiles and natural stone in installations where high mechanical performance is needed, such as commercial or industrial flooring or flooring with radiant heating. Waterproof and frost-resistant.



porce-quick

Features:

- Cement-based, single component adhesive.
- Setting in 3 hours
- Excellent adherence. Flexible adhesive.
- Non-slipping adhesive.
- Application thickness up to 12 mm.
- Frost-resistant.
- Mixing water: 4,2 - 4,6 l per 20 kg bag

Recommended uses:

- Kitchen and bathrooms walls.
- Domestic showers walls.
- Indoor and outdoor floors.
- High traffic floors.
- Under floor heating floors.
- Exteriors or areas subject to immersion such as swimming pools.
- On bonded facades, replace mixing water with **unilax** additive.

Coverage:

• 20 x 30 cm tile	3 kg / m²
• 30 x 30 cm tile	3 kg / m²
• 30 x 60 cm tile	4 kg / m²
• 44 x 44 cm tile	4 kg / m²
• 30 x 90 cm tile	5 kg / m²
• 44 x 66 cm tile	5 kg / m²
• 60 x 60 cm tile	6 kg / m²
• 60 x 120 cm tile	6 kg / m²

Materials:

- Large size ceramic tiles
- Porcelain tiles with a water absorption < 0.5% as per EN-ISO 10545-3.
- Glass mosaic.
- Natural stone and marble not prone to staining.

Certifications/Standards:

EN 12004 C2 FT

porce-quick

KEA		P/UK
B91010000	porce-quick grey	12.56 p/bag

Suitable surfaces:

Walls

- Sand : cement renders
- Brickwork, dense concrete blockwork and stonework
- Plasterboard, moisture resistant plasterboard
- Tile backer boards and waterproof composite boards
- Plywood

Floors

- Sand : cement screeds
- Heated sand:cement screeds
- Concrete
- WBP plywood
- Existing floor tiles

- On anhydrite or plaster substrates apply **universal bonding agent**.

Packaging

Presentation	Europallet
20 kg bag	56 bags/pallet




rapimax n

rapimax n, high tech pourable large format floor tile adhesive, is a grey cement-based, highly polymer modified, high strength, tile adhesive. Its special formula was specifically designed for use with large format tiles permitting full contact to be achieved without the additional need to butter the backs of tiles. **rapimax n** is water and frostresistant and suitable for fixing a wide range of ceramic, vitrified, fully vitrified, porcelain and natural stone tiles in interior and exterior situations.

rapimax n is suitable for use in dry or wet duty areas, such as kitchens, bathrooms, conservatories, showers, balconies and terraces.

The adhesive exceeds the requirements of BS EN 12004:2007 for a C2F rapid setting cement based adhesive, with improved performance.



rapimax n

Features:

- Cement-based, single component adhesive.
- A fluid mortar, applicable with a notched trowel, that under the tile pressure, flows and covers the whole back of the tile.
- Excellent adherence.
- Extended working times. Open time higher than 30 min.
- Application thickness up to 25 mm.
- Frost-resistant.
- Mixing water: 3,6 - 4,0 l per 20 kg bag

Recommended uses:

- Indoor and outdoor porcelain tile coverings.
- Large format porcelain floors.
- High traffic floor tiles.
- Floor tiles with radiant heating.
- Laying of tiles on glazed floor tiles.
- Never use in walls.

Coverage:

• 30 x 30 cm tile	4 kg / m²
• 44 x 44 cm tile	5 kg / m²
• 44 x 66 cm tile	5 kg / m²
• 60 x 60 cm tile	6 kg / m²
• 60 x 120 cm tile	6 kg / m²

Certifications/Standards:

EN 12004 C2F

rapimax n

KEA		P/UK
B00000005	rapimax n grey	23.20 p/bag

Materials:

- Large format ceramics.
- Porcelain tiles with a water absorption < 0.5% as per EN-ISO 10545-3.
- Clay and terracotta.
- Natural stone and marble not prone to staining.

Suitable surfaces:

Floors

- Concrete
- Sand:cement screeds
- Anhydrite / hemi-hydrate screeds
- Heated sand:cement screeds
- Existing floor tiles*.
- Vinyl tiles

Packaging

Presentation	Europallet
20 kg bag	48 bags/pallet




* **super-prim** improves the adherence on polished ceramics and glossy finishing tiles

bt-2000 n

bt-2000 n is a ready mixed acrylic wall tile adhesive. Suitable for use as a thin-bed ceramic tile adhesive and conforms to EN 12004 Type D, Class 1 TE.

Suitable for fixing all types of ceramic wall tiles, including mosaics, porcelain and vitrified tiles in internal locations such as bathrooms, kitchens and domestic shower areas. bt-2000 n can be applied to gypsum plaster, plasterboards, cement fibre boards, existing tiles, cement renders, concrete, blockwork, timber panels and plywood composite boards.

bt-2000 n acrylic based formula also gives outstanding non-slip and high grab properties. It is also mould resistant, suitable for intermittently wet conditions as such domestic showers, kitchens and bathrooms.



bt-2000 n

Features:

- Ready-to-use dispersion adhesive.
- Excellent adherence. Flexible.
- Shower proof.
- Non slip. High initial adherence and no sagging.
- Mould resistant.
- Fine texture adhesive, with excellent mixing and application features.
- Extended working times. Open time higher than 20 min.
- Application thickness up to 3 mm.

Recommended uses:

- Wall tiling on kitchen and bathrooms.
- Wall tiling on domestic showers.
- Wall tiling on dry partition walls: plasterboard and tile backer boards.
- Wall tiling on plaster and cement renders.
- Indoor decoration with ceramics: bath or kitchen countertops.
- Do not use in exteriors or areas subject to immersion such as swimming pools.
- Never use for floor tiles.

Coverage:

• 20 x 20 cm tile	3 kg / m ²
• 20 x 30 cm tile	3 kg / m ²
• 30 x 60 cm tile	4 kg / m ²

Materials:

- Standard format ceramic wall tiles.
- Porcelain mosaics (water absorption < 0.5% as per EN-ISO 10545-3).
- Glass mosaic.
- Natural stone and marble not prone to staining.
- Isolating panels:
 - EPS panels.
 - PS panels.
 - Mineral wool panels.

Certifications/Standards:

EN 12004 D1 TE

bt-2000 n

KEA		P/UK
B00100006	bt-2000 n	11.95 p/tub

Suitable surfaces:

Walls

- Plaster (gypsum plaster)
- Sand: cement renderings
- Brickwork and concrete
- Plasterboard, moisture resistant plasterboard
- Fibre reinforced cement sheets
- Tile backer boards
- Existing ceramic tiles*

Packaging

Presentation	Europallet
10 l tub / 15 kg tub	44 tubs/pallet



* Existing wall tiles, provided the new tile has a water absorption >10% as per EN-ISO 10545-3.


Before using this product in any application not indicated in this catalogue, please perform a test or refer to the product's technical sheet.at

bt-3000 n

bt-3000 n, ceramic wall tile adhesive, is a high performance ready-mixed water resistant high grab, non-slip wall tile adhesive. It is suitable for fixing a wide range of porous ceramic wall tiles and mosaics in interior situations.

bt-3000 n is suitable for use in dry and wet duty areas in bathrooms, showers, kitchens, utility rooms etc.

The adhesive exceeds the requirements of BS EN 12004:2007 for a D2T water resistant dispersion based.



bt-3000 n

Features:

- Ready-to-use dispersion adhesive.
- Excellent adherence. Flexible.
- Resistant to dampness-
- Fine texture adhesive, with excellent mixing and application features.
- High initial adherence and no sagging.
- Extended working times. Open time higher than 30 min.
- Application thickness up to 4 mm.

Recommended uses:

- Wall tile on dry partition wall: plasterboard.
- Wall tile on plaster.
- Indoor ceramic tile coverings.
- Indoor wall tiles in permanently damp environments.
- Indoor decoration with ceramics: bath or kitchen countertops.
- Never use for floor tiles.

Coverage:

• 20 x 20 cm tile	3 kg / m ²
• 20 x 30 cm tile	3 kg / m ²
• 30 x 60 cm tile	4 kg / m ²

Materials:

- Medium and small format ceramic tiles or slabs.
- Small format porcelain tiles (water absorption < 0.5% as per EN-ISO 10545-3).
- Glass mosaic.
- Isolating panels:
 - EPS panels.
 - PS panels.
 - Mineral wool panels.

Certifications/Standards:

EN 12004 D2 T

bt-3000 n

KEA		P/UK
B00100001	bt-3000 n	21.50 p/tub

Suitable surfaces:

Walls

- Sand:cement renderings
- Concrete
- Plasterboard, moisture resistant plasterboard, tilebacker boards
- Gypsum plaster
- Glazed bricks and tiles

Packaging

Presentation	Europallet
10 l tub / 15 kg tub	48 tubs per pallet



* Existing wall tiles, provided the new tile has a water absorption >10% as per EN-ISO 10545-3. **super-prim** improves the adherence on polished ceramics and glossy finishing tiles

Before using this product in any application not indicated in this catalogue, please perform a test or refer to the product's technical sheet.at

politech n

politech is a type R2 T high-tech, two-component polyurethane adhesive as per EN 12004, for laying tiles on deformable substrates. Specially recommended for special substrates like metal sheets or synthetic materials, where cement-based adhesives cannot be used.

A high-tech two-component polyurethane adhesive with high performance properties. Suitable for laying ceramic tiles of all kinds on deformable substrates.



politech n

Features:

- Two-component polyurethane adhesive.
- Excellent adherence. Maximum deformability.
- No water absorption. Waterproof.
- High chemical resistance.
- High initial adherence and no sagging.
- Application thickness up to 8 mm.
- Frost-resistant.

Recommended uses:

- Laying of wall tiles not compatible with cement-based adhesives.
- Wall tiles on substrates not compatible with cement-based adhesives.
- Floor tiles on deformable substrates.
- Floor tiles with special chemical resistance.
- Laying of slate and other natural stones with risk of deformation by water absorption.
- Substrate waterproofing.
- Suitable for AIRSLATE from L'ANTIC COLONIAL in interiors
- Especially recommended for DQS from L'ANTIC COLONIAL.
- Especially recommended for LINKFLOOR from L'ANTIC COLONIAL.
- Especially recommended for KRION.

Coverage:

• 20 x 30 cm tile	3 kg / m²
• 30 x 30 cm tile	3 kg / m²
• 30 x 60 cm tile	4 kg / m²
• 44 x 44 cm tile	4 kg / m²

Materials:

- Large format ceramics.
- Porcelain tiles with a water absorption < 0.5% as per EN-ISO 10545-3.
- Glass mosaic.
- Natural stone and marble not prone to staining.
- DQS slabs and other kinds of marble agglomerate.
- Krypton slabs and other kinds of Solid Surface.

Suitable surfaces

- Concrete or mortar substrates.
- Plasterboards and plaster or anhydrite walls.
- Plasterboards/wood boards.
- Existing wall tiles*.
- Metal sheets.
- Polyester or PVC surfaces.

Packaging

Presentation	Europallet
12 kg can	576 kg/pallet



politech n

KEA		P/UK
B41061005	politech n blanco	7.08 p/can


* **super-prim** improves the adherence on polished ceramics and glossy finishing tiles

Before using this product in any application not indicated in this catalogue, please perform a test or refer to the product's technical sheet.at

unilax

unilax is a latex that, mixed with cement-based adhesives like **one-flex n**, **fr-one n** or **super one n**, **rapimax n** or **maxifluid** improves bonding strength and flexibility up to level C2 S2 as per EN 12004. Specially recommended for laying wall tiles outdoors.

A resin-based latex that can be added to cement-based adhesives to enhance their bonding strength and flexibility. Specially recommended for exterior facades.



unilax

Features:

- Water-based acrylic resins latex.
- Resistant to the most common chemicals.
- Excellent resistance to UV rays and the effect of heat.
- Frost-resistant.

Recommended uses:

- Laying of tiles in facades.
- Large format ceramic floor tiles on radiant heating.
- Indoor large format ceramic tile coverings on slightly deformable substrates.
- Indoor and outdoor porcelain tile coverings.
- High traffic floor tiles.
- Pools and damp environments.

Coverage:

Product	%	litres	Kg/bag
one flex n white	34%	8.25–8.75	25
one flex n grey	32%	7.75-8.25	25
fr-one n	30%	7.25-7.75	25
super-one n	25%	6.00-6.50	25
rapimax n	21%	5.00-5.50	25
maxifluid	21%	5.00-5.50	25

Materials:

- Large format ceramics.
- Porcelain tiles with a water absorption < 0.5% as per EN-ISO 10545-3.
- Glass mosaic.
- Natural stone and marble not prone to staining.
- DQS slabs and other kinds of marble agglomerate.

Suitable surfaces:

- Concrete or mortar substrates.
- Plasterboards.
- Plywood panels.
- Existing wall tiles*.

unilax

KEA		P/UK
B51601002	unilax	53.76 p/can
B51602002	unilax	15.37 p/can

Packaging

Presentation	Europallet
20 kg can	560 kg/pallet
5 kg can	480 kg/pallet



* **super-prim** improves the adherence on polished ceramics and glossy finishing tiles


Before using this product in any application not indicated in this catalogue, please perform a test or refer to the product's technical sheet.at

concealed facade fixings

Innovative concealed fixing clip for ceramic tiles in **bonded facades**. The fixings fit within small slots done on the porcelain piece and are **anchored** to the support by a stainless steel screw. Once the joints are grouted, the fixings are not visible anymore, not affecting the facade design.

These fixings have been designed as a security element in porcelain tile walls installed by the thin layer, double bonding method. We recommend the use of type C2 S2 cement-based adhesives as per EN 12004.

As a general rule, we recommend this kind of fixing from a height corresponding to first concrete slab. In any case, standards in force must be observed for every project.



concealed facade fixings

Features:

- 1.4301 (AISI 304 V2A) stainless steel clips.
- Suitable for 5 - 7 mm wide joints.
- Suitable for tiles 9 to 12 mm thick.
- Start fixings available in 80 and 160 mm lengths for overhanging installations.
- Includes stainless steel screw and plug.

Coverage:

Coverage changes with every facade design. In the case of a regular facade with no gaps, clip calculation would be the following:

Tile	Type I fixings	Type A/T fixings
cm	u/m ²	u/m ²
43.5 x 65.9	5.6	1.4
44 x 66	5.5	1.4
60 x 60	4.5	1.1
45 x 90	4.0	1.0
60 x 120	3.4	0.8

Additional materials:

fr-one grey n	6.00 – 7.00 kg/m ²
unilax	1,80 – 2,45 l/m ²
unicem	1.25 – 1.75 kg/m ²

concealed facade fixings

KEA	concealed fixing	P/UK
B80111001	minimum I joint	1.24 p/piece

KEA	concealed fixing	P/UK
B80111002	minimum A/T joint 4 cm	1.24 p/piece
B80111003	minimum A/T joint 8cm	1.40 p/piece
B80400012	minimum A/T joint 16cm	4.24 p/piece

Recommended uses:

- Laying of tiles in facades.
- Laying of ceramics in ceilings and cornices.
- Indoor laying of large format porcelain tiles at a certain height.

Materials:

- Medium and large format porcelain tiles resistant to side slotting:
 - STON-KER
 - PAR-KER
 - URBATEK


Suitable surfaces:

- Cement covered floors and walls .
- In outdoor cement screeds, we recommend to add **unicem**:
150 gr **unicem** / m² and milimeter of screed thickness

Packaging

Presentation
50 u. bag

Presentation
50 u. bag
50 u. bag
50 u. bag




visible facade fixings

Visible fixing clip for ceramic tiles in **bonded facades**. Fixings hold the ceramic tiles and are anchored to the support by a stainless steel screw. Once the joints are grouted, the fixings are visible, and a 5 mm clip can be seen.

These fixings have been designed as a security element in porcelain tile walls installed by the thin layer, double bonding method. We recommend the use of type C2 S2 cement-based adhesives as per EN 12004.

As a general rule, we recommend this kind of fixing from a height corresponding to first concrete slab. In any case, standards in force must be observed for every project.



visible facade fixings

Features:

- 1.4301 (AISI 304 V2A) stainless steel clips.
- Suitable for 12 mm wide joints.
- Suitable for tiles 10 to 12 mm thick.
- Available in metallic or lacquered finish.
- Customizable colour lacquering on demand.
- Includes stainless steel screw and plug.

Coverage:

Coverage changes with every facade design. In the case of a 5 x 20 m regular facade with no gaps, clip calculation would be the following:

Tile	100 fixing	1100 fixing	1200 fixing	1500 fixing
cm	u/m ²	u/m ²	u/m ²	u/m ²
43.5 x 65.9	0.04	0.58	0.22	3.19
44 x 66	0.04	0.58	0.22	3.19
60 x 60	0.04	0.64	0.16	2.56
45 x 90	0.04	0.42	0.20	2.10
60 x 120	0.38	0.32	1.52	1.28

Additional materials:

fr-one grey n	6.00 – 7.00 kg/m ²
unilax	1,80 – 2,10 l/m ²
unicem	1,80 – 2,15 kg/m ²

visible facade fixings

KEA	fixing clip stainless	P/UK
B80107010	ref. 1000	1.24 p/piece
B80107011	ref. 1100	2.23 p/piece
B80107012	ref. 1200	1.24 p/piece
B80107013	ref. 1500	1.68 p/piece

KEA	fixing clip lac. black	P/UK
B80400008	ref. 1000	1.35 p/piece
B80400005	ref. 1100	2.34 p/piece
B80400007	ref. 1200	1.35 p/piece
B80400006	ref. 1500	1.77 p/piece

Recommended uses:

- Laying of tiles in facades.
- Laying of ceramics in ceilings and cornices.
- Indoor laying of large format porcelain tiles at a certain height.

Materials:

- Medium and large format porcelain tiles:
 - STON-KER
 - PAR-KER
 - URBATEK

Suitable surfaces:

- Cement covered floors and walls .
- Concrete slabs.
- In outdoor cement screeds, we recommend to add **unicem**:
150 gr **unicem** / m² and milimeter of screed thickness.

Packaging

Presentation
50 u. bag
50 u. bag
50 u. bag
50 u. bag

Presentation
50 u. bag
50 u. bag
50 u. bag
50 u. bag





Grouting material and elastic sealants

Cement-based materials for tile joints

colorstuk 0-4	89
colorstuk 2-12	91
colorstuk especial n	93
colorstuk rapid n	95

Epoxy grouting materials

epotech aqua	97
epotech nature	98
epotech crystal	99
epotech gold & silver	100
epotech	101

Leveling system for ceramic tiles

Self-leveling spacers	103
-----------------------	-----

Elastic joint sealants

s-107	105
s-107 n	106
p-404	107

Additive for grouting material

cl-stuk	108
---------	-----

colorstuk 0-4

colorstuk 0-4 is a type CG 2 fine grain grouting material as per EN 13888, for grouting joints up to 4 mm. It is easy to apply, resistant and colour stable, and it is specially recommended for rectified tiles.

A high-tech, fine grained colored mortar for grouting tile joints from 0 to 4 mm. Suitable for all kinds of ceramic tiles and natural stone. Indoors and outdoors.



- 
glass
mosaic
- 
rectified
ceramics
- 
indoors
- 
high
traffic
- 
pools
- 
radiant
heating

colorstuk 0-4

Features:

- Cement-based, single-component, colored mortar.
- Fine texture mortar for grouting tile joints up to 4 mm.
- Easy to apply and clean.
- Resistant to heat and UV radiation.
- Frost-resistant.
- Wide colour range.
- Mixing water:

colorstuk 0-4 n white 1,7 l per 5 kg bag.

colorstuk 0-4 n white 8,5 l per 25 kg bag.

colorstuk 0-4 n white 1,3 l per 5 kg bag.

Recommended uses:

- Tile joints up to 4 mm.
 - Indoor wall tile coverings. Specially recommended for rectified tiles.
 - Indoor floor tiles, including public buildings.
- In the following applications, replace mixing water by **cl-stuk** additive.
- Outdoor floors.
 - High traffic floor tiles.
 - Floor tiles on radiant heating.
 - Pools and damp environments.

Materials:

- Absorbent and non-absorbent ceramic tiles, including porcelain tiles.
 - Glass mosaic.
 - Natural stone and marble not prone to staining.
- In the following applications, replace mixing water by **cl-stuk** additive.
- Wall tiles with mosaic-like patterns.
 - DQS slabs and other kinds of marble agglomerate.

Substrates:


- All usual substrates for ceramic tiles laying.

Certifications/Standards:

EN 13888 CG2

Coverage for 1 mm joint.

Tile	a x b mm	h mm	gr/m²
Mosaic	20 x 20	4	600
Mosaic	50 x 50	4	240
Tile	100 x 100	6	192
Tile	200 x 200	8	120
Tile	200 x 316	10	122
Tile	316 x 446	10	81
Tile	316 x 596	10	73
Tile	316 x 900	10	64
Tile	316 x 316	10	95
Tile	446 x 446	10	67
Tile	446 x 660	10	57
Tile	596 x 596	10	50
Tile	800 x 800	10	38
Tile	596 x 1200	10	38
Tile	180 x 659	10	106
Tile	193 x 1200	10	90



colorstuk 0-4

KEA			P/UK
B21501001	blanco		5.07 p/bag
B21502002	manhattan		5.07 p/bag
B21502003	bahama		6.86 p/bag
B21502004	cemento		6.86 p/bag
B21502005	antracita		6.86 p/bag
B21502006	negro		6.86 p/bag
B21502009	marfil		5.07 p/bag
B21502010	marrón		6.86 p/bag
B21502016	beige		7.07 p/bag
B21522218	caramelo		6.75 p/bag
B21522217	moka		6.97 p/bag
B21522219	gris		6.55 p/bag

Packaging

Presentation	Europallet
5 kg bag	400 kg
5 kg bag	400 kg
5 kg bag	400 kg
5 kg bag	400 kg
5 kg bag	400 kg
5 kg bag	400 kg
5 kg bag	400 kg
5 kg bag	400 kg
5 kg bag	400 kg
5 kg bag	400 kg
5 kg bag	400 kg
5 kg bag	400 kg
5 kg bag	400 kg

Colours shown are approximate. There are physical samples available to customers for checking the real grout colour.

* Replace mixing water by **cl-stuk**.

Before using this product in any application not indicated in this catalogue, please perform a test or refer to the product's technical sheet.at

Before using this product in any application not indicated in this catalogue, please perform a test or refer to the product's technical sheet.at

colorstuk 2-12

colorstuk 2-12 is a type CG 2 fine grain grouting material as per EN 13888, for grouting joints from 2 to 12 mm. It is easy to apply, resistant and colour stable, and it is specially recommended for floors with a wide joint.

A high-tech, fine grained colored mortar for grouting tile joints from 2 to 12 mm. Suitable for all kinds of ceramic tiles and natural stone. Indoors and outdoors.



- rustic floors
- rectified ceramics
- indoors
- high traffic
- outdoor floors
- radiant heating

colorstuk 2-12

Features:

- Cement-based, single-component, colored mortar.
- Fine texture mortar for grouting tile joints from 2 to 12 mm.
- Easy to apply and clean.
- Resistant to heat and UV radiation.
- Frost-resistant.
- Wide colour range.
- Mixing water: colorstuk 2-12 n colour 1,0 l per 5 kg bag.
colorstuk 2-12 n colour 5,0 l per 25 kg bag.

Recommended uses:

- Tile joints from 2 to 12 mm.
 - Indoor wall tile coverings with wide joint.
 - Indoor floors. Specially recommended for rustic tiles.
- In the following applications, replace mixing water with **d-stuk** additive.
- Outdoor floor and wall tiles.
 - High traffic floor tiles.
 - Floor tiles on radiant heating.
 - Pools and damp environments.

Materials:

- Absorbent and non-absorbent ceramic tiles, including porcelain tiles.
 - Glass mosaic.
 - Natural stone and marble not prone to staining.
 - Terracotta tiles.
- In the following applications, replace mixing water with **d-stuk** additive.
- Ceramic tiles with relief to be covered with grouting material.

Substrates:


- All usual substrates for ceramic tiles laying.

Certifications/Standards:

EN 13888 CG2

Coverage for 1 mm joint.

Tile	a x b mm	h mm	gr/m²
Mosaic	20 x 20	4	600
Mosaic	50 x 50	4	256
Tile	100 x 100	6	192
Tile	200 x 200	8	128
Tile	200 x 316	10	131
Tile	316 x 446	10	87
Tile	316 x 596	10	77
Tile	316 x 900	10	68
Tile	316 x 316	10	101
Tile	446 x 446	10	72
Tile	446 x 660	10	61
Tile	596 x 596	10	54
Tile	800 x 800	10	40
Tile	596 x 1200	10	40
Tile	180 x 659	10	113
Tile	193 x 1200	10	96



* Replace mixing water by **d-stuk**.

Before using this product in any application not indicated in this catalogue, please perform a test or refer to the product's technical sheet.at



colorstuk 2-12

KEA			P/UK
B21521001	manhattan		5.71 p/bag
B21522002	cemento		7.17 p/bag
B21522004	antracita		7.17 p/bag
B21522005	negro		7.17 p/bag
B21522006	marfil		7.17 p/bag
B21522009	beige		7.17 p/bag
B21522016	blanco		7.17 p/bag
B21522224	gris		6.95 p/bag
B21522222	marrón		6.65 p/bag

Packaging

Presentation	Europallet
5 kg bag	400 kg
5 kg bag	400 kg
5 kg bag	400 kg
5 kg bag	400 kg
5 kg bag	400 kg
5 kg bag	400 kg
5 kg bag	400 kg
5 kg bag	400 kg
5 kg bag	400 kg
5 kg bag	400 kg

Colours shown are approximate. There are physical samples available to customers for checking the real grout colour.

Before using this product in any application not indicated in this catalogue, please perform a test or refer to the product's technical sheet.at

colorstuk especial n

colorstuk especial n is a type CG 2 very fine grain grouting material as per EN 13888, for grouting joints up to 4 mm. Its formula includes ultrafine aggregates, which make it specially recommended for tiles with a glaze sensitive to scratching.

A high-tech, fine grained colored mortar for grouting tile joints up to 4 mm. Specially recommended for grouting rectified ceramic tiles sensible to scratching.



- glass mosaic
- rectified ceramics
- bath environments
- Crystal series
- high traffic
- radiant heating

colorstuk especial n

Features:

- Cement-based, single-component, colored mortar.
- Ultrafine aggregates formula.
- Fine texture mortar for grouting tile joints up to 4 mm.
- Easy to apply and clean.
- Resistant to heat and UV radiation.
- Frost-resistant.
- Wide special colours range.
- Mixing water: colorstuk especial n colour 0,65 l per 2 kg bag.

Recommended uses:

- Tile joints up to 4 mm.
- Ceramic tiles with low hardness glaze as per Mohs scale.
- Indoor wall tile coverings. Specially recommended for rectified tiles.
- Indoor floor tiles, including public buildings.

In the following applications, replace mixing water with **cl-stuk** additive.

- Wall and floor tiles into direct contact with water.
- Floor tiles on radiant heating.

Materials:

- Absorbent and non-absorbent ceramic tiles.
- Ceramic tiles with special finishes.
- Glass mosaic.
- Natural stone and marble not prone to staining.
- Do not use on polished materials.

In the following applications, replace mixing water by **cl-stuk** additive.

- Wall tiles with mosaic-like patterns.
- DQS slabs and other kinds of marble agglomerate.

Substrates:


- All usual substrates for ceramic tiles laying.

Certifications/Standards:

EN 13888 CG2

Coverage for 1 mm joint.

Tile	a x b mm	h mm	gr/m²
Mosaic	20 x 20	4	640
Mosaic	50 x 50	4	256
Tile	100 x 100	6	192
Tile	200 x 200	8	128
Tile	200 x 316	10	131
Tile	316 x 446	10	87
Tile	316 x 596	10	77
Tile	316 x 900	10	68
Tile	316 x 316	10	101
Tile	446 x 446	10	72
Tile	446 x 660	10	61
Tile	596 x 596	10	54
Tile	800 x 800	10	40
Tile	596 x 1200	10	40
Tile	180 x 659	10	113
Tile	193 x 1200	10	96



* Replace mixing water by **cl-stuk**.



colorstuk especial n

KEA		P/UK
B24302045	acid	9.06 p/kg
B24302049	cherry	19.08 p/kg
B24302043	dark	13.26 p/kg
B24302047	moka	9.02 p/kg
B24302042	nacare	9.36 p/kg
B24302044	vanilla	9.06 p/kg
B24302046	white	9.06 p/kg
B24302051	graphite	13.64 p/kg

Packaging

Presentation	Europallet
2 kg bag	432 kg
2 kg bag	432 kg
2 kg bag	432 kg
2 kg bag	432 kg
2 kg bag	432 kg
2 kg bag	432 kg
2 kg bag	432 kg
2 kg bag	432 kg

Colours shown are approximate. There are physical samples available to customers for checking the real grout colour.

Before using this product in any application not indicated in this catalogue, please perform a test or refer to the product's technical sheet.at

colorstuk rapid n

colorstuk rapid n is a type CG 2 high-performance, cement-based grouting material as per EN 13888, for grouting joints up to 15 mm. Suitable for all kinds of ceramic tiles and natural stone, it is specially recommended for outdoor applications and permanently damp environments.

A high-tech, fine grained colored mortar with fast setting and hardening times for grouting tile joints up to 15 mm. Suitable for all kinds of ceramic tiles and natural stone. Indoors and outdoors.



- glass mosaic
- rectified ceramics
- high traffic
- bathroom environments
- pools
- facades

colorstuk rapid n

Features:

- Cement-based, single-component, colored mortar.
- Fine texture mortar for grouting tile joints up to 15 mm.
- Mortar with fast setting and hardening times.
- It prevents efflorescences.
- Excellent mechanical resistance.
- Resistant to heat and UV radiation.
- Frost-resistant.
- Waterproof mortar.
- Anti-mold action.
- Easy to apply and clean.
- Wide colour range.
- Mixing water: colorstuk rapid n 1,1 l per 5 kg bag.

Recommended uses:

- Tile joints up to 15 mm.
- Indoor wall and floor tiles.
- Outdoor floors and terraces.
- High traffic floor tiles.
- Floor tiles on radiant heating.
- Pools and damp environments.
- Outdoor wall tiles in facades.

Materials:

- Absorbent and non-absorbent ceramic tiles, including porcelain tiles.
- Tiles with mosaic-like patterns.
- Glass mosaic.
- Clay and terracotta tiles.
- Natural stone and marble not prone to staining.

Substrates:


- All usual substrates for ceramic tiles laying.

Certifications/Standards:

EN 13888 CG2 Ar W

Coverage for 1 mm joint.

Tile	a x b mm	h mm	gr/m ²
Mosaic	20 x 20	4	600
Mosaic	50 x 50	4	240
Tile	200 x 200	8	192
Tile	200 x 200	8	120
Tile	200 x 316	10	122
Tile	316 x 446	10	81
Tile	316 x 596	10	73
Tile	316 x 900	10	64
Tile	316 x 316	10	95
Tile	446 x 446	10	67
Tile	446 x 660	10	57
Tile	596 x 596	10	50
Tile	800 x 800	10	38
Tile	596 x 1200	10	38
Tile	180 x 659	10	106
Tile	193 x 1200	10	90



colorstuk rapid n

KEA		P/UK
B22501001	blanco	12.42 p/bag
B22502002	manhattan	9.92 p/bag
B22502003	bahama	12.94 p/bag
B22502004	cemento	9.92 p/bag
B22502005	antracita	9.92 p/bag
B22502006	negro	12.39 p/bag
B22502007	caramelo	12.39 p/bag
B22502008	terracota	12.39 p/bag
B22502009	marfil	12.83 p/bag
B22502010	marrón	12.39 p/bag
B22502011	tabaco	16.56 p/bag
B22502013	gris	12.03 p/bag
B22502016	beige	12.81 p/bag
B21522220	moka	11.79 p/bag
B22902006	negro	52.79 p/bag

Colours shown are approximate. There are physical samples available to customers for checking the real grout colour.

Packaging

Presentation	Europallet
5 kg bag	400 kg
5 kg bag	400 kg
5 kg bag	400 kg
5 kg bag	400 kg
5 kg bag	400 kg
5 kg bag	400 kg
5 kg bag	400 kg
5 kg bag	400 kg
5 kg bag	400 kg
5 kg bag	400 kg
5 kg bag	400 kg
5 kg bag	400 kg
5 kg bag	400 kg
5 kg bag	400 kg
5 kg bag	400 kg
25 kg bag	1.000 kg

epotech aqua

epotech aqua is a new line of epoxy putties for grouting tile joints. Two-component epoxy putty with no organic solvents. It is waterproof, it has outstanding chemical and mechanical properties and it is easy to apply. Specially recommended for application on mosaics and ceramic tiles with relief.

This material is suitable for grouting joints from 0 to 10 mm in floor and wall tiles, indoors and out. Excellent resistance to chemicals. Suitable for pools and permanently damp environments. Suitable as high adherence grouting material for ceramic tiles with any absorption level and format, for glass mosaic or natural stone.



- ☒ kitchen countertops
- ☒ bathroom environments
- ☒ public toilets
- ☒ adhesive epoxy
- ☒ shower trays showers
- ☒ pools

epotech aqua

Features:

- Two-component colored epoxy putty.
- Easy to apply and clean. This product is free of organic solvents and plasticizers
- Excellent joint colour stability.
- Resistance to most chemicals and alkali, even in high concentrations.
- Waterproof joint, no water absorption.
- Excellent adherence and mechanical resistance.
- Tile joints up to 10 mm.
- Wide colour range.

Recommended uses:

- Public toilets and private bathrooms.
- Wall tiles with special chemical resistance.
- Pools and damp environments.
- Tile joints with uniform colour and shade, resistant to the passing of time.
- High traffic and outdoor floors.
- High adherence grouting material. Specially recommended.
 - Slate and natural stone.
 - Mesh backed glass mosaic.
- Especially recommended for meshed glass mosaics from L'ANTIC COLONIAL in wet areas.

Materials:


- Absorbent and non-absorbent ceramic tiles, including porcelain tiles.
- Tiles with mosaic-like patterns. Please refer to PORCELANOSA / VENIS catalogues.
- Glass mosaic.
- Natural stone and marble not prone to staining.

Substrates:

- All usual substrates for ceramic tiles laying.

Coverage for 1 mm joint.

Tile	a x b mm	gr/m²
Mosaic	20 x 20	960
Wall tile	mosaic type 20 x 30	600-800
Wall tile	20 x 30	125
Wall tile	30 x 90	90
Floor tile	30 x 30	95
Floor tile	44 x 44	75
Floor tile	60 x 60	60



epotech aqua

KEA			P/UK
B42562016		antracita	42,23 p/kg
B42562017		beige	42,23 p/kg
B42562020		blanco	42,88 p/kg
B42562019		gris	42,23 p/kg
B41061004		marfil	41,36 p/kg
B35200002		epoxy cleaning kit	52.60 p/u

Colours shown are approximate. There are physical samples available to customers for checking the real grout colour.

Before using this product in any application not indicated in this catalogue, please perform a test or refer to the product's technical sheet.at

epotech nature

epotech nature is a new micro grain porcelain grout for the sealing of joints in ceramic tiles with designs inspired by nature. It has been specially developed for porcelain tiles that reproduce the appearance and texture of wood, such as PORCELANOSA Group's par-ker. Professional use.

This material is suitable for grouting tile joints up to 5 mm. in floorings and wall coverings, both indoors and outdoors. Excellent resistance to chemicals. Suitable for pools and permanently damp environments. Suitable as high adherence grouting material for ceramic tiles with any absorption level and format, for glass mosaic, or natural stone.



- ☒ ceramic parket
- ☒ par-ker
- ☒ high traffic
- ☒ outdoor
- ☒ shower trays
- ☒ pools

epotech nature

Characteristics:

- Two-component colored epoxy putty.
- Easy to apply and clean. This product is free of organic solvents and plasticizers.
- Excellent joint color stability.
- Resistance to most chemicals and alkali, even in high concentrations.
- Waterproof joint, no water absorption.
- Excellent adherence and mechanical resistance. Hypoallergenic and bacteriostatic.
- Tile joints up to 5 mm.
- Wide range of colors inspired by natural woods.

Recommended use:

- Floorings and wall coverings in natural wood-inspired ceramics.
- Tile joints with uniform color and shade, resistant to the passing of time.
- Floorings with built-in heating.
- Pools and damp environments.
- High traffic floor tiles
- Outdoor floorings protected against the presence of rising moisture
- Floorings and wall coverings in direct contact with chemicals. See technical sheet.

Consumo para junta de 1 mm:

Tile	a x b mm	h	gr/ m²
Wall covering	316 x 900	11	71
Wall covering	330 x 1000	11	67
STON-KER	446 x 446	11	75
STON-KER	435 x 659	11	63
STON-KER	446 x 660	11	62
STON-KER	450 x 900	11	55
STON-KER	596 x 596	11	56
STON-KER	800 x 800	11	42
STON-KER	596 x 1200	11	293
PAR-KER	180 x 659	11	118
PAR-KER	219 x 660	11	101
PAR-KER	143 x 900	11	135
PAR-KER	220 x 900	11	94
PAR-KER	193 x 1200	11	100
PAR-KER	193 x 1800	12	104
PAR-KER	294 x 1800	12	171

epotech nature

KEA	SAP		P/EU
B42562034		wenge	12.89 per kg
B42562029		doussie	12.89 per kg
B42562033		iroko	12.89 per kg
B42562035		oak	12.89 per kg
B42562028		elm	12.89 per kg
B42562031		beech	12.89 per kg
B42562032		ash	12.89 per kg
B42562030		maple	12.89 per kg

Colors shown are approximate. There are physical samples available to customers for checking the real grout color.

Packaging

Presentation	Europallet
1.5 kg container	378 Kg
1.5 kg container	378 Kg
1.5 kg container	378 Kg
1.5 kg container	378 Kg
1.5 kg container	378 Kg
1.5 kg container	378 Kg
1.5 kg container	378 Kg
1.5 kg container	378 Kg



epotech crystal

epotech crystal is an epoxy putty for grouting tile joints. Two-component putty with a translucent finish. It reflects the colour of the tile or mosaic surrounding the joint. It features all the properties of epoxy putties: watertightness, high resistance to chemicals and mechanical properties. Specially recommended for application on mosaics and ceramic tiles with relief. Extra fine, micro grain porcelain grout.

This material is suitable for grouting joints up to 5 mm in floor and wall tiles indoors. Excellent resistance to chemicals in high concentrations. Suitable for permanently damp environments.



- ☒ Glass mosaic
- ☒ Rectified ceramics
- ☒ Par-ker
- ☒ Technical porcelain tiles
- ☒ Shower Trays
- ☒ Outdoors

epotech crystal

Features:


- Extra fine, micro grain porcelain grout.
- Easy to apply and clean epoxy putty.
- Translucent appearance.
- High resistance to most acids and alkali, even in high concentrations.
- Waterproof joint, no water absorption.
- Excellent adherence and mechanical resistance.
- Prevents the development of fungi and bacteria.
- Tile joints up to 5 mm.

Recommended uses:

- Wall and floor tiles with minimum joint.
- Indoor floor and wall tiles.
- Mosaic or natural stone wall coverings.
- Wall tiles and mosaics with glass elements.
- Par-ker floor coverings.
- Technical, porcelain floor coverings.

Coverage for 1 mm joint.

Tile	a x b mm	gr/m ²
Mosaic	20 x 20	960
Wall tile	mosaic type	600-800
Wall tile	20 x 30	125
Wall tile	30 x 90	90
Floor tile	30 x 30	95
Floor tile	44 x 44	75
Floor tile	60 x 60	60



epotech crystal

KEA		P/UK
B42562025	crystal	52.60 p/kg

Packaging

Presentation	Europallet
3 kg can	295 Kg



epotech gold & silver

epotech gold & silver is an epoxy putty for grouting tile joints. Two-component putty plus metal flakes featuring a unique, glossy finish. It features all the properties of epoxy putties: watertightness, high resistance to chemicals and mechanical properties. Specially recommended for application on mosaics and ceramic tiles with relief.

This material is suitable for grouting joints up to 5 mm in floor and wall tiles indoors. Excellent resistance to chemicals in high concentrations. Suitable for permanently damp environments.



- ☒ Glass mosaic
- ☒ Mosaic-like tiles
- ☒ Rectified ceramics
- ☒ Special glazes
- ☒ Shower Trays
- ☒ Outdoors

epotech gold & silver

Features:


- Two-component epoxy putty plus golden or silver metallic additive.
- Easy to apply and clean.
- High resistance to most chemicals and alkali, even in high concentrations.
- Waterproof joint, no water absorption.
- Excellent adherence and mechanical resistance.
- Prevents the development of fungi and bacteria.
- Tile joints up to 5 mm.

Recommended uses:

- Wall and floor tiles with decorative, metallic finish.
- Indoor wall and floor tiles.
- Damp environments.
- Tile joints with uniform colour and shade, resistant to the passing of time.

Consumption for 1 mm joint.

Tile	a x b mm	gr/m ²
Mosaic	20 x 20	960
Wall tile	mosaic type	600-800
Wall tile	20 x 30	125
Wall tile	30 x 90	90
Floor tile	30 x 30	95
Floor tile	44 x 44	75
Floor tile	60 x 60	60



epotech gold

KEA		P/UK
B42562021	gold	67.62 p/kg

epotech silver

KEA		P/UK
B42562022	silver	65.67 p/kg

Materials:

- Absorbent and non-absorbent ceramic tiles, including porcelain tiles.
- Glass mosaic.
- Natural stone and marble not prone to staining.

Before applying epotech gold & silver on metallic profiles or wall tiles with special glazes, carry out a prior test or check with the Technical Department at butech.

Substrates:

- All usual substrates for ceramic tiles laying.

Certifications/Standards:

EN 13888 RG

Packaging

Presentation	Europallet
3 kg can	295 Kg

Packaging

Presentation	Europallet
3 kg can	295 Kg



epotech

epotech is an epoxy putty for grouting tile joints. Waterproof, two-component epoxy putty with outstanding chemical and mechanical properties. Specially recommended for tile joints requiring the highest mechanical and chemical properties.

This material is suitable for grouting joints from 3 to 15 mm in floor and wall tiles, indoors and out. Excellent resistance to chemicals in high concentrations. Suitable for pools and permanently damp environments. Suitable as high adherence grouting material for ceramic tiles with any absorption level and format, for glass mosaic or natural stone.



- ☒ kitchen countertops
- ☒ industrial kitchens
- ☒ chemical industry
- ☒ food industry
- ☒ shower trays showers
- ☒ pools

epotech

Features:

- Two-component colored epoxy putty.
- Excellent joint colour stability.
- High resistance to most chemicals and alkali, even in high concentrations.
- Waterproof joint, no water absorption.
- Excellent adherence and mechanical resistance.
- Tile joints from 3 to 15 mm.

Recommended uses:

- Wall tiles with special chemical resistance.
- Chemical and food industry and premises subject to thorough cleaning.
- Pools and permanently damp environments, Turkish baths and spas.
- High traffic and outdoor floors.
- High adherence grouting material. Specially recommended.
 - Slate and natural stone.
 - Mesh backed glass mosaic.
- Especially recommended for slate from L'ANTIC COLONIAL.
- Especially recommended for AIRSLATE from L'ANTIC COLONIAL.

Materials:

- Absorbent and non-absorbent ceramic tiles, including porcelain tiles.
- Glass mosaic.
- Natural stone and marble not prone to staining.

Substrates:

- All usual substrates for ceramic tiles laying.

Certifications/Standards:

EN 13888 RG


Packaging

Presentation	Europallet
5 kg can	375 kg/pallet
5 kg can	375 kg/pallet
5 kg can	375 kg/pallet
5 kg can	375 kg/pallet



Coverage for 1 mm joint.

Tile	a x b mm	gr/m²
Mosaic	20 x 20	960
Wall tile	mosaic type 20 x 30	600-800
Wall tile	20 x 30	125
Wall tile	30 x 90	90
Floor tile	30 x 30	95
Floor tile	44 x 44	75
Floor tile	60 x 60	60



epotech

KEA			P/UK
B42562001		blanco	164.90 p/can
B42562002		manhattan	147.40 p/can
B42562005		antracita	164.90 p/can
B42562009		marfil	28.80 p/can
B35200002		epoxy cleaning kit	52.60 p/u

Colours shown are approximate. There are physical samples available to customers for checking the real grout colour.

Grouting material selection chart

1. Once chosen the wall tile model, determine the type of ceramic material. Refer to the manufacturer's catalogue: PORCELANOSA, VENIS, URBATEK and L'ANTIC COLONIAL.

2. Search in the wall or floor tables, given the case, the grouts which are compatible with the type of ceramic material chosen.

	colorstuk 0-4	colorstuk 2-12	colorstuk especial	colorstuk rapid n	epotech aqua	epotech crystal	epotech gold & silver	epotech
WALL								
Wall tile								
Rectified wall tiles								
Gloss (Crystal) wall tiles								
Mosaic-like wall tiles			*					
Glass mosaic			*		**	**	**	**
Urbatek								
Urbatek polished					**	**	**	**
Ston-ker								
Par-ker								
XLIGHT								
Natural stone	**	**	**	**	**	**	**	**

	colorstuk 0-4	colorstuk 2-12	colorstuk especial	colorstuk rapid n	epotech aqua	epotech crystal	epotech gold & silver	epotech
FLOOR								
Stoneware tiles								
Porcelain tiles								
Urbatek								
Urbatek polished					**	**	**	**
Ston-ker								
Ston-ker brick / Mosaic								
Par-ker								
DQS	*				**	**	**	**
Natural stone	**	**	**	**	**	**	**	**
Glass mosaic			*		**	**	**	**

3. Check which one of the compatible adhesives best matches its final use and substrate type.

	Bath-rooms	Electric radiant floor heating	High traffic	Pool	Outdoor floor	Façade	Watertight-ness	Resistance to chemicals
INTENTDED USE								
colorstuk rapid n								
epotech aqua								
epotech crystal								
colorstuk 0-4	*	*	*					
colorstuk 2-12	*	*	*					
colorstuk especial	*	*						
epotech gold & silver								
epotech								


4. Once you have chosen an adhesive which is compatible with the tile and its final use, check its features in this catalogue.

Given the wide variety of natural stones and glass mosaics from L'ANTIC COLONIAL, we recommend to check the material's scratch and stain resistance.

*: Mix with **cl-stuk** additive.
**: Be extremely cautious when cleaning the grout off the chosen floor or wall tile.

self-leveling spacers

Leveling system for ceramic tiles. Eases ceramic tile laying and guarantees a perfectly flat surface of the final installation. The system consists of a new type of spacer with adjustable height that levels the surrounding tiles and prevents them from moving. Specially recommended when tile, design or use features demand a perfect finish, with an even, seamless surface.



Large format floors

- ☒urbatek
- ☒ston-ker
- ☒parker
- ☒large format
- ☒rectified ceramics
- ☒minimum joint

self-leveling spacers

Features:

- Guarantees tiles are even.
 - Prevents tiles from moving due to laying errors or due to mortar setting.
 - Reduces retouching and laying times.
- Suitable for 1-3 mm wide joints.
 - Suitable for tiles 3 to 15 mm thick.
 - The system consists of a spacer, a wedge and an adjusting tool.
 - Wedges are recoverable, only the spacers are consumed.

Recommended uses:

- Wall and floor tiles with minimum joint.
- Large format floor tiles.
- Laying of rectified wall tiles.
- Tiles with reduced thickness: XLIGHT
- Interlocking floor designs.
- Glued facades.

Materials:

- All wall tiles and similar products laid with cement-based adhesives.
- Thickness between 3 and 15 mm.

Substrates:

- All usual substrates for ceramic tiles laying.



Grouting material and elastic sealants

Coverage:

Tile	a x b mm	u/ m²
Tile	200 x 316	64
Tile	316 x 446	29
Tile	316 x 596	22
Tile	316 x 900	15
Tile	316 x 316	41
Tile	446 x 446	21
Tile	435 x 659	18
Tile	596 x 596	17
Tile	800 x 800	13
Tile	450 x 900	15
Tile	596 x 1200	10
Par-ker	180 x 659	43
Par-ker	143 x 900	47
Par-ker	220 x 900	31
Par-ker	193x 1200	26
XLIGHT	1000 x 1000	8
XLIGHT	1000 x 3000	4

self-leveling spacers

KEA		P/UK
B83511063	wedge	16.20 p/bag
B83511062	wedge	37.61 p/bag
B83511056	wedge	71.43 p/bag

B83511059	1 mm spacer	11.34 p/bag
B83511058	1 mm spacer	32.28 p/bag
B83511065	1 mm spacer	50.88 p/bag

B83511061	2 mm spacer	11.34 p/bag
B83511060	2 mm spacer	32.28 p/bag
B83511057	2 mm spacer	50.88 p/bag

B83511067	3 mm spacer	11.34 p/bag
B83511066	3 mm spacer	30.92 p/bag
B83511070	3 mm spacer	50.88 p/bag

B83511072	supplementary lift piece	11.97 p/bag
-----------	--------------------------	-------------

KEA		P/UK
B83511064	1 mm spacer system kit	60.60 p/kit
B83511069	2mm spacer system kit	60.60 p/kit
B83511068	3mm spacer system kit	60.60 p/kit

KEA		P/UK
B83510071	pincers for self-leveling spacer	38.25 p/u

Products with special sale conditions

Packaging

Presentation	Packaging
100 units/bag	840 bags/pallet
300 units/bag	240 bags/pallet
500 units/bag	140 bags/pallet

100 units/bag	600 bags/pallet
300 units/bag	200 bags/pallet
500 units/bag	120 bags/pallet

100 units/bag	600 bags/pallet
300 units/bag	200 bags/pallet
500 units/bag	120 bags/pallet

100 units/bag	600 bags/pallet
300 units/bag	200 bags/pallet
500 units/bag	120 bags/pallet

50 units/bag

Presentation
Kit
Kit
Kit

Presentation
Unit

s-107

S-107 is an acetic silicone putty for sealing joints. Specially recommended for sealing joints in bathrooms and for sealing perimeter joints in wall tile coverings. Indoor use.

Is a silicon rubber technical elastic joint sealant with acetic crosslinking. It polymerizes in contact with dampness becoming an elastomer highly elastic and resistant to atmospheric agents.



- ☒mortar
- ☒ceramics
- ☒glass
- ☒metal
- ☒joint joint
- ☒outdoor

s-107

Features:

- Single-component acetic silicone.
- High elasticity.
- Good adherence.
- Resistant to UV rays.

Recommended uses:

- Sealing joints in ceramics, glass, plastics and painted surfaces.
- Sealing perimeter joints in wall tile coverings.
- Gluing ceramic materials on wood boards.

Coverage:

• 2 x 2 mm joint	75.0 m
• 3 x 3 mm joint	33.3 m
• 5 x 3 mm joint	20.0 m
• 5 x 5 mm joint	12.0 m
• 8 x 4 mm joint	8.3 m
• 8 x 6 mm joint	6.2 m

Coverage
(ml/cartridge)

=

300
joint width (mm) x joint depth (mm)

s-107

KEA	SAP		P/UK
B82301004	100005811	s-107 blanco	2.88 p/u
B82301005	100005812	s-107 transparente	2.88 p/u
B82301006	100005813	s-107 gris	2.88 p/u

Products with special sale conditions



s-107 n

S-107 n is a neutral silicone putty for sealing joints. Specially recommended for sealing movement joints. Indoor and outdoor use.,

This putty crosslinks in contact with dampness and does not give off odors, thus becoming an elastomer highly elastic and resistant to atmospheric agents.



- ☒mortar
- ☒ceramics
- ☒glass
- ☒metal
- ☒movement joint
- ☒outdoor

s-107 n

Features:

- Single-component neutral silicone.
- High elasticity.
- Good adherence.
- Resistant to UV rays.
- Frost-resistant.

Recommended uses:

- Sealing joints even between materials sensible to chemical attack.
- Sealing movement joints in floors and walls.
- Sealing joints in ceramics, glass, metal and plastics.
- Sealing perimeter joints in wall tile coverings.
- Gluing ceramic materials on wood boards.

Coverage:

• 2 x 2 mm joint	75.0 m
• 3 x 3 mm joint	33.3 m
• 5 x 3 mm joint	20.0 m
• 5 x 5 mm joint	12.0 m
• 8 x 4 mm joint	8.3 m

Coverage
(ml/cartridge)

=

300
joint width (mm) x joint depth (mm)

s-107 n

KEA			P/UK
B82302001	blanco	white	4.39 p/u
B82302002	transparente	transparent	4.39 p/u
B82302003	gris	grey	4.39 p/u
B82302004	negro	black	4.39 p/u
B82600026	beige	beige	4.39 p/u
B82600035	caramelo	caramel	5.49 p/u
B82600036	antracita	anthracite	5.49 p/u
B82600032	bahama	bahama	5.49 p/u
B82600030	cemento	cement	5.49 p/u
B82600029	marfil	ivory	5.49 p/u
B82600031	marrón	brown	5.49 p/u
B82600034	moka	moka	5.49 p/u
B82600028	tabaco	tobacco	5.49 p/u

Products with special sale conditions

Materials:

- Ceramic tiles and glass mosaic.
- Glass.
- Metal.
- Plastic material, PVC.
- Concrete slabs.
- Wood.

Substrates:

- All usual substrates for ceramic tiles laying.

Packaging

Presentation	Packaging
300 ml cartridge	25 cartridges x box
300 ml cartridge	25 cartridges x box
300 ml cartridge	25 cartridges x box
300 ml cartridge	25 cartridges x box
300 ml cartridge	25 cartridges x box
300 ml cartridge	25 cartridges x box
300 ml cartridge	25 cartridges x box
300 ml cartridge	25 cartridges x box
300 ml cartridge	25 cartridges x box
300 ml cartridge	25 cartridges x box
300 ml cartridge	25 cartridges x box
300 ml cartridge	25 cartridges x box
300 ml cartridge	25 cartridges x box
300 ml cartridge	25 cartridges x box



p-404

p-404 is polyurethane putty for sealing joints. Specially recommended for sealing movement joints outdoors. Indoor and outdoor use.,

This reticular putty in contact with dampness does not give off odors, thus becoming an extraordinary adherent, elastic and resistant elastomer to atmospheric agents.



- ☒ mortar
- ☒ ceramics
- ☒ glass
- ☒ metal
- ☒ joint joint
- ☒ outdoor

p-404

Features:

- Single-component polyurethane putty.
- High elasticity.
- High adherence.
- Resistant to UV rays.
- Frost-resistant.

Recommended uses:

- Sealing joints even between materials sensible to chemical attack.
- Sealing movement joints in floors and walls.
- Bonding of building materials like ceramics, concrete, roof tiles, wood, aluminium, polyester or PVC.
- Gluing ceramic materials on metal or wood boards.
- Gluing Concept XPS panels.

Coverage:

• 2 x 2 mm joint	77.5 m
• 3 x 3 mm joint	31.4 m
• 5 x 3 mm joint	20.6 m
• 5 x 5 mm joint	12.4 m
• 8 x 4 mm joint	8.6 m
• 8 x 6 mm joint	6.4 m

Coverage
(ml/cartridge)

=

310

joint width (mm) x joint depth (mm)

Materials:

- Ceramic tiles and glass mosaic.
- Glass.
- Metal.
- Plastic material, PVC.
- Concrete slabs.
- Wood.
- Concept XPS panels.

Substrates:

- All usual substrates for ceramic tiles laying.

p-404

KEA		P/UK
B82401001	p-404 blanco	4.83 p/u
B82401002	p-404 gris	4.83 p/u
B82401003	p-404 negro	5.36 p/u

Packaging


Presentation	Packaging
310 ml cartridge	25 cartridges x box
310 ml cartridge	25 cartridges x box
310 ml cartridge	25 cartridges x box



cl-stuk

cl-stuk is a latex which mixed with cement-based grouts like **colorstuk n**, reduces water absorption and enhances mechanical resistance and deformability. Specially recommended when laying ceramic outdoors and in permanently damp environments.

A latex additive that can be mixed with the **colorstuk** range of high-tech grout mortars in cases when increased mechanical resistance, reduced water absorption or improved flexibility is required.



- ☒ floors
- ☒ glass mosaic
- ☒ radiant heating
- ☒ high traffic
- ☒ pools
- ☒ facades

cl-stuk

Features:

- Water-based acrylic resins latex.
- Resistant to the most common chemicals.
- It reduces mortar water absorption.
- It enhances the adherence and deformability of the grouting material.
- It increases resistance to abrasion.
- Excellent resistance to UV rays and the effect of heat.
- Frost-resistant.

Coverage:

Product	%	liters	Kg/bag
Colorstuk 0-4 n white	34%	1.6-1.8	5
Colorstuk 0-4 n white	34%	8.2 - 8.8	25
Colorstuk 0-4 n colour	26%	1.2-1.4	5
Colorstuk 0-4 n colour	26%	6.4-6.6	25
Colorstuk 2-12 n	20%	0.9-1.1	5
Colorstuk 2-12 n	20%	4.8 - 5.2	25
Colorstuk especial n	32.5%	0.65	2

cl-stuk

KEA		P/UK
B51201001	cl-stuk	2.39 p/can
B51501001	cl-stuk	11.14 p/can

Recommended uses:

- Specially recommended in:
- Outdoor floor and wall tiles.
 - High traffic floor tiles.
 - Floor tiles on radiant heating.
 - Pools and damp environments.

It enhances grouting material performance in:

- Indoor wall tile coverings. Specially recommended for rectified tiles.
- Indoor floor tiles, including public buildings.

Materials:

- Specially recommended in:
- Wall tiles with mosaic-like patterns.
 - DQS slabs and other kinds of marble agglomerate.

It enhances grouting material performance in:

- Absorbent and non-absorbent ceramic tiles, including porcelain tiles.
- Glass mosaic.
- Natural stone and marble not prone to staining.

Substrates:

- All usual substrates for ceramic tiles laying.

Packaging

Presentation	Packaging
2 kg can	448 kg/pallet
5 kg can	480 kg/pallet





Substrate preparation products

Electric Radiant Floor Heating

Electric Radiant Floor Heating

111

Primer

universal bonding agent

113

super-prim

114

Self-leveling mortars

level 3

115

Cleaning products

acid net pro

116

acid net +

117

acid net 1L

117

basic gel 1L

117

porce-clean

118

colorstuk cleaner

118

epotech cleaner

118

colorstuk sealer

119

non slip tile

119

electric radiant floor heating

The **electric radiant floor heating** from **butech**, also know as **ERFH**, is a heating system with an electric element for radiant floors, specially designed to provide comfort in ceramic floors in bathrooms and, in general, all kinds of floors walked barefoot. The **ERFH** system consists of an electric element and a digital thermostat timer.

The electric element is a 5 mm diameter heating wire that transforms electric energy into heating. Never cut this kind of wire. Maximum power is 150 W/m².

User-friendly digital thermostat that regulates the turn on and off and heating power of the system.



- ☒ indoor
- ☐ outdoor
- ☒ new building work
- ☒ refurbishing homes
- ☒ bath environments
- ☒ living rooms

electric radiant floor heating

Features:

- Easy, quick and economic installation. No maintenance costs.
 - Ideal for homes not connected to the gas distribution network.
 - Applicable in floors where a water pipe heating cannot be installed.
 - More uniform heat distribution to all the surface of the room.
 - More pleasant elevation of heat distribution .
 - No air movement.
- Voltage: 230 V – 50/60 Hz
 - Maximum charge: 16 Amp / 230 V max
 - Maximum temperature: + 40°C

Recommended uses:

- Radiant heating in home refurbishings.
- Comfort and auxiliary heating in bathrooms and dressing rooms.
- Comfort and auxiliary heating in spas and premises with permanent dampness.
- Comfort and auxiliary heating in locker rooms, recreational and sports premises.
- Heating of indoor areas with high ceilings.
- Temporary heating of workplaces.
- Do not use in outdoor floors.

Installation:


- Professional heating system. Please contact authorized electrical installers.
- Choose the radiant mesh that suits the surface to be heated.
- In case of surfaces bigger than 10 m², connect meshes in parallel in a connection box.
- Do not connect meshes with a total surface bigger than 20 m² to one thermostat.
- Never cut the heating wire.
- Do not install under static elements and less than 10 cm from the walls.
- Never drill a floor where a radiant heating has been installed.
- Install concept panels. The thermal properties reflect all the heat up through the tile.

Guarantee:

- Thermostat guarantee: 2 years
- Electric mesh guarantee: 10 years

Materials:

- Absorbent ceramics and porcelain tiles (water absorption < 0.5% as per EN-ISO 10545-3).
- Natural stone and marble not prone to staining.
- Wooden floors bonded to the substrate.
- Do not use under floating floors.
- Do not use under material sensible to heat.



electric radiant floor heating

KEA	electric radiant floor heating	P/UK
B62902132	ERHF 1 m² (150w) n	226.01 p/u
B62902136	ERHF 2 m² (150w) n	267.41 p/u
B62902134	ERHF 3 m² (150w) n	282.21 p/u
B62902142	ERHF 4 m² (150w) n	370.72 p/u
B62902144	ERHF 5 m² (150w) n	413.74 p/u
B62902138	ERHF 6 m² (150w) n	439.95 p/u
B62902133	ERHF 7 m² (150w) n	491.70 p/u
B62902149	ERHF 8 m² (150w) n	543.47 p/u
B62902135	ERHF 10 m² (150w) n	474.13 p/u
B62902168	ERFH touch control thermostat	129.90 p/u
B62901102	ERHF reparation kit	13.99 p/u

Packaging

Contents	Presentation
mesh + thermostat	1 mesh/box
mesh + thermostat	1 mesh/box
mesh + thermostat	1 mesh/box
mesh + thermostat	1 mesh/box
mesh + thermostat	1 mesh/box
mesh + thermostat	1 mesh/box
mesh + thermostat	1 mesh/box
mesh + thermostat	1 mesh/box
only mesh	1 mesh/box
only thermostat	1 thermostat/box
	1 kit/box

universal bonding agent

butech universal bonding agent, multipurpose primer, is a high quality water-based synthetic primer for preparing both absorbent and non-absorbent substrates in readiness for the installation of ceramic, porcelain, glass and natural stone tiles and mosaics.

butech universal bonding agent is suitable for use on a wide range of substrates such as plaster, plasterboard, cement-based tilebacker boards, sand:cement render, masonry work, plywood, concrete, sand:cement and calcium sulphate based screeds. It is also suitable for non-absorbent substrates such as glazed or unglazed ceramic tiles, porcelain tiles, natural stone and terrazzo, tilebacker boards, **butech concept panel**, vinyl tiles etc. For use in interior and exterior areas.



Plaster substrates

- ☒ mortar
- ☒ concrete
- ☐ wood
- ☒ untiled floor anhydrite
- ☒ plaster board
- ☒ plastered wall

universal bonding agent

Features:

- Consolidates fine surface dust.
- Water-based synthetic resins primer.
- Once dry, it leaves a film over the substrate, which in plaster-based substrates prevents contact and chemical reaction with cement-based adhesives. It prevents ettringite buildup.
- It reduces substrate water absorption.
- It improves the bonding material setting time.
- It increases cohesion of the substrate.
- Easy application with a paint roller or a wide paintbrush.
- Indoor and outdoor use.,

Coverage:

Substrate	Coverage
Anhydrite/plaster substrate	100 - 200 gr/m²

Materials:

- All wall tiles and similar products to be laid with cement-based adhesives.

Recommended uses:

- Wall tiles on plaster or molding plaster substrates.
- Floor tiles on anhydrite substrates.
- Ceramic tiles on cement-based substrates with weak consistency.
- Reinforcement of self-leveling mortars.
- Pavimentos con calefacción radiante.

Suitable surfaces:

Walls

- Sand:cement renderings
- Concrete
- Lightweight block / brickwork, dense
- concrete blockwork
- Plasterboard, moisture resistant plasterboard, tilebacker boards
- Gypsum plaster
- Glazed bricks and tiles

Floors

- Concrete
- Sand:cement screeds
- Heated sand:cement screeds
- Anhydrite / hemi-hydrate screeds
- Plywood overlay
- Existing floor tiles
- Vinyl tiles


Packaging

Presentation	Europallet
1 l / bottle	



super-prim

superprim is a water-based acrylic resin primer with silica arids, used for preparing substrates prior to using adhesives, self-leveling mortars and mortar screeds. It reduces water absorption and improves the consistency of cement-based substrates. Professional use.



Primer for self-leveling mortars

- ☒ mortar
- ☒ plaster or anhydrite
- ☒ existing ceramics
- ☒ wood
- ☒ metal
- ☒ self-leveling mortar

super-prim

Features:

- Water-based, acrylic resin latex with silica arids.
- It enhances the adherence of cement mortars on glazed wall coverings.
- It improves the bonding material setting time.
- It reduces substrate water absorption.
- It increases cohesion of the substrate.
- Easy application with a paint roller or a wide paintbrush. Can be applied with airless spray.
- Indoor and outdoor use.
- Do not dilute with water or mix with any other liquids.

Coverage:

Substrate	Coverage
Non absorbent	200 - 250 gr/m²
Absorbent	250-300 gr/m²

super-prim

KEA		P/UK
B57500002	super-prim	6.26 p/kg

Recommended use:

- Primer for self-leveling mortars on highly absorbent or existing ceramic tile coverings.
- Ceramic tiles on cement-based substrates with weak consistency or existing ceramic tile coverings.
- Ceramic floor coverings on anhydrite substrates or ceramic wall coverings on plaster or molding plaster.
- Mortar screeds on brick partition walls or concrete block walls.
- Mortar screeds on ceramic tile or natural stone floors.
- Do not use in substrates subject to dampness increases.

Materials:

- All wall tiles and similar products to be laid with cement-based adhesives.

Substrates:

- Ceramic brick partition walls.
- Cement covered floors and walls.
- Concrete slabs and aerated concrete blocks.
- Anhydrite-covered floors and plastered walls.
- Indoor ceramic floor and wall tiles.
- Indoor wood boards.
- Indoor metal sheets.

Packaging

Presentation	Box
10 kg can	480 kg/pallet



level 3 n

butech level 3, fast setting fibre-reinforced self-levelling mortar, is a specially developed polymer modified cement-based self-levelling compound designed for evening out floor irregularities and to provide a perfectly flat base ready to receive tiled finishes.

Suitable for interior areas only. Can be used from 3 – 30 mm in thickness. Can be applied by hand or pump. At 3 mm, **butech level 3** can be walked on after 4-5 hours and is ready to receive tiled finishes after 24 hours. **butech level 3** is classified as C25-F5-A2_n-S1 to BS EN 13813.



Large format floors

- ☒ston-ker
- ☒large format
- ☒rectified ceramics
- ☒radiant heating
- ☒ceramics existing
- ☒outdoor

level 3 n

Features:

- Compressive strenght ≥ 25 N/mm²
- Flexural strenght ≥ 5 N/mm²
- Single-component, self-leveling mortar.
- Excellent adherence. Flexible.
- High fibre content.
- Application thickness between 3 and 30 mm.
- Easy application with a straight edge trowel or scraper.
- Indoor use.
- Mixing water: 4,25 - 4,50 l per 25 kg bag

Recommended uses:

- Indoor large format floor tile coverings.
- Indoor large format rectified floor tile coverings.
- Indoor floor tile coverings with a 1 mm joint.
- Floor tiles with radiant heating.

Coverage:

Substrate	Coverage
Self-leveling floors	1,4 kg/m ² and thickness millimeter

Materials:

- Large format floor tiles.
- Porcelain tiles (water absorption < 0.5% as per EN-ISO 10545-3).
- Natural stone and marbles.

Suitable surfaces:

Floors

- Concrete
- Sand:cement screeds
- Anhydrite / hemi-hydrate screeds
- Heated sand:cement screeds
- Plywood overlay
- Existing floor tiles
- Vinyl tiles

Packaging

Presentation	Europallet
25 kg bag	1000kg/pallet



acid net pro

acid net pro is an acid detergent for cleaning ceramic floor and wall tiles. Specially recommended for cleaning building debris. Indoor and outdoor use.

It is an acid solution that in contact with cement reacts and removes dirt or stains without damaging coverings or cement based joints like **colorstuk**. Suitable for removing saltpetre remains or dirt sensible to acid attack.



Building site cleaning

- ☒wall tile
- ☒floor tile
- ☒floor tile porcelain tile
- ☒glass mosaic
- ☒natural
- ☒special glazes

acid net pro

Features:

- Acid solution.
- Colorless liquid.
- pH < 0.1
- Viscosity: 5.0 - 8.0 cp at 20°C
- Recommended action time: 10-15 min.

Recommended uses:

- Building site final cleaning.
- Cleaning of remains of adhesives and cement-based grouting materials in floor and wall tiles.
- Cleaning of efflorescences and salts remains.
- Cleaning of lime remains and film.
- Cleaning of glazed substrates prior to laying new tiles.

Coverage:

Dilution	
1 : 1 with clear water	90-100 gr/m ²
1 : 2 with clear water	45-50 gr/m ²
1 : 3 with clear water	25-35 gr/m ²
1 : 5 with clear water	20 gr/m ²

Materials:

- Ceramic glazed and non-glazed tiles GLA, ULA.
- Glass mosaic.
- Natural stones resistant to acid descalers.
- It is not recommended to use **acid net pro** in materials sensible to acid cleaners like:
 - Marbles and natural limestones.
 - Ceramic tiles with surface finishes sensible to acid attack, like polished or metallic finishes.

Certifications/Standards:

CAS No.: 7664-38-2
Phrases: R-34
S2 , S26 , S36/37/39 , S45
Danger symbols: C

Substrates:

- Do not apply directly on:
 - Cement covered floors and walls .
 - Concrete slabs.

Packaging

Presentation	Europallet
2 kg bottle	448 kg/pallet
5 kg bottle	480 kg/pallet



*Given the wide variety of ceramic materials, we recommend to check with your tile provider about chemical resistance to acid attack.

acid net +

acid net + is a concentrated descaler for cleaning ceramic floor and wall tiles. Specially recommended for cleaning building debris. Indoor and outdoor use.

Recommended use:

- Building site final cleaning.
- Cleaning of remains of adhesives and cement-based grouting materials in floor and wall tiles.
- Cleaning of efflorescences and salts remains.
- Cleaning of plaster remains and plaster-based remains.
- Cleaning of lime remains and film.
- Cleaning of glazed substrates prior to laying new tiles.

acid net +

KEA			P/UK
B35200004		acid net +	9.69 p/u

acid net 1L

acid net is an acid detergent for cleaning ceramic floor and wall tiles. It dissolves all kinds or cement debris without damaging coverings or cement based joints like **colorstuk**.

Recommended use:

- Cleaning of remains of adhesives and cement-based grouting materials in floor and wall tiles.
- Cleaning of efflorescences and salts remains.
- Cleaning of plaster remains and plaster-based remains.
- Cleaning of lime remains and film.
- Cleaning of glazed substrates prior to laying new tiles.

acid net 1L

KEA			P/UK
B35200003		acid net	8.08 p/u

basic gel 1L

Concentrated alkaline detergent developed for cleaning ceramic tiles in general. terra-cotta and antiqued marble. It removes all kinds of oils, varnishes, paints, wax and home stains. Specially effective for etching former treatments.

Recommended use:

- Intensive cleaning of ceramic wall tiles.
- Cleaning of remains of wax, oil or grease from floor and wall tiles .
- Cleaning of glazed substrates prior to laying new tiles.

basic gel 1L

KEA			P/UK
B35200005		basic gel 1000 ml	9.62 p/u



Coverage:

Dilution 1: 1 with clear water	90-100 gr/m²
Dilution 1: 2 with clear water	45-50 gr/m²

Packaging

Presentation	Box
1000 ml bottle	12 bottles



Coverage:

Dilution 1: 1 with clear water	90-100 gr/m²
Dilution 1: 2 with clear water	45-50 gr/m²

Packaging

Presentation	Box
1000 ml bottle	12 bottles



Coverage:

Dilution 1: 1 with clear water	85-100 ml / m²
Dilution 1: 2 with clear water	40-50 ml / m²

Packaging

Presentation	Box
1000 ml bottle	12 bottles

porce-clean

Neutral detergent for cleaning ceramic and natural stone floor coverings. High degreas-ing power for a deep and perfect cleaning. Fast drying. Indoor and outdoor use.

Recommended use:

- Regular cleaning of ceramic wall tiles.
- Cleaning of remains of wax, oil or grease from floor and wall tiles .

porce-clean

KEA			P/UK
B35200008		porce-clean	7.19 p/u

colorstuk cleaner

Cleaner for cement based grouts. It removes dirt build-up and recovers the grout's orig-inal colour. Specially recommended for maintenance of joints sealed with **colorstuk**.

Recommended use:

- Cleaning of cement based joints stained with dust and dirt.
- Recovering the colour in cement based tiling joints.

colorstuk cleaner

KEA			P/UK
B35200007		colorstuk cleaner	8.50 p/u

epotech cleaner

Water-based detergent for cleaning epoxy putties remains and stains. Specially recom-mended for cleaning remains of **epotech aqua**. Professional use.

Recommended use:

- Cleaning of epoxy putties remains and films on ceramic tiles, glass mosaics and natural stones.

epotech cleaner

KEA			P/UK
B35200006		epotech cleaner	15.08 p/u



Coverage:

10 l of clean water	100-200 ml
---------------------	------------

Packaging

Presentation	Box
1000 ml bottle	12 bottles



Coverage for 2 mm joint.

Tile	200 x 316 cm	20 m²/package
Tile	316 x 596 cm	33 m²/package
Tile	316 x 900 cm	37 m²/package
Tile	446 x 446 cm	35 m²/package
Tile	446 x 660 cm	42 m²/package
Tile	596 x 596 cm	47 m²/package

Packaging

Presentation	Box
125 ml package	12 applicators



Coverage for 2 mm joint.

Tile	200 x 316 cm	20 m²/package
Tile	200 x 446 cm	30 m²/package
Tile	316 x 596 cm	33 m²/package
Tile	316 x 900 cm	37 m²/package

Packaging

Presentation	Box
500 ml bottle	20 bottles

*Given the wide variety of ceramic materials, glass mosaics and natural stones, we recommend to check with your tile provider about chemical resistance of the tiles before applying any cleaning product.

Before using any cleaning product, please perform a test or refer to the product's technical sheet.

*Given the wide variety of ceramic materials, glass mosaics and natural stones, we recommend to check with your tile provider about chemical resistance of the tiles before applying any cleaning product.

Before using any cleaning product, please perform a test or refer to the product's technical sheet.

colorstuk sealer

Colorless, waterproof protector for cement based joints. It coats in depth and strengthens the grout. It protects against water, oils and accidental spills. It eases the cleaning of joints as it reduces water absorption.

Recommended use:

- Sealing and protection for cement based grouts.



Coverage for 2 mm joint.

Tile	200 x 316 cm	40 m ² /package
Tile	316 x 596 cm	65 m ² /package
Tile	316 x 900 cm	74 m ² /package
Tile	446 x 446 cm	70 m ² /package
Tile	446 x 660 cm	83 m ² /package
Tile	596 x 596 cm	94 m ² /package

Packaging

Presentation	Box
125 ml package	16 applicators

colorstuk sealer

KEA		P/UK
B87010002	colorstuk sealer	10.40 p/u

non-slip tile

Non-slip treatment for glazed and unglazed ceramic tiles reducing the risk of slip and fall accidents. Indoor and outdoor use.

The non-slip treatment reacts with the ceramic tiles surface, generating thousands of microscopic bowls. These evenly distributed engravings increase the contact surface and, in the presence of water, produce a suction between the covering and the foot. This effect increases the coefficient of friction and reduces the risk of slip and fall accidents.



Recommended use:

- Glazed and non-glazed ceramic floor tile coverings.
- Indoor and outdoor floor tile coverings.
- Built in shower trays.
- Do not apply on fibre shower trays and bathtubs.
- Do not apply on materials which are sensible to acid attack, like limestones or mortar substrates.

Coverage

Ceramic tile	200 gr
--------------	--------

Packaging

Presentation	Box
500 ml bottle	20 bottles

non-slip tile

KEA		P/UK
B33601002	non slip tile	30.14 p/u

	Glass mosaic	Glazed ceramic tiles	Porcelain
Remains of building work	acid net +	acid net +	acid net +
Cement	acid net	acid net	acid net
Gypsum	acid net	acid net	acid net
Epoxy putty	epotech cleaner	epotech cleaner	epotech cleaner
Remains of silicone	Vitroceramic scraper + Acetone	Vitroceramic scraper + Acetone	Vitroceramic scraper + Acetone
Efflorescence	acid net	acid net	acid net
Moss	Bleach	Bleach	Bleach

Daily maintenance	porce-clean	porce-clean	porce-clean
Food	porce-clean	porce-clean	porce-clean
Coffee, juices, sodas	basic gel	basic gel	basic gel
Lemon, vinegar	basic gel	basic gel	basic gel
Rust stains	acid net	acid net	acid net
Urine and vomit	acid net	acid net	acid net

Oil, fat	basic gel	basic gel	basic gel
Motor oil	basic gel	basic gel	basic gel
Tar	Acetone	Acetone	Acetone
Paint, varnish, markers	Acetone	Acetone	Acetone
Adhesive and glue	Acetone	Acetone	Acetone
Rubber tires	Acetone	Acetone	Acetone

Waterproofing joints	colorstuk sealer	colorstuk sealer	colorstuk sealer
Joints cleaner	colorstuk cleaner	colorstuk cleaner	colorstuk cleaner
Anti-slip			non-slip tile

Given the wide range of mosaics and ceramics, it is recommended to consult the supplier of tiles about the chemical resistance. In any case, it is recommended to take a test.

We recommend the use on cleaning polished tiles, also with metal finish. Contact the supplier of tiles to know the chemical resistance. In any case, you have to take a test.

*Given the wide variety of ceramic materials, glass mosaics and natural stones, we recommend to check with your tile provider about chemical resistance of the tiles before applying any cleaning product.

Before using any cleaning product, please perform a test or refer to the product's technical sheet.



Waterproofing

Waterproofing

imperband	123
sylastic	125
terrace drain	126

Decoupling and waterproofing

lamitech n	127
------------	-----

Drainage

super drain	128
-------------	-----

imperband

imperband is a waterproof sheet, specially designed for indoor waterproofing of ceramic wall and floor coverings.

It is a 0,5mm thick polymer membrane with a double thermoplastic polyolefin sheet and covered on both sides by non woven polyester fibre that allow it to be bonded to surfaces using cement-based adhesives. Ideal for use in new construction and refurbishment of showers and baths, and any indoor environment permanently affected by damp.



- ☒ bath environments
- ☐ terraces
- ☒ new building work
- ☒ refurbishing bathrooms
- ☒ ceramic showers
- ☐ pools

imperband

Features:

- Double thermoplastic polyolefin membrane covered on both sides by non woven polyester fibre.
- Maximum waterproofing with minimal thickness (0.5 mm).
- Direct installation of the tile on the sheet.
- Good chemical resistance.
- Quick and easy application.

Recommended uses:

- Private bathrooms. Built in showers.
- Public toilets and showers.
- Spas and premises in permanently damp environments.
- Balconies and terraces smaller than 10 m².
- Do not use in outdoors surfaces greater than 10 m².

Installation:

- **imperband** sheet is compatible with type C2 cement-based adhesive as per EN 12004.
- In case of surfaces bigger than the length of the sheet, overlap two 10 cm sheets and bond with C2 adhesive.
- In waterproofing of floors, leave an excess of sheet of at least 10 cm in all the spots where floor meets the wall.
- Be extremely cautious when connecting the sheet to the drainage systems.
- Once the **imperband** sheet has been installed, cover with the chosen floor covering. Never leave exposed to direct sunlight.

Materials:

- Absorbent and non-absorbent ceramic tiles. Porcelain tiles with a water absorption < 0.5% as per EN-ISO 10545-3.
- Glass mosaic.
- Natural stone and marble not prone to staining.

Substrates:

- Cement covered floors and walls .
- Concrete slabs.
- Plasterboards.
- Plywood boards.
- On anhydrite or plaster substrates apply **universal bonding agent**.

Certifications/Standards:

Avis technique: CSTB 13/08-1035

imperband

KEA		P/UK
B84901001	imperband	320.08 p/roll
B84901006	imperband	55.34 p/roll

Packaging

Presentation	Europallet
30 m roll	720 m/pallet
5 m roll	300 m/pallet



Waterproofing

sylastic

sylastic is a two-component cement-based waterproofer with excellent bonding and deformability features, specially recommended for waterproofing outdoors. Compatible with type C2 cement-based adhesive as per EN 12004. Indoor and outdoor use.

Prevents the need of screed between waterproofing sheet and ceramic floor, thus reducing the final system thickness. It is applied in two 1-2 mm layers each, with a fiberglass mesh reinforcement on the first application. Special pieces and bands available for waterproofing joints and other critical spots.



- ☒ bath environments
- ☒ terraces
- ☒ new building work
- ☒ refurbishing bathrooms
- ☒ ceramic showers
- ☒ pools

sylastic

Features:

- Two-component waterproofing mortar.
- Indoor and outdoor waterproofer.
- Maximum waterproofing with minimal thickness (3 mm).
- It allows for direct laying of ceramic tiles with cement-based adhesive.
- Excellent adherence and maximum deformability.
- Good chemical resistance.
- Suitable for direct contact with water.

Coverage:

Bond coat:		
• One-layer application.		2,60 kg / m ²
• Sylastic mortar		1,95 Kg / m ²
• Sylastic additive		0,65 Kg / m ²
Waterproofing:		
• Two-layer application.		5,20 kg / m ²
• Sylastic mortar		3,90 Kg / m ²
• Sylastic additive		1,30 Kg / m ²
Maximum thickness per sylastic layer: 1.5 mm		

Recommended uses:

- Waterproofing of bathrooms and showers.
- Spas and premises in permanently damp environments.
- Outdoor terraces and balconies.
- Pools and premises into direct contact with water.
- Cisterns and reservoirs into direct contact with water.
- Repair of cracked floors and renderings.
- Promotes adherence on existing ceramic wall tiles and on wood or metal substrates.

Materials:

- Absorbent and non-absorbent ceramic tiles. Porcelain tiles with a water absorption < 0.5% as per EN-ISO 10545-3.
- Glass mosaic.
- Natural stone and marble not prone to staining.

Substrates:

- Cement covered floors and walls .
- Concrete slabs.
- Plasterboards.
- Wood boards.
- Existing floor tiles.
- Metal sheets.

Packaging

Presentation	Europallet
24 kg bag	960 kg/pallet
8 kg can	320 kg/pallet
50 m ² roll	
5 m roll	
10 m roll	
50 m roll	
Unit	
Unit	



sylastic

KEA		P/UK
B85900004	sylastic mortar	15.90 p/bag
B85900005	sylastic additive	66.68 p/can
B84900303	50 m fiberglass mesh	123.5 p/roll
B85900008	5 m waterproof band	18.85 p/roll
B85900009	10 m waterproof band	32.40 p/roll
B84905004	50 m waterproof band	171.5 p/roll
B84900101	outer angle	6.86 p/u
B84900202	inner angle	6.86 p/u

Before using this product in any application not indicated in this catalogue, please perform a test or refer to the product's technical sheet.

terrace drain

The **floor drain** from **butech** is a drain for terraces and outdoor floors. It features a wide dish around the grating, which ease the connection to waterproofing sheets. Available with horizontal and vertical outlet, it helps to solve easily and effectively outdoor waterproofing and drainage.

The 10 cm connecting piece between the grating and the drain can be cut, so that it can be installed with glass mosaics up to natural stones. Includes steel grating.



- ☒ indoor
- ☒ outdoor
- ☒ lamitech n
- ☒ sylastic
- ☒ new building work
- ☒ concept xps shower tray.

terrace drain

Recommended uses:

- Drain designed for connecting with waterproofing sheet.
- Specially designed for waterproofing outdoor terraces and floors.
- Vertical outlet.

Terrace drain features:

- 190 mm high drain.
- Discharge speed. 1.6 l/s.
- 75/110 mm vertical outlet.
- 36 cm diameter crown for waterproofing sheet fixation.
- Includes u-bend.
- 143 x 143 mm steel grating.



Terrace drain

KEA		P/UK
B82901009	75/110 vertical drain	50.76 p/u
B82901010	compensation piece	34.52 p/u
B82901011	floor drain connection	22.83 p/u

Terrace drain complements


Terrace drain connection:

Clamp for fixing waterproofing sheet to drain. Includes stainless steel clamp, rubber o-ring and 6 fixing screws.



Compensation piece:

Connection piece between drain and grating for installations with two overlaid waterproofing levels.
36 cm diameter crown for waterproofing sheet fixation.
12.5 cm high piece.



Packaging

Presentation
1 u./box
1 u./box
1 u./box

Before using this product in any application not indicated in this catalogue, please perform a test or refer to the product's technical sheet.

lamitech n

lamitech n is a multilayer polymer sheet, specially designed for outdoor floors decoupling. Protects tiles against substrate tensions, reducing the risk of breakage and piece lifting. Suitable for outdoor waterproofing.

Coextruded HDPE/EVAC membrane, with one side covered with polyester fibre and the other one with polyester entwined felt, that allows laying with cement-based adhesives. Absorbs tensions, reducing their transmission to the ceramic floor. Indoor and outdoor use.



- ☒

bath environments
- ☒

terraces
- ☒

anti-cracks
- ☒

refurbishing
- ☒

ceramic showers
- ☒

pools

lamitech n

Features:

- Multilayer HDPE/EVAC polymer membrane covered with polyester fibre.
- Maximum outdoors waterproofing with minimal thickness (3,4 mm).
- It allows for direct laying of ceramic tiles with cement-based adhesive.
- Good chemical resistance.
- Improves impact noise reduction.
- Quick and easy application.

Recommended uses:

- Decoupling of balconies and terraces.
- Waterproofing of outdoor floors.
- Laying of ceramics on wood substrates.
- Laying of floor tiles on cracked substrates. Terrace refurbishing.
- Laying of ceramics on substrates which are not set yet or present residual damp.

Installation:

- lamitech n sheet is compatible with type C2 cement-based adhesive as per EN 12004.
- Place sheets side by side, without overlappings. In case of using it as water-proofer, proceed to sealing sheet joints with **sylastic** waterproof mortar and **lamiband 200** waterproof band..
- In waterproofing of floors, lengthen the waterproofing with **lami-band 200** at least 10 cm in all the spots where floor meets the wall.
- In movement joints, use flexible tape **waterproof band**.
- Be extremely cautious when connecting the sheet to the drainage systems.
- Once **lamitech n** has been installed, lay the chosen floor with compatible adhesives. Never leave exposed to direct sunlight.

Materials:

- Absorbent and non-absorbent ceramic tiles. Porcelain tiles with a water absorption < 0.5% as per EN-ISO 10545-3.
- Glass mosaic.
- Natural stone and marble not prone to staining.

Substrates:

- Cement or anhydrite covered floors.
- Concrete slabs.
- Existing floor tiles.
- Plywood boards.

lamitech n


KEA		P/UK
B85900011	lamitech n	55.70 p/roll
B84901005	200 mm lami-band	101.70 p/roll
B84905004	waterproof band	171.50 p/roll
B85900004	sylastic mortero	15.90 p/bag
B85900005	sylastic aditivo	66.68 p/can

Packaging

Presentation	Europallet
5 m reel	200 m ² /pallet

30 m roll
50 m roll

Unit
Unit



super drain

super-drain is an 8 mm thick drainage sheet for waterproofing systems in outdoor terraces and balconies. It eases water evacuation and reduces the risk of damp appearance. Suitable for floors as well as for walls.

Polyethylene sheet with a tridimensional structure. It features 20 mm diameter circular nerves and it is covered by a filtering fabric. Installed on the waterproofing system, it drains the water towards the drain and protects mechanically.



- ☒

bath environments
- ☒

terraces
- ☒

new building work
- ☒

refurbishing terraces
- ☒

drainage
- ☒

pools

super-drain

Features:

- Polyethylene sheet with tridimensional structure with 20 mm circles.
- Maximum drainage with a 5 mm thickness.
- Good chemical resistance.
- Quick and easy application.

Recommended uses:

- Outdoor floors drainage. Terraces and balconies.
- Protection of ceramic floors against efflorescences.
- Reduction of the risk of substrate cracking.
- Protection of walls against damp.

Installation:

- **super-drain** sheet is directly installed on the waterproofing system with the filtering side facing up.
- In the case of surfaces bigger than 100 cm, overlap two **super-drain** sheets fitting at least three gap lines.
- Once the **super-drain** sheet laid, cover with a mortar at least 4 cm thick and leave the surface ready for laying tiles with the thin-bed method.

Materials:

- Absorbent and non-absorbent ceramic tiles. Porcelain tiles with a water absorption < 0.5% as per EN-ISO 10545-3.
- Glass mosaic.
- Natural stone and marble not prone to staining.

Substrates:

- Waterproofing sheets and paints.
- Slopes are needed on the waterproofing substrate.

super-drain

KEA		P/UK
B84901004	super-drain	158.10 p/roll

Packaging

Presentation	Europallet
15 m ² roll	135 m ² /pallet





concept systems

concept panels

concept panels	131
Fixing elements for concept panels	132
Technical features	138
General instructions for installation	138

concept shower trays

concept shower trays	141
Shower trays for squared outlets	143
Shower trays for linear outlets	145
Bespoke shower trays	147

concept showers

Altea concept shower	150
Victoria corner concept shower	150
Niágara concept shower	151
concept benches	151
Iguazú concept cabin	152

concept panel

concept **panels** are extruded polystyrene panels ready for laying wall tiles, mosaics or natural stone with cement-based adhesives. Polystyrene lightness and easy handling, as well as its mechanical resistance and damp resistance make this panel the perfect substrate for all kinds of environments where damp is present.

This kind of panel is available in thicknesses ranging from 4 to 80 mm and also in special precut boards that allow for a fast installation of curved shapes.



Features:

- Extruded polystyrene boards covered on both sides with waterproof cement mortar.
- Non-absorbent material. Its structure prevents water buildup. Resistant to dampness.
- Excellent surface for laying rectified tiles.
- Low thermal conductivity coefficient.
- Good soundproofing against impact noise.
- Easy handling and transport.
- Quick and clean installation.
- Resistant to microorganism attack.
- Inert, harmless, 100% recyclable material.
- Fire resistant: B1 as per DIN 4102.

Substrates:

- Usual indoor substrates in the building industry.
- Uncovered brick partition walls.
- Concrete floor slabs.
- Existing wall and floor tiles.
- Self-supporting indoors. Only 50 and 80 mm boards.

Recommended use:

- Preparation of substrates for ceramic tiles laying. Specially recommended in refurbishing jobs.
- Bathroom countertops and vanities in permanently wet areas.
- Bathroom partition walls and platforms.
- Bathtub panel and shower cabins.
- Shelves and panels attached to partition walls.
- Health resorts, saunas and spa premises.
- Thermal insulation of electric radiant heating floors.

Materials:

- Absorbent and non-absorbent ceramic tiles. Porcelain tiles with a water absorption < 0.5% as per EN-ISO 10545-3.
- Glass mosaic.
- Natural stone and marble not prone to staining.

concept panels

KEA	SAP		P/UK
B88000286	100103351	4 mm 1250 x 600	16.52 p/u
B88000287	100103352	6 mm 1250 x 600	16.52 p/u
B88000289	100103349	10 mm 2500 x 600	37.02 p/u
B88000288	100103350	20 mm 2500 x 600	38.78 p/u
B88000292	100103354	30 mm 2500 x 600	39.95 p/u
B88000293	100103355	50 mm 2500 x 600	46.19 p/u
B88000291	100103356	80 mm 2500 x 600	72.22 p/u

Packaging

u./pallet
150
150
120
100
68
40
24



Fixing elements for concept panels

concept fasteners

KEA	concept	P/UK
B88000002	50 mm U shape	12.21 p/u
B88000026	80 mm U shape	12.21 p/u
B88000029	50 mm H shape	24.53 p/u
B88000031	80 mm H shape	27.97 p/u
B88000003	50 mm T shape	21.87 p/u
B88000001	80 mm T shape	21.87 p/u
B88000030	50 mm L shape	21.87 p/u
B88000008	80 mm L shape	21.87 p/u

Packaging

Presentation
4 u. bag
4 u. bag
4 u. bag
4 u. bag
4 u. bag
4 u. bag
4 u. bag
4 u. bag



UK screws and washers

KEA		P/UK
B88000042	45 mm metal fastening	27.05 p/u
B88000017	130 mm plastic fastening	7.92 p/u
B88000028	130 mm plastic fastening	36.77 p/u
B88000021	80 mm plastic fastening	5.83 p/u
B88000013	80 mm plastic fastening	24.98 p/u

Packaging

Presentation
50 u. bag
10 u. bag
50 u. bag
10 u. bag
50 u. bag



Self-adhesive fiberglass mesh roll

KEA		P/UK
B88000012	self-adhesive fiberglass mesh	8.06 p/u
B88000009	self-adhesive fiberglass mesh	13.88 p/u

Packaging

Presentation
10 m roll
20 m roll



Polyurethane mastic

KEA		P/UK
B82401003	P-404 black	5,36 p/u

Packaging

Presentation
25 cartridges x box





Indoor partition walls

concept 50 and **concept 80** panels allow to create partition walls, in any size and share. Using them reduces installation times and provides a perfect substrate for laying rectified ceramics or glass mosaic.

concept panels

KEA		P/UK
B88000293	2.500 x 600 x 50	46.19 p/u
B88000291	2.500 x 600 x 80	72.22 p/u

Refer to union and fastening elements on page 114.



Bathtub skirts

concept 30 panels allow to create bathtub skirts in a fast and easy way. Specially recommended for whirlpool baths and in general for any kind of installation to which you need access once it has been installed.

There are adjustable height special pieces for the panel base.

KEA		P/UK
B88000292	concept 30 panel 2.500 x 600 x 30	39.95 p/u

Refer to union and fastening elements on page 114.





Platforms and steps

concept panels can replace, many kinds of internal walls and plinths, reducing installation times and improving the final result. Specially recommended in projects with limitations for use overload.

concept panels

KEA		P/UK
B88000292	2.500 x 600 x 30	39.95 p/u
B88000293	2.500 x 600 x 50	46.19 p/u
B88000291	2.500 x 600 x 80	72.22 p/u

Refer to union and fastening elements on page 114.



Furniture and countertops

concept panels can replace, many kinds of internal walls and plinths, reducing installation times and improving the final result. Specially recommended in projects with limitations where the presence of water advises against the use of wood.

There are reinforcement elements for the installation of countertops and shelves.

concept panels

KEA		P/UK
B88000288	2.500 x 600 x 20	38.78 p/u
B88000292	2.500 x 600 x 30	39.95 p/u
B88000293	2.500 x 600 x 50	46.19 p/u
B88000291	2.500 x 600 x 80	72.22 p/u

Refer to union and fastening elements on page 114.





Wall and floor covering

concept panels are an excellent solution for covering walls and floors prior to laying ceramics. Specially recommended in refurbishing jobs where, apart from preparing the substrate for laying ceramics, you need to waterproof and thermally isolate the substrate.

This kind of panel can be directly installed on the substrate with adhesive spots or installed on a plasterboard-type metallic structure.

concept panels

KEA		P/UK
B88000286	1.250 x 600 x 4	16.52 p/u
B88000287	1.250 x 600 x 6	16.52 p/u
B88000289	2.500 x 600 x 10	37.02 p/u
B88000288	2.500 x 600 x 20	38.78 p/u

Refer to union and fastening elements on page 114.



Technical features

Properties	Standard	Unit of measure	Value
Determination of deformation under specified compressive loads and temperature.	UNE EN 1605	deformation %	1.1 (mean value)
Compressive strength (for a 10% deformation)	UNE EN 826	kPa	80 to 210 197 (mean value)
Apparent density	UNE EN 1602	kg/m³	32.4 (mean value)
Bending strength	UNE EN 12089	kPa	2422
Tensile strength perpendicular face of panel.	UNE EN 1607	kPa	310 to 420 360 (mean value)
Long-term water absorption by immersion.	UNE EN 12087	kg/m²	0.76 (mean value)
Long-term water absorption by immersion.	UNE EN 12087	volume %	7.3 (mean value)
Water vapor permeability.	UNE EN 12086	μ (water vapor diffusion resistance)	44
Thermal conductivity.	UNE EN 12667	W/(mK)	0.0336
Working temperature range.		°C	-50/+75
Dimensional tolerance of panels.		mm	Thickness +/-2 Length +/-2 Width +/-2 Squareness +/-2 in 1000 mm
Fire resistance.	DIN 4102		B1 not easily flammable

General instructions for installation

- Measure accurately the surface to be covered and transfer the measures to the **concept** panel.
- Before installing the **concept** panel on the surface to be covered, clean and remove any element which could compromise the bonding.
- Depending on the panel thickness, cut with a cutter or a hand saw. Once cut, remove irregularities from the cut sides using a sanding paper.
- Use **super-one n**, type C2S1 FTE cement-based adhesive, to bond the **concept** panel on flat surfaces. On even surfaces, we recommend to use a notched trowel, while on uneven surfaces, the use of adhesive spots (5 spots/m²) is recommended.
- Use **concept 45 metal fasteners** (fixing screws) for installing panels on to wooden substrates (5 fasteners/m²). Specially recommended on plywood and chipboards substrates.
- Use **p-404**, polyurethane glue on the joint of panels, sealing of joints and bonding of panels.
- Use **plastic fasteners** (fixing screws) to reinforce cross union of panels. Specially recommended for corners.
- Use the self-adhesive fiberglass mesh to reinforce unions between boards and cover with a layer of **super-one n** adhesive. In the case you need to waterproof the joint, use **sylastic** waterproof mortar.
- In partition walls, use different kinds of **concept** unions to fix the boards to the substrate. We recommend the use of a U type union every 60 cm.
- In partition walls, we recommend to use an H type union every 100 cm to reinforce the union between adjacent boards.
- Use cut pieces from a **concept** panel to create structures and shapes to be covered with ceramics or mosaic. Specially recommended in platforms, steps, shelves and furniture in general.
- Once the **concept** installed, lay the chosen wall covering with **super-one n** adhesive and seal the joints with **colorstuk rapid**, type CG2 colored grout for joints. In Turkish baths and environments with high concentrations of water vapor, replace grout with **epotech aqua** epoxy putty.



concept shower trays

concept shower trays are a custom shower tray system, ready to be tiled with ceramics, natural stone or other materials. They are designed to be flush fitted and can be swiftly and easily assembled with no mess.

They can come with installation kits for each model and size.

concept shower trays

concept shower trays are a prefabricated system for creating built in shower trays. They include the slopes for the correct water drainage, as well as the drain and the waterproofing system. This system is supplied ready to use, which reduces working times while guarantees a perfect substrate for laying mosaic, natural stone or ceramics.

concept shower tray is light, resistant and safe, reason why it is specially recommended in bathroom refurbishing jobs.



Features:

- Prefabricated shower tray made of extruded polystyrene covered with cement mortar.
- It includes slopes for water drainage.
- Waterproofing: covering consisting of waterproof mortar.
- Available in two options:
 - **Standard concept shower tray:** 45 mm high
 - **Special concept shower tray:** 22 mm high
- Available for square as well as for linear drains.
- Compression resistance (10% crush risk): ASTM D 1621 371 kN / m²
- Initial thermal conductivity: BS EN 13164 0.036 W/m°K
- Flammability: BS 476, part 5 P
- Impact noise reduction: BS-ISO 140-8 dLw=21

Recommended use:

- Specially designed for waterproofing built in showers.

Materials:

- Absorbent and non-absorbent ceramic tiles. Porcelain tiles with a water absorption < 0.5% as per EN-ISO 10545-3.
- Glass mosaic.
- Natural stone and marble not prone to staining.

Substrates:

- Concrete floor slabs.
- Screeded floors.
- Wooden floors
- Tongue and groove wooden floors

concept shower tray selection guide

1. First of all, select the kind of drain:

- Squared drain
- Linear drain

2. Depending on the choice of installation, select the type of **concept** shower tray to be used:

- Level access installation: **Special concept shower tray**
- Step up or raised installation: **Standard concept shower tray**

3. Select the drain position:

- COR: Drain in a corner.
- CENT: Drain in a central position.
- LAT: Drain in off-center position.

4. Select the shower tray shape:

- Squared shower tray.
- Rectangular shower tray.

5. Choose the shower tray from the available sizes.

In the case that the available sizes do not fit in the project needs, there is the possibility of making custom shower trays.

6. For shower trays with linear drain, select the type of grate:

- Steel grate
- Tileable steel grate

7. For shower trays with squared drain, select the drain:

- Vertical drain
- Horizontal drain

For shower trays with squared drain, you will need two references to place an order:

- Reference for the shower tray
- Reference for the drain and grate

For shower trays with linear drain, you will need three references to place an order:

- Reference for the shower tray
- Reference for the drain
- Reference for the grate




45 mm shower trays for squared outlets

These shower trays feature a 45 mm thickness.
Does not include the **drain** and the **grate**.

concept shower trays


COR	Squared shower tray corner drain position		
KEA	Square tray	P/UK	
B88000480	900x900x45	224.05 p/u	
B88000466	1000x1000x45	236.93 p/u	
B88000496	1200x1200x45	251.67 p/u	
B88000454	1500x1500x45	380.95 p/u	

Packaging
Presentation
Shower tray
Shower tray
Shower tray
Shower tray




CENT	Squared shower tray center drain position		
KEA	Square tray	P/UK	
B88000469	900X900x45	224.06 p/u	
B88000455	1000x1000x45	237.17 p/u	
B88000475	1200x1200x45	251.67 p/u	
B88000460	1500x1500x45	337.53 p/u	

Packaging
Presentation
Shower tray
Shower tray
Shower tray
Shower tray




LAT	Rectangular shower tray off-center drain position		
KEA	Rectangular shower tray	P/UK	
B88000487	1200X900x45	263.78 p/u	
B88000486	1200X1000x45	284.73 p/u	
B88000477	1400X900x45	287.90 p/u	
B88000457	1500X900x45	298.03 p/u	
B88000465	1600X900x45	307.44 p/u	
B88000414	1800X900x45	334.42 p/u	

Packaging
Presentation
Shower tray
Shower tray
Shower tray
Shower tray
Shower tray
Shower tray



CENT	Rectangular shower tray center drain position		
KEA	Rectangular shower tray	P/UK	
B88000478	1000X800x45	221.88 p/u	
B88000462	1200X900x45	266.37 p/u	
B88000468	1200X1000x45	284.73 p/u	
B88000491	1400X900x45	287.90 p/u	
B88000453	1500X900x45	298.03 p/u	
B88000461	1600X900x45	307.42 p/u	
B88000456	1800X900x45	506.41 p/u	

Packaging
Presentation
Shower tray
Shower tray
Shower tray
Shower tray
Shower tray
Shower tray



Vertical or horizontal drain with standard grate

Square gratings		
KEA	Square grating	P/UK
B82902060	Horizontal drain	67.48 p/u
B82902061	Vertical drain	59.61 p/u
100119594	Pipe converter for vertical drain	8.95 p/u

Vertical drain includes standard squared grate. Pipe converter not included.
Horizontal drain includes standard squared grate and pipe converter.

Packaging
Presentation
1 box
1 box
1 box




22 mm shower trays for squared outlets

These shower trays feature a 22 mm thickness.
Does not include the **drain** and the **grate**.

concept shower trays


COR	Squared shower tray corner drain position		
KEA	Square tray	P/UK	
B88000567	900X900x22	235.38 p/u	
B88000523	1000X1000x22	244.38 p/u	
B88000504	1200X1200x22	280.22 p/u	
B88000566	1500X1500x22	382.12 p/u	

Packaging
Presentation
Shower tray
Shower tray
Shower tray
Shower tray




CENT	Squared shower tray center drain position		
KEA	Square tray	P/UK	
B88000561	900X900x22	235.38 p/u	
B88000499	1000X1000x22	244.38 p/u	
B88000516	1200X1200x22	282.97 p/u	
B88000503	1500X1500x22	385.87 p/u	

Packaging
Presentation
Shower tray
Shower tray
Shower tray
Shower tray




LAT	Rectangular shower tray off-center drain position		
KEA	Rectangular shower tray	P/UK	
B88000565	1200X900x22	256.39 p/u	
B88000517	1200X1000x22	261.53 p/u	
B88000528	1400X900x22	281.25 p/u	
B88000539	1500X900x22	291.54 p/u	
B88000563	1600X900x22	304.41 p/u	
B88000579	1800X900x22	334.42 p/u	

Packaging
Presentation
Shower tray
Shower tray
Shower tray
Shower tray
Shower tray
Shower tray



CENT	Rectangular shower tray center drain position		
KEA	Rectangular shower tray	P/UK	
B88000505	1000X800x22	231.52 p/u	
B88000519	1200X900x22	231.52 p/u	
B88000521	1200X1000x22	258.99 p/u	
B88000543	1400X900x22	256.39 p/u	
B88000577	1500X900x22	297.21 p/u	
B88000545	1600X900x22	307.84 p/u	
B88000536	1800X900x22	327.56 p/u	


Packaging
Presentation
Shower tray
Shower tray
Shower tray
Shower tray
Shower tray
Shower tray



Waterproofing kit

Waterproofing kit	
KEA	P/UK
B85900020	110.35 p/u

The mounting kit includes:
1 **p-404** tube + **imperband n** 5 m roll + 2 **corners** + 10 ml of **waterproof band**.



All the standard **concept** shower trays have available a 55 mm thickness special piece to increase the height of the shower tray and cover sewer and drain. Check conditions with your sales representative from PORCELANOSA GRUPO.


45 mm shower trays for linear outlets

These shower trays feature a 45 mm thickness.
Does not include the **grate**.

concept shower trays


LINEAR LAT Q	Squared linear shower tray standard drain	
KEA	Square tray	P/UK
B88000546	900X900x50	240.09 p/u
B88000510	1000x1000x50	270.11 p/u
B88000535	1200x1200x50	295.83 p/u
B88000525	1500x1500x50	415.23 p/u

Packaging
Presentation
Shower tray
Shower tray
Shower tray
Shower tray




LINEAR CENT Q	Squared linear shower tray center drain position	
KEA	Square tray	P/UK
B88000549	900X900x50	240.09 p/u
B88000512	1000x1000x50	267.48 p/u
B88000520	1200x1200x50	292.95 p/u
B88000537	1500x1500x50	415.23 p/u

Packaging
Presentation
Shower tray
Shower tray
Shower tray
Shower tray




LINEAR LAT R	Rectangular linear shower tray off-center drain	
KEA	Rectangular shower tray	P/UK
B88000569	1200X900x50	250.50 p/u
B88000533	1200X1000x50	254.75 p/u
B88000570	1400X900x50	278.68 p/u
B88000532	1500X900x50	284.47 p/u
B88000568	1600X900x50	288.70 p/u
B88000426	1800X900X50	334.42 p/u

Packaging
Presentation
Shower tray
Shower tray
Shower tray
Shower tray
Shower tray
Shower tray



LINEAR CENT R	Rectangular linear shower tray center drain position	
KEA	Rectangular shower tray	P/UK
B88000509	1000X800x50	231.52 p/u
B88000548	1200X900x50	250.50 p/u
B88000515	1200X1000x50	246.26 p/u
B88000557	1400X900x50	275.97 p/u
B88000531	1500X900x50	284.47 p/u
B88000538	1600X900x50	288.70 p/u
B88000562	1800X900X50	334.42 p/u

Packaging
Presentation
Shower tray
Shower tray
Shower tray
Shower tray
Shower tray
Shower tray



Linear drain

KEA	Linear grate	P/UK
B82902064	Steel grate 700 mm	79.38 p/u
B82902063	Tileable steel grate 700 mm	105.00 p/u
B82902147	Black glass grate 700 mm	266,71 p/u
B82902151	Black glass grate 900 mm	335,29 p/u
B82902149	Grey glass grate 700 mm	266,71 p/u
B82902145	Grey glass grate 900 mm	335,29 p/u
B82902146	White glass grate 700 mm	266,71 p/u
B82902152	White glass grate 900 mm	335,29 p/u
B82902148	Beige glass grate 700 mm	266,71 p/u
B82902150	Beige glass grate 900 mm	335,29 p/u
B82902163	UK linear drain frame	37.19 p/u

Presentation
1 box
1 box
1 box
1 box
1 box
1 box
1 box
1 box
1 box
1 box
1 bag




22 mm shower trays for linear outlets

These shower trays feature a 22 mm thickness.
Does not include the **grate**.

concept shower trays


LINEAR LAT Q	Squared linear shower tray standard drain	
KEA	Square tray	P/UK
B88000556	900X900x22	256.39 p/u
B88000500	1000X1000x22	265.65 p/u
B88000501	1200X1200x22	301.45 p/u
B88000506	1500X1500x22	427.88 p/u

Packaging
Presentation
Shower tray
Shower tray
Shower tray
Shower tray




LINEAR CENT Q	Squared linear shower tray center drain position	
KEA	Square tray	P/UK
B88000571	900X900x22	256.39 p/u
B88000507	1000X1000x22	263.07 p/u
B88000514	1200X1200x22	304.41 p/u
B88000551	1500X1500x22	427.88 p/u

Packaging
Presentation
Shower tray
Shower tray
Shower tray
Shower tray




LINEAR LAT R	Rectangular linear shower tray off-center drain	
KEA	Rectangular shower tray	P/UK
B88000542	1200X900x22	270.96 p/u
B88000554	1200X1000x22	275.25 p/u
B88000553	1400X900x22	298.40 p/u
B88000529	1500X900x22	307.84 p/u
B88000552	1600X900x22	321.56 p/u

Packaging
Presentation
Shower tray
Shower tray
Shower tray
Shower tray
Shower tray



LINEAR CENT R	Rectangular linear shower tray center drain position	
KEA	Rectangular shower tray	P/UK
B88000544	1000X800x22	247.81 p/u
B88000527	1200X900x22	270.96 p/u
B88000524	1200X1000x22	272.57 p/u
B88000498	1400X900x22	269.25 p/u
B88000522	1500X900x22	307.40 p/u
B88000550	1600X900x22	321.56 p/u
B88000558	1800X900x22	342.56 p/u

Packaging
Presentation
Shower tray
Shower tray
Shower tray
Shower tray
Shower tray
Shower tray



Square gratings

KEA	Linear drain	P/UK
B82902062	Horizontal drain with pipe converter	89.76 p/u

The reference Horizontal drain with pipe converter does not include any steel grate.

Packaging
Presentation
1 box



All the standard **concept** shower trays have available a 55 mm thickness special piece to increase the height of the shower tray and cover sewer and drain. Check conditions with your sales representative from PORCELANOSA GRUPO.



Bespoke shower trays


If you need a shower tray with certain dimensions or shape that cannot be found in our standard shower trays range, **butech** can make the shower tray with the shape and dimensions you need.

Just send us a drawing with the dimensions and shape you want for your shower tray and we will give you a price and a delivery date. If you agree, we will make your custom shower tray.

For making a square or rectangular shower tray, we need the following information:

- Shower tray dimensions:
 - Long side xP
 - Wide side yP
 - Thickness: 45 mm (standard tray)
- Draining/grating type
 - Square grating choose between vertical and horizontal drain
 - Linear grating choose between steel grate and tileable steel grate
- Drain position
 - Long side xS
 - Wide side yS

All dimensions must be entered in millimeters.



All the custom **concept** shower trays have available a 55 mm thickness special piece to increase the height of the shower tray and cover sewer and drain. Check conditions with your sales representative from PORCELANOSA GRUPO.

In case you need a shower tray with a non orthogonal shape, check with **butech** sales department.




Altea cabin

Shower cabin with circular tray with 100 cm radius and 200 cm height. Specially recommended for health resorts and outdoors.

This circular shower includes the following elements:

- Circular shower tray.
- Panels for circular walls.
- Drain system.



Altea concept shower



KEA		P/UK
B88000447	2.000 x 1000 x 1000	1480.61 p/u

Victoria corner cabin

Shower cabin with circular tray with 100 cm radius and 200 cm height. Specially recommended for bathroom refurbishings.

This circular shower includes the following elements:

- Circular shower tray
- Panels for circular walls
- Drain system.



Victoria corner concept shower


KEA		P/UK
B88000445	1.100 x 1.100 x 2.000	1652.95 p/u

Niágara cabin

Snail shaped shower cabin with 59 cm entrance and 200 cm high. Specially recommended for health resorts and outdoors.


This snail-shaped shower includes the following elements:

- Shower tray
- Panels for circular walls
- Imperband kit (waterproofing + outlet)



Niágara concept shower		
KEA		P/UK
B88000448	1890 x 1515 x 2000 right entrance	2266.07 p/u

concept benches



concept benches		
KEA		P/UK
B88000446	1000X484X484 backless bench	259.75 p/u
B88000451	1000X600X870 backed bench	430.01 p/u


Iguazú cabin

Rectangular cabin, 180 cm long, 100 cm wide and 228.9 cm high, with 60 cm entrance. Specially recommended for health resorts.


This shower includes the following elements:

- Shower tray.
- Panels for walls.
- concept bench.
- Flat ceiling.
- Imperband kit (waterproofing + outlet).

Taps, main door, manhole cover and plumbing not included.



Iguazú vapor cabin		
KEA		P/UK
B88000449	1800X1000X2300	4175.87 p/u





Product family

Product name

Image of a possible use of the product

Cement-based adhesives

super-one n

super-one n is a type C2 FTE S1 high-performance cement-based adhesive, as per EN 12004, ready for traffic after 4 hours. Specially recommended for quick installation and use of ceramic tiles and natural stone.

It solves the need of quick installation of any kind of format and ceramic tile, including porcelain tiles. Ready for traffic in just 4 hours, this adhesive can be used to lay ceramic tiles and natural stone in environments where high mechanical performance is needed, such as commercial or industrial flooring or flooring with radiant heating. Waterproof and frost-resistant.

ston-ker

natural stone

large format

plasterboard

plywood

tiles existing

Marble floors

Product name

Product features

Product Coverage

Product certifications and standards

Product name

Value

super-one n

Features:

- Cement-based, single component adhesive.
- Ready for traffic in just 4 hours.
- Excellent adhesion. Flexible.
- Fine texture mortar, with excellent mixing and application features.
- High initial adhesion and no sagging.
- Extended working times. Open time higher than 30 min.
- Application thickness up to 10 mm.
- Frost-resistant.
- Mixing water: 6.0 - 6.50 l per 25 kg bag

Coverage:

• 20 x 30 cm tile	3 kg / m ²
• 30 x 30 cm tile	3 kg / m ²
• 30 x 60 cm tile	4 kg / m ²
• 44 x 44 cm tile	4 kg / m ²
• 30 x 90 cm tile	5 kg / m ²
• 44 x 66 cm tile	5 kg / m ²
• 60 x 60 cm tile	6 kg / m ²
• 60 x 120 cm tile	6 kg / m ²

Certifications/Standards:

BS EN 12004 C2 FTE S1

super-one n

KEA		P/UK
B12909010	super-one n white	27.17 p/bag
B12909011	super-one n grey	18.20 p/bag

Recommended uses:

- Laying of ceramics in refurbishing jobs.
- Indoor large format ceramic tile coverings.
- Indoor and outdoor porcelain tile coverings.
- Plywood substrates.
- High traffic floor tiles.
- Floor tiles on radiant heating.
- Pools and damp environments.
- On bonded facades, replace mixing water with **unilax** additive.

Materials:

- Large format ceramics.
- Porcelain tiles with a water absorption < 0.5% as per EN-ISO 10545-3.
- Glass mosaic.
- Natural stones and marble without risk of deformation by water absorption.
- In installations of DQS slabs and other kinds of marble agglomerate, mix with **unilax** latex.

Suitable surfaces:


- Cement covered floors and walls.
- Concrete slabs.
- Plasterboards.
- Plywood boards.
- On **fomopac r** replace mixing water with **fomolax**.
- Existing wall tiles.
- On anhydrite or plaster substrates apply **universal bonding agent**.

Packaging

Presentation	Europallet
25 kg bag	1,000 kg/pallet
25 kg bag	1,000 kg/pallet

Product picture

59



International Showrooms

A CORUÑA
SANTIAGO DE COMPOSTELA -PORCELANOSA
General Pardiñas, 13-Bajo.
T:981 569 230 - F:981 569 230
SANTIAGO DE COMPOSTELA - PORCELANOSA
Rúa Polonia, Pol. Comercial Costa Vella
T:981 897 595 - F:981 530 901
SANTIAGO DE COMPOSTELA - PORCELANOSA
Rua Clara Campoamor, 13-15 (Montouto) - Teo
T:981 509 270 - F:981 819 334
A CORUÑA - SUMINISTROS VIA-MAR
Médico Rodríguez 18-20. T:981 279 431 - Fax: 981 279 431
BETANZOS - SUMINISTROS VIA-MAR
Avenida Fraga Iribarne, s/n. T:981 772 190 - Fax: 981 774 257
FERROL - NEIRA & ORTEGAL S.L.
Carretera Cataboís, 258. T:981 326 532 - F:981 324 951
ORTIGUEIRA - NEIRA & ORTEGAL S.L.
Carretera C-642 s/n, Cuiña. T:981 400 880 - F:981 400 883
PUEBLA DEL CARAMINAL - PEREZ DOMINGUEZ PUEBLA S.L.
Angustia, 30. T:981 830 214 - F:981 107 219

ÁLAVA
VITORIA-GASTEIZ - JORGE FERNÁNDEZ
Los Herrán, 30. T:945 254 755 - F:945 259 668
VITORIA-GASTEIZ - JORGE FERNÁNDEZ
Polígono Jundiz, Paduleta, 53. T:945 244 250 - F:945 229 321

ALBACETE
ALBACETE - PORCELANOSA
Avda. Gregorio Arcos, 32 (Polígono Campollano)
T:967 243 658 - F:967 193 465
VILLARROBLEDO - OLIVARES MAT. CONSTRUCCIÓN
Avda. Reyes Católicos, 168. T:967 138 105 - F:967 138 023

ALICANTE
ALICANTE - PORCELANOSA
Pol. Las Atalayas, Parcela VI. Calle del Franco.
T:965 109 561 - F:965 106 965
SAN JUAN - PORCELANOSA
Carretera Valencia, km 88. T:965 656 200 - F:965 655 644
BENISA - HIJOS DE JUAN RIBES
Avda. de la Estación, 2. T:965 730 419
ELCHE - PORCELANOSA
Avda. Alicante, 105. T:966 610 676 - F:966 610 700
JAVEA - AZULEJOS JAVEA
C/Liverpool, 4. T:965 791 036
ALTEA - ELDECO
Ctra. N-332 Partida Cap. Blach, 38 A.
T:966 874 360 - F:966 873 543
DENIA - NOVA RECAL
Avda. Alcoy, 2. T:965 786 034
ALCOY - SANEAMIENTOS COLON S.A.
Avda. De la Alameda, 10. T:965 331 891 - F:965 524 210

ALMERÍA
ALMERÍA - PORCELANOSA
Avenida Mediterráneo, 2º tramo. T:950 143 567 - F:950 142 067
VICAR - PORCELANOSA
Centro Comercial Viapark, Parcela 1. T:950 325 575 - F:950 338 651

ASTURIAS
OVIEDO - PORCELANOSA
Pol.Espíritu Santo C/ Dinamarca s/n. T:985 791 526 - F:985 985 963
GIJÓN - PORCELANORTE
Menéndez Pelayo 30. T:984 396 462

ÁVILA
ÁVILA - PAVIMARSA
Pol.industrial Vicolozano -Parcela 2. T:920 259 820 - F:920 259 821

BADAJÓZ
MÉRIDA - PORCELANOSA
Avenida Reina Sofía, 8. T:924 330 218 - F:924 330 315
BADAJÓZ - GALLERY CERAMIC
Carretera N-V Madrid-Lisboa, km 399. T:924 229 144 - F:924 229 143
HERRERA DEL DUQUE - JUBEL
Avda. Juan Carlos I, s/n. T:924 145 372
ZAFRA - MUNDO OBRAS
Bodion, 27. Pol. Ind. Los Caños. T:924 551 264 - F:924 551 264

BARCELONA
L'HOSPITALET DE LLOBREGAT - PORCELANOSA
Ciències, 65. Gran Via l'Hospitalet. T:932 642 500 - F:932 007 036
SANT SADURNI D'ANOIA - COMERCIAL STC
Rambla Generalitat, 59. T:931 593 137 - F:931 615 015
BARCELONA - AZULEJOS SAN ANDRÉS
Plaça Mossen Clapes 2-3. T:933 455 102 - F:933 461 015
CORNELLÀ - LOFT CUINA
La Miranda, 6-8. T:934 743 793 - F:937 741 305
MOLINS DE REI - HIJO DE FERNANDO ROCA
Pla, 9. T:936 681 434 - F:936 801 458
CABRERA DE MAR - ORMAT
Ctra. Vilassar-Argentona Km.1. T:937 591 139 - F:937 502 076
SANT POL DE MAR - AMARGANT
Passeig Parc, 1. T:937 600 112 - F:937 600 411
PINEDA DE MAR - AMARGANT
Santiago Rusiñol, 96. T:937 671 416 - F:937 627 488
MATARÓ - ROSA JORDANA RABETLLAT
Montserrat, 7. T:937 903 089 - F:937 903 089

VILANOVA DEL CAMÍ - ROSA JORDANA RABETLLAT
Montserrat, 108-111. T:938 060 240 - F:938 060 239
TARADELL - JODIL
Ctra. Vic, km 5,8. T:938 800 800 - F:938 126 054
GRONELLA - ANTONI PONT
Farguell, 31. T:938 228 088 - F:938 250 786
SANT PEDOR - CONSAN
Pol. Ind. Les Verges. T:938 320 669 - F:938 320 669
SANT BOI DE LLOBREGAT - GARRO
Ctra. Creu de Clafell, Km 10,7. T:936 545 952 - F:938 400 620
CANOVELLES - COMERCIAL MAESTRO CANET
Pol. Can Castells, nave 7-8. T:938 466 568 - F:938 409 216
TORELLÓ - JOAN DOT
Ter, 50. T:938 504 646 - F:938 504 286
TORELLÓ - ARQUIMATT MATERIALS I DECORACIÓ
Sant Jordi, 16. T:679531877
CALAF - PLANELL
Ctra. Manresa, Km 31. T:938 698 750 - F:938 600 181
PALAU SOLITA I PLEGAMANS - COMERCIAL SOLSAN
Cami Reial, 109. T:938 648 125 - F:938 649 617
VIC - CORRETTJA
Mas de Bigas, 8-26. T:938 854 261 - F:938 894 733
ST. PERE DE RIBES - SUMICO
Ctra. Barcelona C-246, Km 42,4. T:938 933 066 - F:938 936 004
CUBELLES - MA-CO
Penedes / La Selva Pol. Ind. Les Salines.
T:938 954 141 - F:938 954 142
MATARÓ - MARESMÉ GRES
Sant Isidor, 78. T:931 615 015
CASSERES - MATERIALS CASSERRES
San Rafael. T:938 213 770
TIANA - BADALONA GRESS
CR B-500, Km 3,2. T:933 950 311 - F:934 650 758
VILAFRANCA DEL PENEDES - FERRET I CAULLERAS
Sant Martí, 2. T:938 170 353
SANTA MARIA PALAUJORDERA - RIERA MAGATZEM CONSTRUCCIÓ
Antiga Via Provincial, 2. T:938 670 764

BURGOS
MIRANDA DE EBRO - JORGE FERNÁNDEZ
Camino Fuente Basilio, S/N. T:947 323 351 - F:947 314 589
BURGOS - BIGMAT FONTECHA
Alcalde Martin Cobos, naves 5 y 6. T:947 485 153 - F:947 483 941
ARANDA DE DUERO - GRUPO DISMAR DUERO
Avda. Portugal, Parcela 17. T:947 513 28 - F:947 513 349

CÁCERES
MORALEJA - BIGMAT CAYUELA
Avda. Extremadura, 26. T:927 515 198 - F:927 147 266
VALENCIA DE ALCANTARA - BIGMAT TEJEDA
Pol. Ind. Cerro San Francisco, s/n. T:924 410 155 - F:927 668 016
CÁCERES - PORCELANOSA
Avda. Juan Pablo II, 130. T:927 236 337 - F:927 236 205
PLASENCIA - GEMAT
Avda. Ambroz, 5-7. T:927 316 828
MONTEHERMOSO - GEMAT
Ctra. Pozuelo de Zazon, s/n. T:927 430 597
NAVALMORAL DE LA MATA - MAGERVYSA
Rio salor, 83. T:927 535 234 - F:927 535 575

CÁDIZ
OLVERA - ALMECOR
Avda. Julian Besteiro, 29. T:956 120 776 - F:956 120 776
JEREZ DE LA FRONTERA - PORCELANOSA
Parque Empresarial Avda De la Ilustración, 1.
T:956 187 160 - F:956 302 904
UBRIQUE - DOCURRI
Paseo del Prado 38-40. T:956 462 263 F:956 462 623
ALGECIRAS - PORCELANOSA
Ctra. Málaga, Km 190. T:956 635 282 - F:956 635 285
VILLAMARTÍN - AZULGRIF
Rosario, 9. T:956 730 687 - F:956 730 911
PUERTO SANTA MARIA - PORCELANOSA
Pol. El Palmar. Ctra. Madrid-Cádiz, Km 653,2
T:956 540 084 - F:956 872 464
SAN FERNANDO - PORCELANOSA
Pol. Tres Caminos, S/N. T:956 592 360 - F:956 884 677

CANTABRIA
SANTANDER - PORCELANOSA
Avenida Parayas, s/n. T:942 352 510 - F:942 352 638
TORRELAVEGA - PORCELANOSA
Boulevard Demetrio Herrero, 1. T:942 835 026 - F:942 881 787

CASTELLÓN
CASTELLÓN DE LA PLANA - PORCELANOSA
Asensi, 9. T:964 239 162 - 964 238 930
VILLARREAL - PORCELANOSA
Ctra.Vila-real - Puebla de Arenoso (CV-20) Km. 0,7
T:964 506 800 - F:964 525 418
VINARÓZ - PORCELANOSA
Carretera N-340, km 1.050,1. T:964 400 944 - F:964 400 650

CEUTA
CEUTA - BAEZA.
Ampliación muelle de Poniente, 96. T:956 511 312 - F:956 511 309

CIUDAD REAL
CIUDAD REAL - PORCELANOSA
Ctra. de Carrión, Km.11. T:926 251 730 - F:926 255 741

CÓRDOBA
CÓRDOBA - PORCELANOSA
Ctra. Nacional IV Km.404. Pol. de Torrecilla.
T:957 760 024 - F:957 760 123
POZOBLANCO - ACAÑAS CABRERA
Ctra. pozoblanco-Alcaracejos Km 3,3
T:957 772 999 - F:957 131 170
VILLA DEL RIO - JUAN PRIETO E HIJOS S.L.
Ctra. Bujalance, s/n. T:957 177 693 - F:957 177 335
HINOJOSA DEL DUQUE - HORMIGONES SANFRANCISCO
Velázquez, 13. T:957 140 181
PRIEGO DE CÓRDOBA - SANEAMIENTO Y REVESTIMIENTOS JULIO
Camino Fontanal s/n. T:957 540 943
MONTILLA - ALMACENES MANOLIN Y LUIS S.L.
Avda. Andalucía, 24. T:957 651 509 - F:957 653 253
LUCENA - AUDOS CERÁMICAS
Ejido Plaza de Toros, 35. T:957 516 572.
CASTRO DEL RIO - COMERCIO DE MATERIAL
DE CONSTRUCCIÓN Y TRANSPORTES
Ronda de Jesús, 68. T:957 372 775 - F:957 372 775

CUENCA
CUENCA - VICOSAZ
Hermanos Becerril, 6 bajo. T:969 233 200 - F:969 234 475
CASAS DE HARO - MAT. CONST. MARTINEZ ORTEGA
Dos de Mayo, 28. T:969 380 708 - F:969 380 708
TARANCÓN - VICENTE DE LOS RIOS S.A.
Avda del Progreso, 19. T:969 321 323 - F:969 321 334
VILLANUEVA DE LA JARA - ALMACENES PAÑOS S.L.
Camino de Rubielos, 8. T:967 498 000 - F:967 498 000

GERONA
BLANES - BRECOR SL
Ctra.Tordera,79. T:972 336 062 - F:972 358 482
PALAMOS - TG NOVA ARQUITECTURA
Avgda. Catalunya, 91. T:972 312 250 - F:972 312 249
PALOL D'ONYAR-QUART - OLIVERAS
Ctra. Comarcal C-250 Km. 4,3. T:972 468 119 - F:972 468 123
SANT FELIU DE GUIXOL'S - GINESTA
Santa Magdalena, 11. T:972 320 529 - F:972 321 616
LLORET DE MAR - CARMONA
Ctra. Lloret Vidrere Km2,1. T:972 372 710 - F:972 349 763
GIRONA - GIROP
Llora, 5. T:972 393 200 - F:972 393 071
SALT - FULCARA BRUGUE XAVIER
Rafael Maso, 56. T:972 234 591 - F:972 402 284
CORNELLÀ DEL TERRI - OLIVERAS
Ctra. Girona-Banyoles, km 12,8. T:972 594 131 - 972 594 552
ESCLANYA BEGUR - MATERIALS CREIXELL
Palafrugel Regencos. Pol. Ind. Riera Esclanya, 1. T:972 300 628
FIGUERES - OLIVERAS
Ctra. N-II, km 759. T:972 672 259 - F:972 672 255
VILA-SACRA - FRIAS MATERIALS
Castello, 72. T:972 670 073 - F:972 673 071
LES PRESSES - OLIVERAS
Pol. Ind Les Prespes, parcel.la 20. T:972 694 704 - F:972 693 003
CANET DE TALLADA - SERVIMAT INICIATIVES
Ctra. C-31 Km 354. T:972 780 524 - F:972 780 827
ARBUCIES - ARC ARBUCIES CERAMIQUES
Pol. Ind. Cal Xic-Parc, 4. T:972 162 364 - F:972 860 954
SARRIÀ DE TER - FERRER CERVIA
Avda. França, 192. T:972 173 442 - F:972 173 456
MONT-RAS - MERCAMAT
Ctra. C-31 Km 329,8. T:972 612 027 - F:972 302 146

GRANADA
ARMILLA - TECMACER
Avenida San Rafael. (Junto Sprinter).
T:958 253 081 - F:958 183 367

GUIPÚZCOA
SAN SEBASTIÁN - JORGE FERNÁNDEZ
Polígono Belartzat. Fernando Mújika, 15.
T:943 376 966 - F:943 376 841

HUELVA
HUELVA - PORCELANOSA
Ctra. Tráfico Pesado, s/n Pol. La Paz.
T:959 543 600 - F:959 237 951

HUESCA
HUESCA - PORCELANOSA
Pol. Sepes. C/ Ronda la Industria 1-3 nave C.
T:974 242 738 - F:974 242 676
FRAGA - BERGES CENTRO COMERCIAL
Avda. Aragón, 70. T:974 471 439 - F:974 471 439
AINSA - COMERCIAL CAMPODARVE
Pol. Ind. Sobrarbe, naves 11 y 12
T:974 500 267 - F:974 500 865

ILLES BALEARS
PALMA DE MALLORCA - PORCELANOSA
Gran Via Asima, 21 Pol. Son Castelló.
T:971 430 667 - F:971 297 094

INCA (MALLORCA) - PORCELANOSA
Pagesos s/n. Pol. Inca. T:971 507 650 - F:971 507 656
LLUCMAJOR (MALLORCA) - MAGATZEM SES FORQUES
Doctor Fleming, 10. T:971 662 114 - F:971 662 816

International Showrooms

SOLLER - PORCELANOSA
Del Mar,193. T:971 630 219
MANACOR- PORCELANOSA
Via Palma, 102. T:971 554 502
CALA D' OR- MACODOR
Ctra. Calonge-Cala D'or, Km 1,5. T:971 658 210
SANT RAFAEL-SANT ANTONIO- PORCELANOSA
Avda.Llauradors,7.Pol.MonteCristo.T:971317292-F:971317293

JAÉN
JAÉN - PORCELANOSA
Polígono Olivares. Carretera Bailén-Motril, km 323.
T:953 280 757 - F:953 284 035
ALCALA LA REAL - PAVIMENTOS AZUGRISA
Polígono Ind. Fre. Granada Vial II. T:953 582 963
BEAS DE SEGURA - GRUPO PEREA MORANTE S.L.
Polígono El Cormicabral, parcela 517 T:953 424 565
HUELMA - VIFERSAN S.L.
Virgen de la Fuensanta, 61. T:953 391 413
LINARES - HERNÁNDEZ GÁMEZ S.L.
Ctra. Torreblascopedro, s/n. T:953 693 423 - F:953 693 444
ÚBEDA - HERNANDEZ GAMEZ
Avenida de la libertad, 88. T:953 795 168 - F:953 795 168
VILLACARRILLO - MAT. CONST. Y SAN. HIJOS MARTIN SANCHEZ
C/ José Rodero Mataran, 53. T:953 454 167

LA RIOJA
LOGROÑO - RIOJACER
Avenida de Burgos, 43-45. T:941 286 021 - F:941 202 271

LAS PALMAS
LAS PALMAS DE GRAN CANARIA - PORC. Y PAV. CANARIOS
Avenida Mesa y López, 61. T:928 472 949 - F:928 472 944

LEÓN
SAN ANDRÉS DE RABANEDO - PORCELANOSA
Ctra León-Astorga, km 3,5. - San Andrés de Rabanedo -
T:987 801 570 - F:987 801 475
PONFERRADA - DISEÑARTE BIERZO S.L.
Avda. Galicia 380 - T:987 455 870

LÉRIDA
EL PONT DE SUERT - PRETENSATS RIBERA
Ctra. N-230 Km. 124,5. T:973 690 063 - F:973 690 400
LA SEU D'ULLEIJA - MATERIALS PIRINEU
Ctra. de Urded, 28. T:973 351 850 - F:973 353 410
LLEIDA - MATERIALS GERMAN'S MAURI
Príncipe Viana, 36. T:973 232 139 - F:973 247 943
VIELHA - PRETENSATS RIBERA
Ctra. França, 40 (Mig Aran). T:973 641 460 - F:973 642 271
TARREGA- NOUMAG
Júpiter,7 (Pol. Ind. La Canaletta). T:607 497 330
BALAGUER - J.FARRÉ
Urgell, 39. T:973 445 765 - F:973 445 072
SOLSONA - JORDI VILAR
Ctra. Manresa, Km 50. T:973 482 077 - F:973 482 373
LLEIDA - PROMOCIÓN DE PREFABRICADOS S.L.
Ivars d'Urgell, 20. Pol. Ind. Neoparc.
T:973 603 954 - F:973 603 950
MOLLERUSA - PROMOCIÓN DE PREFABRICADOS S.L.
Avda. Canal 8. Baixos. T:967 542 944
LLEIDA - PUJOL ELEMENTS
Tarragona, 40. T:973 202 350 - F:973 203 113

LUGO
FOZ - ALMACENES BAHIA
Maestro Lugilde, 6. T:982 140 957 - F:982 132 065
LUGO - ARIAS NADELA
Tolda de Castilla, s/n. T:982 245 725
XOVE - ESTABLECIMIENTOS REY S.L.
Avda. Diputación, 88. T:982 592 006 - F:982 592 071
CHANTADA - SONIA GOMEZ GOMEZ
Juan XXIII, 22. T:982 441 249 - F:982 440 331

MADRID
LEGANÉS - PORCELANOSA
Avda. Recomba, 13. Pol. La Laguna Salida 53 - M50.
T:914 819 200 - F:916 930 292
ALCOBENDAS - PORCELANOSA
Parque Río Norte. T:916 623 232 - F:916 624 607
ALCORCÓN - PORCELANOSA
Ctra. N-V, km 15,5. Parque Oeste de Alcorcón.
T:916 890 172 - F:916 890 170
MADRID - PORCELANOSA
Ortega y Gasset, 62. Esquina Conde Peñalver.
T:914 448 460 - F:914 025 111
MADRID - PORCELANOSA
Alcalá, 514. T:917 545 161 - F:917 545 555

MÁLAGA
MÁLAGA - PORCELANOSA
Avda. Velázquez, 77. T:952 241 375 - F:952 240 092
MARBELLA - PORCELANOSA
Avda. Ricardo Soriano, 65. T:952 826 868 - F:952 822 880
RONDA - MARMOLERA RONDEÑA
Guadalevín, 12. Pol. Ind El Fuerte. T:952 872 225
VELEZ - MATERIALES MUÑOZ PEREZ
Ferrocarriil, 2. T:952 507 879 - F:952 504 760

MELILLA
MELILLA - FERRETERIA MODERNA E HIJOS
Paseo Marítimo Mir Berlanga, 19. T:952 671 144 - F:952 671 285

MURCIA
MURCIA - PORCELANOSA
Avda. Juan de Borbón, s/n. Parque Comercial Thader.
T:968 879 527 - F:968 831 725
CARAVACA DE LA CRUZ - PORCELANOSA
Avda. Ctra. Granada, 20. T:968 705 647 - F:968 705 648
EL ALGAR - AZULEJOS ZAPATA PEÑALVER S.L.
Ctra. La Palma, s/n. T:968 135 480 - F:968 135 000
LORCA - PORCELANOSA
Ctra. de Granada, 127. Polígono Los Peñones.
T:968 478 130 - F:968 470 820

NAVARRA
MULTIVA BAJA - MONTEJO CERÁMICAS
Pol. Ctra. Tajonar, Calle A, Naves 2-4.
T:948 239 065 - F:948 230 503
CINTRUENIGO - CERÁMICAS CECILIO CHIVITE
Pol. Ind. s/n. Variante N-113. T:948 811 973 - F:948 815 249
PAMPLONA - MONTEJO CERÁMICAS
Navas de Tolosa, s/n. T:948 224 000 - F:948 226 424
TUDELA - MONTEJO CERÁMICAS
Ctra. Tudela-Tarazona, Pol. Centro de Servicios de Tudela.
T:948 848 365 - F:948 848 573

OURENSE
OURENSE - BLANCO QUINTAS
Nosa Señora do Sainza, 48. T:988 391 114 - F:988 250 413
CARBALLIÑO - JOSE R. PITEIRA,S.L.
Avda. Julio Rodríguez Soto, 63. T:988 271 071 - F:988 274 780

PALENCIA
PALENCIA - CANTALAPIEDRA
La Puebla, 2. T:979 706 421 - F:979 702 652

PONTEVEDRA
DENA - PREFABRICADOS DENA S.L.
Rua Galicia, 24. T:986 743 121 - F:986 745 131
SEIXO, MARÍN - SANEAMIENTOS ROSALES
Avenida Doctor Otero Ulloa, 1. T:986 702 041 - F:986 702 080
O GROVE - PREFABRICADOS DENA S.L.
Alexandre Boveda, 82. T:986 702 041- F:986 733 415
LALÍN - ALMACENES CANDA S.L.
Monserrat, 36-39 B. T:986 780 184 - F:986 782 301
MOS - BLANCO QUINTAS, S.L.
Monte Faeiña s/n - B. T:986 288 041 - F:986 486 316
SILLEDA - ARCOLAR 2000 S.L.
Rua Venezuela, 40. T:986 580 114 - 986 592 513
VIGO - SANEAMIENTOS ROSALES
García Barbón, 139 B. T:986 228 806

SALAMANCA
VILLARES DE LA REINA - PORCELANOSA
Pol. Villares. Ctra. Salamanca - Valladolid, km 2,2.
T:923 243 811 - F:923 123 414

SANTA CRUZ DE TENERIFE
SANTA CRUZ DE TENERIFE - PORC. Y PAV. CANARIOS
Avda. 3 de Mayo, 18. T:922 209 595 - F:922 209 596
LOS LLANOS DE ARIDANE - AFELSA
Las Rosas, s/n. T:922 461 112 - F:922 461 166
SANTA CRUZ DE LA PALMA - AFELSA
Abenguaerne, 3. T:922 412 143 - F:922 420 012
SANTA MIGUEL - PORC. Y PAV. CANARIOS
Avenida Claudio Delgado Díaz, 59. T:649 298 137

SEGOVIA
EL ESPINAR - SEGOGER
Carretera Madrid-La Coruña, km 64.
T:921 172 426 - F:921 171 828
SEGOVIA - SEGOGER
José Zorrilla, 134. T:921 444 122

SEVILLA
SEVILLA - PORCELANOSA
Pol.Ind.La Negrilla. C/ Tipografía, 2.(Autovía A-92 Málaga-Granada) T:954 260 540 - F:954 528 681
LORA DEL RÍO - HERNÁNDEZ CARBALLO S.L.
Betis s/n. T:955 800 473 - F:955 801 439
TOMARES - PORCELANOSA
San Roque, s/n. Polígono El Manchón.
T:954 152 792 - F:954 153 188

SORIA
SORIA - MAT. CONSTRUCCIÓN ODORICIO S.L.
Polígono las Casas-II. Calles A y J, Parcela 201.
T:975 233 228 - F:975 232 188

TARRAGONA
CAMBRILS - MONSERRATE ESTIL CERAMIC S.L.
Pol. Ind. Belianes nau 5, Ctra. Cambrils-Montrbrío.
T:977 364 900 - F:977 364 953
ALCOVER - EXPOMAT
Tramuntana, s/n (pol. Roques Roges)
T:977 760 476
EL VENDRELL - COMERCIAL STC

Terrissaires, 1. T:977 661 951
EL VENDRELL - VIUDA DE ANTONIO FONT
Valls, 12. T:977 660 794 - F:977 662 217
MORA LA NOVA - COMERCIAL LLAUARADO
Ctra. Tivissa, S/N. T:977 400 387 - F:977 400 052

REUS - COMERCIAL STC
Plz. de les Oques, 8. T:977 312 502 - F:977 317 211
RODA DE BARA - CONSTRUCCIONS CIURO
Acceso a Roda de Bara Km. 1. T:977 802 951 - F:977 802 012
TARRAGONA - MATERIALS GISBERT
Francesc Macia, 4. T:977 242 363
TORTOSA - MATERIALS GISBERT
Ctra. Gandesa Km 3,5. T:977 500 306 - F:977 501 550
VALLS - RAMÓN MAGRIÑA BATALLA
Montblanc, 14. T:977 600 210 - F:977 603 302
TARRAGONA - TINALEX ARTE
Ctra. Valencia, 202. T:977 551 055
TARRAGONA - TINALEX ARTE
Ctra. Pont D'Armentera, 202. T:977 221 901

TERUEL
TERUEL - GARGÓN
Polígono La Paz, Parcela 143-149. T:978 609 661 - F:978 607 980

TOLEDO
TOLEDO - PORCELANOSA
Pol.Ind.Sta. María de Benquerencia, C/del Río Marchés,123
T:925 232 402 - F:925 232 406

International Showrooms

ALBANIA
TIRANA - ALBA CERÁMICA PORCELANOSA
T: +355 42233817 - F: +355 42233817
TIRANA - ALBA CERAMICA
T: +355 48300084 - F: +355 48300084

ALEMANIA
ASCHAFFENBURG - KALKWERKE
T: +49 (0) 60 213 601 62 - F: +49 (0) 60 213 602 93
BAD SALZUFLEN - W. LINNENBECKER GmbH
T: +49 (0) 5222 / 5301 221 - F: +49 (0) 5222 / 5301 209
BADEN BADEN - E. Wertheimer GmbH
T: +49 (0) 7221 50020 - F: +49 (0) 722171080
BAUTZEN - FLIESEN LEHMANN GmbH
T: +49 (0) 3591 / 3726 32 - F: +49 (0) 351 / 8931420
BEESKOW - BADER BAUSTOFFE & WERKZEUGE, HANDELSGEGSELLSCHAFT T: GmbH
+49 (0) 3366 / 417 0 - F: +49 (0) 3366 / 417 90
BERGISCH GLADBACH - SCHMIDT RUDERSDORF GmbH & Co
T: +49 (0) 2204 / 4007 0 771 - F: +49 (0) 3320 / 854715
BERLIN - W. LINNENBECKER GMBH & CO. KG
T: +49 (0) 30 / 756 888 - F: +49 (0) 30 / 756 88 756
BERLIN - FLIESEN PARADIES GLAESKE + SEFZIG GmbH
T: +49 (0) 30 650 737 0 - F: +49 (0) 30 650 737 34
BERLIN - BERLINER FLIESENMARKT GmbH
T: +49 (0) 30 326 725 10 - F: +49 (0) 30 326 725 58
BOFFZEN - HERMANN BACH GmbH & CO. KG
T: +49 (0) 5271 / 955 251 - F: +49 (0) 5271 / 955 200
BONN - SCHMIDT-RUSSERDORF
T: +49 (0) 228 55 916 0
BOTTROP - W. LINNENBECKER GMBH & CO. KG
T: +49 (0) 2041 / 7958 13 - F: +49 (0) 2041 / 7958 10
BURGSTÄDT - FLIESEN THOMAS FLIESEN GROSßHANDEL GMBH
T: +49 (0) 3724 / 1856 0 - F: +49 (0) 3724 / 1856 70
DORTMUND - W. LINNENBECKER GMBH & CO. KG
T: +49 (0) 231 / 562 090 22 - F: +49 (0) 231 / 562 090 88
DOSSENHEIM - SENGEWITZ FLIESEN GALERIE
T: +49 (0) 6221 874440 - F: +49 (0) 6221874442
DOSSENHEIM - FLIESEN GALERIE SENGEWITZ
T: +49 (0) 6221 874440 - F: +49 (0) 6221 874442
ELTERLEIN - FLIESNHAUS MÜLLER
T: +49 (0) 37349 / 7305 - F: +49 (0) 37349 / 6093
ERKRATH - W. LINNENBECKER GMBH
T: +49 (0) 211 / 92503 19 - F: +49 (0) 211 / 92503 34
FREIBURG - GÖTZ & MORIZ GMBH
T: +49 (0) 76 145 180 - F: +49 (0) 76 145 711 2
FULDA - OSWALD KERAMIK UND STEIN GMBH
T: +49 (0) 66 194 151 0 - F: +49 (0) 66 194 151 40
GERA - BAUSTOFFE GEBR. LÖFFLER GMBH
T: +49 (0) 365 430 701 9 - F: +49 (0) 365 430 701 4
GÖRLITZ - FLIESEN-PEDERSEN GMBH
T: +49 (0) 3581 / 402809 - F: +49 (0) 3581 / 409166
HAMBURG - LURUP - CROONEN FLIESENHANDEL GMBH
T: +49 (0) 40 / 83383 377 - F: +49 (0) 40 / 83383 301
KARLSSTADT - FLIESEN GEHRET
T: +49 (0) 93 539 731 0 - F: +49 (0) 93 539 731 26
KOBLENZ - J. N. KÖBIG GMBH - KOBLENZ
T: +49 (0) 26 198 169 20 - F: +49 (0) 26 198 169 10
KRANICHFELD - MÜHL 24 - KRANICHFELD
T: +49 (0) 36 450 330 - F: +49 (0) 36 450 332 89
LEVERKUSEN - SCHMIDT-RUDERSDORF
T: +49 02 14 - 8 68 13 0 - F: +49 02 14 - 8 68 13 13
LÖBNITZ - SACHSENKERAM GBR
T: +49 (0) 34208 / 7400 - F: +49 (0) 34208 / 7400
LÜBECK - HEINRICH 'S FLIESENMARKT
T: +49 (0) 451 896669 - F: +49 (0) 451 8973494
MAINZ - J. N. KÖBIG GMBH - MAINZ
T: +49 (0) 61 313 943 10 - F: +49 (0) 61 316 942 75
MESSEDE - W. LINNENBECKER GMBH & CO. KG
T: +49 (0) 291 / 952 82 21 - F: +49 (0) 291 / 952 82 82
MÜNCHEN - CERAMICAS OHG
T: +49 (0) 89 318 280 0 - F: +49 (0) 89 318 280 20
MÜNSTER - W. LINNENBECKER GMBH & CO. KG
T: +49 (0) 251 / 979 12 21 - F: +49 (0) 251 / 979 1220
NORDHAUSEN - HERMANN BACH GMBH & CO. KG
T: +49 (0) 3631 / 633 126 - F: +49 (0) 3631 / 633 143
NÜRNBERG/HAFEN - HEINRICH CHRIST GMBH & CO. KG
T: +49 (0) 91 164 318 0 - F: +49 (0) 91 164 318 50
OFFENBURG - Maier + Kaufmann GmbH
T: +49 (0) 78196780 - F: +49 (0) 781967890
POTSDAM - KERANA KERAMIK und Natursteinhandel GMBH
T: +49 (0) 33208 / 547 0 - F: +49 (0) 3381 7304501
RADEBEUL - FLIESEN EHRLICH & CO. GMBH
T: +49 (0) 351 / 89314 10 - F: +49 (0) 351 / 89314 20
RONNENBERG/EMPELDE - W.LINNENBECKER GMBH & CO.KG
T: +49 (0) 511 / 438 90 36 - F: +49 (0) 511 / 438 90 49
SCHRAMBERG - SÜLGEN - ARMBRUSTER GMBH
T: +49 (0) 7422 28008-0 - F: +49 (0) 7422 28008-20
STUTTGART - TAXIS - STUTTGART
T: +49 (0) 71 189 003 121 - F: +49 (0) 71 189 003 104
UNTERGRUPPENBACH - KONZ & SCHAEFER HANDEL GmbH
T: +49 (0) 71312037480 - F: +49 (0) 71312037489
VÖLKLINGEN - NIEDERER GMBH
T: +49 (0) 68 989 802 21 - F: +49 (0) 68 989 802 30
WAIBLIGEN - KONZ FLIESENHANDEL GmbH
T: +49 (0) 7151149200 - F: +49 (0) 710510149-209

WÜRSELEN - SCHMIDT-RUDERSDORF
T: +49 (0) 24 05 - 41 38 50 - F: +49 (0) 24 05 - 41 38 55
ZWETHAU - GRAMER GMBH
T: +49 (0) 3421 / 7327 18 - F: +49 (0) 3421 / 7326 73

ANGOLA
LUANDA-PORCELANOSA ANGOLA
T: +244 928463705 - F: +244 222372374

ARABIA SAUDI
JEDDAH - MANART AL ANDALOS EST
T: +966 2 629 3402 - F: +966 2 629 3416
RIYADH - MANART AL ANDALOS EST
T: +966 1 282 1500
AL AHSA - KHALED AL ANSARI SHOWROOM
T: +966 3 589 2888 - F: +966 3 5817043
DAMMAM - KHALED AL ANSARI VALENCIA SHOWROOM
T: +966 3 8180355 - F: +966 3 8188060
DAMMAM - MOHAMED M. AL DOSSARY STORES
T: 38348681 - F: +38340086

ARGELIA
ORAN - PORCELANOSA ORAN
T: +213 555035414/15
ALGER - NOVACASA
T: +213 21 55 07 37 - F: +213 23 94 74 46

ARGENTINA
BUENOS AIRES - BLAISTEN S.A.
T: +54 11 463 620 00 - F: +54 11 463 614 86
MAR DEL PLATA - IMEPHO S.A.
T: +54 223 481 3827

ARMENIA
YEREVAN - SACO & ARARAT-SALON BOMOND
T: +37 410 55 08 99 - F: +37 410 51 75 81

AUSTRALIA
BRISBANE - ACESTONES & TILES
T: +61 7 5493 3344 - F: +61 7 5493 3117
NEWCASTLE - EARP BROSTILE
T: +61 2 4925 4555 - F: +61 2 4962 2926
SYDNEY - EARP BROSTILE
T: +61 2 9410 3222 - F: +61 2 9410 2011
MELBOURNE - EARP BROSTILE
T: +61 3 9328 8598 - F: +61 3 9348 9996
ADELAIDE - ITALIA CERAMICS
T: +61 8 8336 2366 - F: +61 8 8336 9016
OSBORNE PARK - MIDDLESWAN TRADING
T: +61 8 9445 1777 - F: +61 8 9446 3127
HOBART - ROSSETTO TILING
T: +61 3 6231 2931 - F: +61 3 6231 5783
LAUNCESTON - ROSSETTO TILING
T: +61 3 6326 4955 - F: +61 3 6326 6003
BRISBANE - TILES COPE IMPORTS
T: +61 7 3371 5777 - F: +61 7 3371 5133

AUSTRIA
INNSBRÜCK – FLIESEN CENTER TIROL
T: +43 512 364444
GRAZ – TENNE
T: +43 316 262 524 0 - F: +43 316 262 524 22
LEIBNITZ – TENNE
T: +43 3452 707 65 – F: +43 3452 707 29
BRÜCK – TENNE
T: +43 3862 588 44 – F: +43 3862 588 44-22
WIEN – TENNE
T: +43 1 2020 520 – F: +43 1 2020 520-20
WIEN – BEINKOFER BEI BÄDERPARADIES
T: +43 1 52242200 – F: +43 1 522422020
WIEN – BEINKOFER BEI HOLTNER
T: +43 1 61516006900 – F: +43 1 61516006909
WIEN – FLIESEN FÜHRER HANDELS GmbH
T: +43 1 5971 533 0 – F: +43 1 5971 533 28
LINZ – BEINKOFER
T: +43 (0) 732 655 2550 – F: +43 (0) 732 655 25520
LINZ – BEINKOFER
T: +43 732 776 543 0 – F: +43 732 776 543 60
SALZBURG – BEINKOFER
T: +43 6624 69 09 69 20 – F: +43 6624 69 09 42 89
VÖSENDORF – TENNE VÖSENDORF
T: +43 1 699 33 33 – F: +43 1 699 33 33-22
WELS – BEINKOFER
T: +43 (0) 7242 25253210 – F: +43 (0) 7242 25253250
HALL – BEINKOFER BEI HOLTNER
T: +43 (0) 5223 5046910 – F: +43 (0) 5223 5046919

AZERBAIJÁN
BAKU - AKSESUAR PORCELANOSA GRUPO
T: +994 12 5962548/+994 12 4973103 - F: +994 12 447 4383
BAKU - AKSESUAR INSAAT
T: +994 12 546 74 86 - F: +994 12 546 74 86

BAHRÁIN
MANAMA - AL ABBAS GALLERY
T: +973 741 919 - F: +973 741 747

BANGLADESH
DHAKA - NUPAMI TRADING
T: +880 17837 01416
DHAKA - NUPAMI
T: +880 1793567404

BÉLGICA
HEIST-OP-DEN-BERG - PGB CERAMICA NV
T: +32 (0) 15 253366 - F: +32 (0) 15 253367

BERMUDAS
PEMBROKE - PEMBROKE TILE & STONE Co. LTD
T: +441 292 8453 - F: +441 295 8453

BIELORRUSIA
GOMEL - UNDERGROUND
T: +375 2327 76919 - F: +375 2327 76757
MINSK - UNDERGROUND
T: +375 1721 78785 - F: +375 1721 75632
MINSK - DOMIART
T: +375 17 259 60 33 - F: +375 17 259 6212

BOLIVIA
SANTA CRUZ - ELEMENTO DISEÑO & ARQUITECTURA
T: +591 3 364 7313 - F: +591 3 347 6226

BOSNIA Y HERZEGOVINA
CITLUK - BROTTIS d.o.o.
T: +387 633 21500 - F: +387 366 50950
SARAJEVO - LUK d.o.o.
T: +387 33 777 888 - F: +387 33 777 889
BANJA LUKA - LUK d.o.o.
T: +387 51 379 261/262 - F: +387 51 370 877
BIJELJINA - LUK d.o.o.
T: +387 55 228 100 - F: +387 55 228 101

BRASIL
CAMPO LARGO - PORCELANOSA BRASIL REVESTIMENTOS LTDA
T: +55 (41) 3392 1500 - F: +55 (41) 3392 1400

BULGARIA
PETRICH - NIKMAR
T: +359 866 321 111 - F: +359 745 234 64
SOFIA - NIKMAR
T: +359 2 868 93 95
SOFIA - NIKMAR
T: +359 888 143 313
SOFIA - ELE CERAMICA
T: +359 2 860 60 60
VARNA - ELE CERAMICA
T: +395 52 500 555

CAMBOYA
PHNOM PENH - HOME LIVING
T: 855092434264

CANADÁ
VANCOUVER - FONTILE DISTRIBUTORS
T: +604 683 9358 - F: +604 683 6758
MONCTON - DOMINION TILE & SUPPLIES
T: +506 857 8906 - F: +506 857 4149
CALGARY - PORCELANOSA CALGARY
T: + (587) 349-2290

CHILE
SANTIAGO DE CHILE - BUDNIK HERMANOS S.A.
T: +562 398 0100 - F: +562 212 3058
LAS CONDES - PORCELANOSA GRUPO CHILE SPA
T: +569 5 653 4306

CHINA
BEIJING – PO YICK DECORATION DESIGN CO LTD
T: +861085271313 - F: +861064229976
CHANGSHA - TAOTAO LE BUILDING MATERIALS CO.LTD
T: +8673189931787 - F: +8673189931786
CHENGDU - DEHUA SANITARY EQUIPMENT
T: +86 28 8775100181 - F: +86 28 877421681
CHONGQUING - JIANGBEI YAO CHENG BUILDING MATERIALS
T: +86 23 86358360 - F: +86 23 86357182
DALIAN - PO YICK BUILDING MATERIALS Co. Ltd.
T: +86 41182301911 - F: +86 41182301911
FOSHAN – GUANGZHOU PO YICK DECORATION DESIGN CO LTD
T: +86 757 8278 2507 - F: +86 757 8278 5795
FUZHOU – PO YICK BUILDING MATERIALS
T: +86 591 8805 5823 - F: +86 591 8805 5823
GUANGZHOU – PO YICK BUILDING MATERIALS Co. Ltd. (FAFA)
T: +86 20 22008228 - F: +86 20 22008230
GUANGZHOU – PO YICK BUILDING MATERIALS Co. Ltd. (MAFO)
T: +86 20 8701 8223 - F: +86 20 8701 8226
HAIKOU - HAIKOU QIONGSHAN HUAXIN SANITARY BUILDING MATERIALS BUSINESSES
T: +86 898 6532 2417 - F: +86 898 6533 4893
HANGZHOU - DA DOU BUILDING MATERIAL BUSINESS
T: +86 139 5814 9905
HANGZHOU - MING OU BUILDING MATERIALS Co. Ltd.
T: +86 571 8658 2691 - F: +86 571 8608 5893

HARBIN-MING JIA LIVING SPACE BUILDING MATERIAL BUSINESS
T: +86 139 0450 4791
JIANGYIN - PORCELANOSA BUILDING MATERIALS Co. Ltd.
T: +86 510 8169 3999 - F: +86 510 8169 3999
JIAXING - JIAXING FEIFAN BUILDING MATERIALS
T: +86 573 8277 0662 - F: +86 573 8277 0662
NANJING - XINGLANG BUILDING MATERIALS Co. Ltd.
T: +86 255 8823 208 - F: +86 255 8823 208
QINGDAO – TUOLI SPACE BUILDING MATERIALS Co. Ltd.
T: +86 532 8099 5657 - F: +86 532 8099 5657
SHANGHAI - PO YICK DECORATION DESIGN Co. Ltd.
T: +86 21 6438 3735 - F: +86 216 4281 607
SHANGHAI - GUANGZHOU PO YICK DECORATION DESIGN Co. Ltd.
T: +86 216 4411 484 - F: +86 216 4281 607
SHENYANG - BAO LU SHA PO YICK BUILDING MATERIALS Co. Ltd
T: +86 24 8563 7137 - F: +86 24 8563 7137
SHENZHEN - PO YICK BUILDING MATERIALS Co. Ltd. (BAILIMA)
T: +86 755 8240 7728 - F: +86 755 8240 7738
SHENZHEN - PO YICK BUILDING MATERIALS Co. Ltd. (HONGHU LU)
T: +86 755 2562 0359 - F: +86 755 2562 0344
TIANJIN – OU LIN BUILDING MATERIALS Co. Ltd.
T: +86 22 2352 8765 - F: +86 22 8827 7023
WENZHOU - MINGJIA INTERNATIONAL BUILDING MATERIALS Co. Ltd.
T: +86 577 8971 2011 - F: +86 577 8971 2066
XIAMEN - PO YICK BUILDING MATERIALS SHOP
T: +86 952 3755123 - F: +86 591 88055823

CHIPRE
LIMASSOL - THE ENGINEERING AND COMMERCIAL ASSOCIATION (EKA)
T: +357 2585 4444 - F: +357 2585 4545
GIRNE - MEPAS LTD
T: +9039 2815 2964 - F: +9039 2815 5651
NICOSIA - N. M. MARKOU BROS LTD
T: +357 2261 0740 - F: +357 2261 2162

COLOMBIA
BOGOTÁ - PORCELANOSA GRUPO COLOMBIA
T: +571 310 02 45
BOGOTÁ - PROSEIN
T: +57 743 5566
BARRANQUILLA - D.I.M.C.E.
T: +57 5 300 6208

COREA DEL SUR
SEOUL - T&S TRADING CO. LTD
T: +82 234 438 600 - F: +82 234 438 822
SEO-GU - COTTO CERAMIC CO LTD
T: +82 325 840 770 - F: +82 325 840 660
BUSAN - COTTO CERAMIC CO LTD
T: +82 512 080 022 - F: +82 512 088558

COSTA RICA
SAN JOSE - FERNANDEZ AGUILAR S.A.
T: +506 2222 5674 - F: +506 221 9952

COSTA DE MARFIL
ABIDJAN - FADCO COMPANY
T: +225 21757355 - F: +225 21757358

CROACIA
DUBROVNIK - OTP DUBROVNIK
T: +385 20 412478 - F: +385 20 311521
POREC - SPINA
T: +385 52 451 348 - F: +385 52 434 005
PULA - SPINA
T: +385 52 219 002 - F: +385 52 219 118
RIJEKA - SPINA
T: +385 51 741 300 - F: +385 51 741 298
SPLIT - SPINA
T: +385 21 668 991 - F: +385 21 668 992
VARAZDIN - SPINA
T: +385 42 303 707 - F: +385 42 303 709
ZAGREB - SPINA
T: +385 13 492 552 - F: +385 13 492 560
ZAGREB - ABC INTERJER
T: +385 16 393 164 - F: +385 16 055 985

DINAMARCA
GLOSTRUP - MOSAIKHJORNET
T: +45 43 633 900 - F: +45 43 663 857
ODENSE M - DANESP FLJSE KOMPAGNIET APS
T: +45 66 173 221 - F: +45 66 173 821

ECUADOR
GUAYAQUIL - ARKETIP'S CA
T: +593 422 467 52 - F: +593 422 403 96
QUITO - ARKETIP'S CA
T: +593 422 498 39 - F: +593 225 573 99

EGIPTO
EL CAIRO - MAHGOUB TRADING & IMPORTING
T: +20 2 57 12 565 - F: +20 2 57 39 344

EMIRATOS ÁRABES UNIDOS
DUBAI - GALAXY TRADING
T: +971 42696882

ESLOVAQUIA
BRATISLAVA - CERSA
T: + 421244442833 - F: 421244642113
KOSICE - VODOARM
T: + 055/6222660 - F: 055/6222654
ESLOVENIA
LJUBLJANA - KEOR d.o.o.
T: +386 1 542 14 86 - F: +386 1 542 14 88
MARIBOR - KEOR d.o.o.
T: +386 2 480 54 15 - F: +386 2 471 06 33
MARIBOR - MAVI d.o.o.
T: +386 2 23 50 316 - F: +386 2 23 50 312

ESTADOS UNIDOS
CALIFORNIA:
ANAHEIM - PORCELANOSA ANAHEIM
T: +1 714 772 3183 - F: +1 714 772 9851
SAN FRANCISCO - PORCELANOSA SAN FRANCISCO
T: +1 415 593 7763 - F: +1 415 593 7664
SAN JOSE - PORCELANOSA SAN JOSE
T: +1 408 467 9400 - F: +1 408 467 9410
BEVERLY HILLS - PORCELANOSA WEST HOLLYWOOD
T: +1 310-300-2090
CONNECTICUT:
RIVERSIDE - PORCELANOSA RIVERSIDE
T: +1 203 698 7618 - F: +1 203 698 7619
FLORIDA:
MIAMI - PORCELANOSA MIAMI
T: +1 305 715 7153 - F: +1 305 715 9635
POMPANO BEACH - PORCELANOSA POMPANO BEACH
T: +1 954 968 7666 - F: +1 954 968 7699

GEORGIA:
ATLANTA - PORCELANOSA ATLANTA
T: +1 305 715 7153
ILLINOIS:
CHICAGO - PORCELANOSA CHICAGO
T: +1 312 204 6220 - F: +1 312 204 6240
MARYLAND:
NORTH BETHESA - PORCELANOSA ROCKVILLE
T: +1 301 294 8193
MASACHUSETS:
BOSTON - PORCELANOSA BOSTON
T: +1 617-963-7666
NEW JERSEY:
EAST BRUNSWICK - PORCELANOSA EAST BRUNSWICK
T: +1 732 613 1915 - F: +1 732 613 9181
PARAMUS - PORCELANOSA PARAMUS
T: +1 201 712 0556 - F: +1 201 599 1520
RAMSEY - PORCELANOSA RAMSEY
T: +1 201 995 1310 - F: +1 201 995 1960
NEW YORK:
NEW YORK - PORCELANOSA NYDC
T: +1 212 252 7370
WESTBURY - PORCELANOSA WESTBURY
T: +1 516 338 0097 - F: +1 516 338 0098
TEXAS:
DALLAS - PORCELANOSA DALLAS
T: +1 214 377 2327 - F: +1 214 234 1340
SEATTLE - POCELANOSA SEATTLE
T: 206 673 8395 - F: 206 673 8402
KING OF PRUSSIA - PORCELANOSA KING OF PRUSSIA
T: 484 751 0050 - F: 484 751 0047
MC ALLEN - SPAÑOLO GALLERY
T: 956 905 0244 / 956 907 5477 - F: 956 627 2522

EL SALVADOR
SAN SALVADOR-FERRETERIA DE LA CONSTRUCCIÓN FERCO
T: 503 2510 8888 - F: 503 2510 8810

ESTONIA
TALLINN - PLAADI PUNKT
T: +372 650 0720 - F: +372 650 0723

ETIOPIA
ADDIS ABABA - I SALE TRADING
T: +251 (0)911 20 53 91 / +251 (0)930 03 45 51

FILIPINAS
MANILA - CASA EUROPA
T: +63 2 519 3515

FINLANDIA
VANTAA - LAATTAPISTE OY
T: +358 9 878031 - F: +358 9 890832
ESPOO - LAATTAPISTE ESPOO
T: +358 (0)207 880 750
HYVINKÄÄ - LAATTAPISTE HYVINKÄÄ
T: +358 (019)455 830
HÄMEELINNA - LAATTAPISTE HÄMEELINNA
T: +358 (0) 207 414 70
JOENSUU - LAATTAPISTE JOENSUU
T: +358 (0) 207 880 880
JYVÄSKYLÄ - LAATTAPISTE JYVÄSKYLÄ
T: +358 (0) 207 433 830
KOTKA - LAATTAPISTE KOTKA
T: +358 (0) 102 314 100
KOUVOLA - LAATTAPISTE KOUVOLA
T: +358 (0) 20 7880 760

KUOPIO - LAATTAPISTE KUOPIO
T: +358 (0) 17-266 3500
LAHTI - LAATTAPISTE LAHTI
T: +358 (03) 875 950
LAPPEENRANTA - LAATTAPISTE LAPPEENRANTA
T: +358 (0) 207 880 720
MIKKELI - LAATTAPISTE MIKKELI
T: +358 (015) 212 055
OULU - LAATTAPISTE OULU
T: +358 (0)20 7880 780
PORI - LAATTAPISTE PORI
T: +358 (0)207 288 320
PORVOO - LAATTAPISTE PORVOO
T: +358 (019) 5766767
RAISIO - LAATTAPISTE TURKU
T: +358 (0) 207 288 300
RAUMA - LAATTAPISTE RAUMA
T: +358 (0)207 288 310
ROVANIEMI - LAATTAPISTE ROVANIEMI
T: +358 (016) 310 403
SALO - LAATTAPISTE SALO
T: +358 (02) 733 1494
SAVONLINNA - LAATTAPISTE SAVONLINNA
T: +358 (015) 522 178
SEINÄJOKI - LAATTAPISTE SEINÄJOKI
T: +358 (0)207 880 700
TAMPERE - LAATTAPISTE TAMPERE
T: +358 (03) 3142 3300
VAASA - LAATTAPISTE VAASA
T: +358 (0)207 880 740

FRANCIA
ALSACE ET LORRAINE:
VENDENHEIM - PORCELANOSA STRASBOURG
T: +33 (0)388 20 82 90 - F: +33 (0)388 209 107

International Showrooms

MIDI-PYRÉNÉES:
TOULOUSE - PORCELANOSA TOULOUSE SAS
T: 05 34 56 57 60 - F: 05 34 56 57 86
NORD - PAS - DE - CALAIS:
LEZENNES - PORCELANOSA LILLE
T: +33 (0)320 340 340 - F: +33 (0)320 340 341
PAYS DE LA LOIRE:
BEAUCOUZE - PORCELANOSA ANGERS
T: +33 (0)241 738 100 - F: +33 (0)241 733 721
GUERANDE - PORCELANOSA LA BAULE
T: +33 (0)240 607 273 - F: +33 (0)240 110 659
LA CHAPELLE SAINT AUBIN - PORCELANOSA LE MANS
T: +33 (0)243 236 520 - F: +33 (0)243 240 512
LA ROCHE SUR YON - PORCELANOSA LA ROCHE S/YON
T: +33 (0)251 241 217 - F: +33 (0)251 242 399
ORVAULT - PORCELANOSA NANTES
T: +33 (0)228 073 950 - F: +33 (0)228 073 957
POITOU - CHARENTES:
CHASSENEUIL DU POITOU - PORCELANOSA POITIERS
T: +33 (0)549 119 787 - F: +33 (0)549 119 788
PROVENCE - ALPES - CÔTE D'AZUR:
AUBAGNE - PORCELANOSA MARSEILLE
T: +33 (0)442 624 330 - F: +33 (0)442 624 339
NICE - PORCELANOSA Associatèe NICE
T: 493041963
MANDELIEU LA NAPOULE - PORCELANOSA CANNES
T: +33 (0)493 477 360 - F: +33 (0)493 477 402
LES PENNES MIRABEAU (PLAN DE CAMPAGNE) -
PORCELANOSA PLAN DE CAMPAGNE
T: +33 (0)442 466 120 - F: +33 (0)442 466 129
RHÔNE ALPES ET AUVERGNE:
CHAMPAGNE AU MONT D'OR - PORCELANOSA LYON
T: +33 (0)478 668 151 - F: +33 (0)478 432 003
SAINT-ÉTIENNE - PORCELANOSA Associatèe SAINT-ÉTIENNE
T: +33 (0) 477 305 676

GEORGIA
TBILISI - LUXOR SHOP
T: +995 32 2388898 - F: +995 32 2388399

GHANA
DZORWULU-ACCRA - ROUGE INTERIORS
T: +223 302 734752

GRECIA
ATTICA - AURORA BAGNO
T: +30 2105 594 520 - F: +30 2105 594 521
HATZ GROUP - PORCELANA:
ATHENS
T: 210 96 07 010 - F: 210 9607013
ATHENS
T: 210 5156 163 - F: 210 5156164
ATHENS
T: 2299041090 - F: 2299041095
GLIFADA
T: +30 2310 752 902 - F: +30 2310 753 564
KASTORIA
T: 2467044174
KATERINI
T: 2351076941 - F: 2351076940
KEFALONIA
T: 2671068360 - F: 26710 68 361
LARISA
T: 2410 619 999 - F: 2410 617444
LARISA
T: 2410561280
LEFKADA
T: 2645 0 72100 - F: 26450 29130
LOANNINA
T: 26510 92735-7 - F: 26510 92738
NAFFAKTOS
T: 2634038393 - F: 26710 68 361
PATRA
T: 2610524000 - F: 2610523532
PATRA
T: 2610647474 - F: 2610242010
RHODES
T: 2241003315 - F: 2241003316
SERRES
T: 23210 36157
THESSALONIKI
T: 2310474767 - F: 2310 474403
THESSALONIKI
T: 2310700861 - F: 2310700861
THESSALONIKI
T: 2310753003 - F: 2310753003
TRILAKA
T: 2351076941

IRAN
TEHRAN - FARBAR CO. LTD.
T: +98 21 88 03 6364 - F: +98 21 88 03 8283

IRAQ
ERBIL - AKSESUAR INSAAT ERBIL
T: +964 750 835 0055 - F: +964 66 210 1900

ISRAEL
BNEY BRAK - VIA ARCADIA
T: +972 3 614 2000 - F: +972 3 614 2020
RAANANA - AMOZI NAGAR IMP. MARK. OGEN LTD.
T: +972 9 760 1501 - F: +972 9 741 1997
RISHON LE ZION - NEGEV CERAMICS
T: +972 9 943 6676 - F: +972 9 6661
JERUSALEM - BAR-AMI 1990 LTD.
T: +972 2 531 3444 - F: +972 2 538 3740
BNEY BRAK - HEZI BANK
T: +972 3 616 6641 - F: +972 4 904 6643
BEERSHEVA - KIMCHI
T: +972 8 628 2060 - F: +972 8 623 2369
BETHLEHEM - AL-KHAYAL (BAYTOUNA)
T: +972 2 277 7279 - F: +972 2 274 4026
UPPER GALILY - KAMARIKA
T: +972 4 680 1010 - F: +972 4 680 0318
BEER SHEVA - NEGEV CERAMICS
T: +972 86280107
ELIAT - NEGEV CERAMICS
T: +972 86333638
HADEERA - NEGEV CERAMICS
T: +972 46186068
JERUSALEM - NEGEV CERAMICS
T: +972 26714455
NAZARETH - NEGEV CERAMICS
T: +972 46462046

GUATEMALA
GUATEMALA- FERRETERIA DE LA CONSTRUCCION FERCO
T: 502 2421 9000 - F: 502 2421 9009

GUAYANA FRANCESA
CAYENNE - ETS HENRY LE GAC
T: +594 302 719 - F: +594 300 713

HAÏTÍ
PUERTO PRINCIPLE - EURO CERAM
T: +509 250 57 14 - F: +509 250 57 15

HONG KONG
HONG KONG - TAI YICK BUILDING MATERIALS CO LTD
T: +852 23 956 670 - F: +852 23 957 831

HUNGRIA
BUDAPEST - PORCHANGARY KFT
T: +36 1 237 08 78
BUDAPEST - PALATINUS FURDOSZOBASZALONOK
T: +36 61-430-04-17 - F: +36 1-387-91-36
DEBRECEEN - PALATINUS FURDOSZOBASZALONOK
T: +36 52-531-476 - F: +36 52 536-822

EGER - PALATINUS FURDOSZOBASZALONOK
T: +36 0636-312-013 - F: +36 0636-313-270
MISKOLC - PALATINUS FURDOSZOBASZALONOK
T: +36 46-412-741 - F: +36 46-416-256
BÉKÉSCSABA - PALATINUS FURDOSZOBASZALONOK
T: +36 66 328 432 - F: +36 66 328 432
GYÖNGYÖS - PALATINUS FURDOSZOBASZALONOK
T: +36 37 500 162 - F: +36 37 500 163
KECSKEMET - PALATINUS FURDOSZOBASZALONOK
T: +36 76 412 272 - F: +36 76 509 204

INDIA
NEW DELHI - MARMO HOME PVT. LTD.
T: +91 11 47128800 - F: +91 11 2321 8728

INDONESIA
BANDUNG - WISMA SEHATI (BANDUNG BRANCH)
T: +62227238515 - F: +62227238516
JAKARTA - WISMA SEHATI (MANGGA DIA BRANCH)
T: +62216013303 - F: +62216251221
JAKARTA - WISMA SEHATI (POLIM BRANCH)
T: +62217278711
JAKARTA - WISMA SEHATI (BSD)
T: +62215377278 - F: +62215377880
SEMARANG - WISMA SEHATI (SEMARANG BRANCH)
T: +62243562233 - F: +62243562222
SURABAYA - WISMA SEHATI (SURABAYA BRANCH)
T: +62315462868 - F: +62315462868
SOUTH JAKARTA - VIVERE
T: +62 21 290 56889

IRÁN
TEHRAN - FARBAR CO. LTD.
T: +98 21 88 03 6364 - F: +98 21 88 03 8283

IRAQ
ERBIL - AKSESUAR INSAAT ERBIL
T: +964 750 835 0055 - F: +964 66 210 1900

IRLANDA
CORK - O.B. HEATING, PLUMBING, BATHROOMS & TILES
T: +353 0 214 310 000 - F: +353 0 214 310 003
DUBLIN - TILESTYLE LTD
T: +00 353 1 8555200 - F: +00 353 1 8557471

ISLANDIA
REYKJAVIK - ALFABORG EHF
T: +354 568 6755 - F: +354 568 1277

ISLA REUNIÓN
SAINT DENIS - RAVATE PROFESSIONNEL SAS
T: +262 904 024 - F: +262 904 057

ISRAEL
BNEY BRAK - VIA ARCADIA
T: +972 3 614 2000 - F: +972 3 614 2020
RAANANA - AMOZI NAGAR IMP. MARK. OGEN LTD.
T: +972 9 760 1501 - F: +972 9 741 1997
RISHON LE ZION - NEGEV CERAMICS
T: +972 9 943 6676 - F: +972 9 6661
JERUSALEM - BAR-AMI 1990 LTD.
T: +972 2 531 3444 - F: +972 2 538 3740
BNEY BRAK - HEZI BANK
T: +972 3 616 6641 - F: +972 4 904 6643
BEERSHEVA - KIMCHI
T: +972 8 628 2060 - F: +972 8 623 2369
BETHLEHEM - AL-KHAYAL (BAYTOUNA)
T: +972 2 277 7279 - F: +972 2 274 4026
UPPER GALILY - KAMARIKA
T: +972 4 680 1010 - F: +972 4 680 0318
BEER SHEVA - NEGEV CERAMICS
T: +972 86280107
ELIAT - NEGEV CERAMICS
T: +972 86333638
HADEERA - NEGEV CERAMICS
T: +972 46186068
JERUSALEM - NEGEV CERAMICS
T: +972 26714455
NAZARETH - NEGEV CERAMICS
T: +972 46462046

RAMAT GAN - NEGEV CERAMICS
T: +972 36155333
HAIFA - TOPOLSKI & CO LTD
T: +972 4 904 0496 - F: +972 4 904 0455
HAIFA - NEGEV CERAMICS
T: +972 48 466 444

ITALIA
BARI:
ANDRIA - MIDIL-CERAMICHE S.A.S
T: +39 08 835 66466 - F: +39 08 835 49260
MILANO:
CORSICO - PORCELANOSA LOMBARDIA S.P.A
T: +39 02 458 64310 - F: +39 02 458 64415
MODENA:
SASSUOLO - PORCELANOSA S.P.A
T: +39 05 368 06677 - F: +39 05 368 02184
ROMA:
ROMA - PORCELANOSA ROMA S.P.A
T: +39 06 888 9977 - F: +39 06 888 7056
CASSINO - CERAMICHE DUEP. S.R.L.
T: (+39) 077625142
BERGAMO - PORCELANOSA BERGAMO
T: (+39) 035299984 - F: (+39) 0352922085
MILAN - SPAZIO LIBIA 3
T: (+39) 0287246767

JERSEY
ST. SAVIOUR - PASTELLA GROUP
T: 01534 870167 - F: 01534 723199

JAPÓN
OSAKA - HIRATA TILES
T: 816 65321280

JORDANIA
AMMAN - AYMAN ABDALLAT & PARTNERS CO.
T: +9626 5504592 / 93 / 95 - F: +9626 5514149

KAZAJISTÁN
ALMATY - PALATIN
T: +7 (727) 395 7878 - F: +7 (727) 351 98 98
ALTAMY - STOCK
T: +7 (727) 2758 50 36
ASTANA - PORCELANOSA Associatèe ASTANA
T: +7 (7172) 28 83 37

KOSOVO
PRISHTINA - N P KERASAN
T: +381 38 602 667 - F: +381 38 602 667

KUWAIT
SAFAT - HASSAN ABUL HASSAN SADIQ
T: +965 2262 4466 - F: +965 2266 3376

KYRGYZ REPUBLIC
BISHKEK - KERAMIN KYRGYZYA
T: +996 (312) 51 05 05

LETONIA
RIGA - TORMANIS UN PARTNERI
T: +371 784 5361 - F: +371 784 5360

LÍBANO
BEIRUT - GEAHCHAN GROUP
T: +961 1480520 - F: +961 1496607
BEIRUT - PORCELANOSA GROUP
T: +961 1480520 - F: +961 1496607

LIBIA
BENGHAZI - EL RAGUOBI
T: 218 61 4704533 - F: 218 61 2237328
TRIPOLI - EL RAGUOBI
T: 218 91 3274885
BERKA BENHAZI - MANART AL ANDALOS EST
T: 21861229605 - F: 218612237328

LITUANIA
ALYTUS - IRIS LTD
T: +370 315 55969 - F: +370 315 55968

MACEDONIA
SKOPIJE - TE LINDI D.O.O.
T: +389 2 2 602 628- F: +389 2 2 602 638

MALTA
BIRKIRKARA - ROGER SATARIANO & SONS LTD
T: +356 21 442 769 - F: +356 21 497 017

MALASIA
KUALA LUMPUR - APEX BOUTIQUE
T: +603 4043 8333 - F: +603 4044 3338
PENANG - APEX BOUTIQUE
T: +604 659 3322 - F: +604 659 3339
SEBERANG PRAI TENGAH - APEX BOUTIQUE
T: +604 3988 333 - F: +604 3988 987
KOLOMBONG - APEX BOUTIQUE
T: +6088 388 150 - F: +6088 389 150
PETALING JAYA - APEX BOUTIQUE
T: + 603 7875 7833 - F: +603 7876 7833

MARRUECOS
CASABLANCA - CERAMEX
T: +00212 945 3646166 - F: +00212 522 395363
CASABLANCA - SANITAIRE 2000
T: +212 22 363 225 - F: +212 22 394 100
TANGER - FACENOR S.A.
T: +212 39 941 910 - F: +212 39 945 445

MARTINICA (ANTILLAS FRANCESAS)
LA MENTIN - JOSEPH COTTRELL S.A.
T: +596 509 810 - F: +596 506 524

MÉXICO
INTERLOMAS - PORCELANOSA MÉXICO
T: (+55) 36 05 00 84 - (+55) 36 05 00 65 - (+55) 36 05 00 67
MÉXICO DF - PORCELANOSA MÉXICO
T: (+55) 528220 00, (+55) 5282 2737
VALLE DORADO - PORCELANOSA MÉXICO
T: (+55) 2620 0186, (+55) 5831 7340

MOLDAVIA
CHISINAU - PLIMED (CASAMODERNA)
T: +373 2 2501252/54/55/56 - F: +373 2 2716824
CHISINAU - CASAMODERNA
T: +373 22 810 260/810 201/810 202/810 207
F: +373 22 810221
CHISINAU - DALIA
T: 223 82 93

MÓNACO
MÓNACO - PORCELANOSA Associatèe MÓNACO
T: +33 06 07 93 26 78

MONGOLIA
ULANBAATAR - ZUUNJIZMZN SUVRAGA CO.LTD
T: +976 (11) 341 217

MONTENEGRO
PODGORICA - ENTEXT
T: 38220260833

NEPAL
KATMANDU - RUKMANI INTERNATIONAL PVT LTD
T: +97714420281 - F: 97714428295

NICARAGUA
MANAGUA - DECO CENTER-GRUPO IBERICA NICARAGUA
T: +505 270 2121 - F: +505 277 0834

NIGERIA
LAGOS - PORCELANOSA Associatèe LAGOS
T: +234 8090371913

NORUEGA
OSLO - FAGFLIS
T: +47 22 80 85 60
OSLO - FAGFLIS OSLO
T: +47 22 80 1800 - F: +47 22 80 18 01
DRØBAK - FAGFLIS DRØBAK
T: +47 64 93 96 76
ELVERUM - FAGFLIS ELVERUM
T: +47 62 41 67 60 - F: +47 62 41 71 50
FAGERNES - FAGFLIS FAGERNES
T: +47 61 36 66 66 - F: +47 61 36 66 52
FREDRIKSTAD - FAGFLIS FREDRIKSTAD
T: +47 69 31 70 00 - F: +47 69 39 22 95
GJØVIK - FAGFLIS GJØVIK
T: +47 61 18 80 86 - F: +47 61 18 80 87
HAMAR - FAGFLIS HAMAR
T: +47 62 53 33 50 - F: +47 62 53 37 66
KLØFTA - FAGFLIS KLØFTA
T: +47 63 98 29 20 - F: +47 63 98 11 31
LIERSKOGEN - FAGFLIS LIERTOPPEN
T: +47 31 00 02 80 - F: +47 31 00 02 81
MOLDE - FAGFLIS MOLDE
T: +47 70 10 22 74 - F: +47 70 10 22 71
MOSS - FAGFLIS MOSS
T: +47 69 24 15 70 - F: +47 69 24 15 71
NARVIK - FAGFLIS NARVIK
T: +47 76 95 04 90 - F: +47 76 95 04 99
OPPDAL - FAGFLIS OPPDAL
T: +47 72 42 23 50
SANDEFJORD - FAGFLIS SANDEFJORD
T: +47 47 24 62 00 - F: +47 47 37 77 78
SANDNES - FAGFLIS SANDNES
T: +47 51 63 15 36 - F: +47 51 63 15 37
TØNSBERG - FAGFLIS TØNSBERG
T: +47 33 35 71 60 - F: +47 33 35 81 51
TRONDHEIM - FAGFLIS TRONDHEIM
T: +47 406 92 877
ÅLESUND - FAGFLIS ÅLESUND
T: +47 70 10 22 64 - F: +47 70 10 22 71
GURSKØY - FAGFLIS SØRE SUNNMØRE
T: +47 70 10 22 77
KOPERVIK - FAGFLIS HAUGALAND
T: +47 52 84 55 90 - F: +47 52 84 55 91
LYSAKER - FAGFLIS BAERUM
T: +47 67 10 34 90 - F: +47 67 10 34 91
NESTTUN - FAGFLIS BERGEN
T: +47 55 11 77 40 - F: +47 55 11 77 49
SKIEN - FAGFLIS GRENLAND
T: +47 35 58 70 00 - F: +47 35 58 70 01
TILLER - FAGFLIS TRONDHEIM
T: +47 72 89 68 60 - F: +47 72 89 68 70

NUEVA ZELANDA
PENROSE - TILE WAREHOUSE
T: 649349550 - F: 646222112
CHRISTCHURCH - NEXT DORE
T: 6433669400 - F: 6433664406

OMÁN
MUSCAT - ROYAL TILES CO
T: +968 9586 8897

PAÍSES BAJOS
AMSTERDAM - PGN CERAMICA B.V.
T: 0031 20 737 2845

PAKISTÁN
LAHORE - 4 WALLS (PVT.) Ltd.
T: 0092 321 403 60 91

PANAMÁ
CIUDAD DE PANAMÁ - EURO CER S.A.
T: (+507) 21 53660

PERÚ
SAN ISIDRO - PORCELANOSA GRUPO PERÚ
T: +519 4600 7828
LIMA - CASSINELLI
T: +51 14 513 712 - F: +51 15 612 757

POLONIA
BIALYSTOK - ACCESS
T: +48 85 6643436 - F: +48 85 6643434
BIELSKO BIALA - P.H.U. CERAMED
T: +48 33 829 8770 - F: +48 33 829 8773
BYDGOSZCZ - CERMAG POZNAN
T: +48 52 348 93 43 - F: +48 52 348 93 54
CZESTOCHOWA - P.H.U. FUGA
T: +48 343682944 - F: +48 343682944
GLIWICE - ART CERAMIKA
T: +48 32 339 8200 - F: +48 32 339 8209
GORZÓW - STREFA ARCHITEKTA
T: +48 95 721 41 08 - F: +48 95 721 41 08
KALISZ - STREFA ARCHITEKTA
T: +48 60 502 10 15 - F: +48 62 502 20 66
KATOWICE - MAX FLIZ
T: +48 32 720 92 00 - F: +48 32 720 92 00
KIELCE - EXCLUSIVE
T: +48 41 345 75 49
KOŁOBRZEG - CERMAG POZNAN
T: +48 94 355 18 88 - F: +48 94 355 18 80
KONIN - STREFA ARCHITEKTA
T: +48 63 243 31 14 - F: +48 63 243 30 97
KRAKÓW - MAX FLIZ
T: +48 01 229 07060 - F: +48 01 229 07060
KOSZALIN - STREFA ARCHITEKTA
T: +48 94 343 08 32
ŁÓDŹ - FUMINO
T: +48 426373767
ŁÓDŹ - CERMAG SP ZOO
T: +48 77 457 35 09 / 10 - F: +48 77 474 88 62
LESZNO - CERMAG POZNAN
T: +48 65 529 63 63 - F: +48 65 529 63 63
LUBLIN - EGEN
T: +48 81 441 58 42 - F: +48 81 441 80 74
OLSZTYN - CERMAG POZNAN
T: +48 89 534 41 21
OSTRÓW-WIELKOPOLSKI - CERMAG POZNAN
T: +48 62 735 81 12 - F: +48 62 737 28 91
OPOLE - CERMAG SP ZOO
T: +48 42 616 55 44 - F: +48 42 611 61 61
POZNAN - CERMAG POZNAN
T: +48 61 835 97 50-54 - F: +48 61 830 23 78
RADOM - CERAMIKA PRIMUS
T: +48 48 381 0287 - F: +48 48 381 0290
RZESZÓW - F.H. BOZ S.A.
T: +48 17 850 0315 - F: +48 17 850 0341
SÓPOL - CERMAG POZNAN
T: +48 58 550 42 35 - F: +48 58 550 54 59
SZCZECIN - STREFA ARCHITEKTA
T: +48 91 434 00 48 - F: +48 91 434 07 35
ŚLUPSK - GRESMAX
T: +48 59 843 41 53 - F: +48 59 843 4153
WARSZAWA - WOIS SP Z.O.O
T: +48 22 6127213 - F: +48 22 6127216
WARSZAWA - GRESTON
T: +48 022 720 5525 - F: +48 022 720 5524
WARSZAWA - ANBAR
T: +48 22 721 11 20 - F: +48 22 721 11 20
WARSZAWA - CERMAG POZNAN
T: +48 22 252 57 39 - F: +48 22 252 57 39
WROCŁAW - CERMAG WROCŁAW
T: +48 717 820 021 - F: +48 717 820 031

RUMANIA
CRAIOVA - SC MYDWAY IMPEX SRL
T: +0040 722 285 029 - F: +0040 251 427 946
ORADEA - MAISON DESING
T: +40 743 507 811 F: +40 259 410 170
BUCAREST - DELTA STUDIO
T: 031/405 82 17
BUCAREST - GLAMOUR
T: 0321 2293201
BUCAREST - PORCELINES
T: +40 756 093 720

RUSIA
EKATERIMBURGO - SALON BOMOND
T: +7 (922) 135 35 92
GROZNY - BOMOND
T: +7 (8712) 224 546
KALININGRAD - KERAMIKA & KERAMONGRANIT
T: +7 (4012) 370 460
KHABAROVSK - DOM APEX
T: +7 (4232) 30 06 88
KHIIMKI - ZODIAC
T: +7 (495) 747 31 69
KRASNODAR - SALON BOMOND
T: +7 (862) 234 10 75
KRASNOYARSK - ELITSTROY
T: +7 (391) 206 99 99
MAKHACHKALA - T. D. MODERN
T: +7 (8722) 676 569
MOSCOW - ARTISAN
T: +7 (495) 742 40 40
MOSCOW - MASTER DOM
T: +7 (499) 120 00 77
MOSCOW - SALON UNDERGROUND
T: +7 (495) 253 69 32
MOSCOW - ZODIAC
T: +7 (495) 975 27 97
MOSCOW - ZODIAC
T: +7 (495) 721 49 90

International Showrooms

MOSCOW - ZODIAC
T: +7 (495) 984 28 57
MOSCOW - ZODIAC
T: +7 (495) 223 40 44
MYTISCHI - ZODIAC
T: +7 (495) 221 75 00
MYTISCHI - ZODIAC
T: +7 (495) 975 27 97
NIZHNY NOVGOROD - ZODIAC
T: +7 (831) 216 08 08
NOVOROSIYSK - AGORA
T: +7 (8617) 615 999
NOVOROSIYSK - MOY DOM
T: +7 (383) 223 24 87
PYATIGORSK - SALON BOMOND
T: +7 (8793) 975 544
ROSTOV NA DONU - SALON BOMOND
T: +7 (863) 266 50 34
RYAZAN - SINTI
T: +7 (4912) 46 00 46
ST. PETERSBURG - DOM LAVERNA
T: +7 (812) 329 56 65
ST. PETERSBURG - DOM LAVERNA
T: +7 (812) 327 94 09
ST. PETERSBURG - DOM LAVERNA
T: +7 (812) 7777 030
ST. PETERSBURG - SALON ELITNOY KERAMIKI NOVUS
T: +7 (812) 325 12 45
ST. PETERSBURG - ZODIAC
T: +7 812 994 79 49
STAVROPOL - SALON VALENCIA
T: +7 (8652) 298 151
VLADIVOSTOK - DOM APEX
T: +7 (4232) 300 688
VOLGOGRAÐ - BOMOND
T: +7 (8442) 944 709

SENEGAL
DAKAR - C.C.S.
T: +221 33 849 04 04 - F: +221 33 823 13 10

SERBIA
BELGRADO - CERAMIC BY PORCEL.
T: +381 11 3343026 - F: +381 11 3343297
NOVI SAD - RACA COMPLETE
T: +381 21 451 534 - F: +381 21 472 0668

SINGAPUR
SINGAPUR - FERNANDO MARTIN BENITO
T: +65 97801472 - F: +65 64621620
SINGAPUR - HAFARY PRIVATE LIMITED
T: +6566047702 - F: +6562534496

SRI LANKA
COLOMBO 13 - RANJANA'S CERAMIC
T: +94 11 2543255 - F: +94 11 2381386

SUDÁFRICA
DURBAN - CLASSIC TRADING
T: +27 31 577 8382 - F: +27 31 577 7056
JOHANNESBURGO - CLASSIC TRADING
T: +27 11 656 0400 - F: +27 11 656 0403

SUECIA
MÖLNDAL - KAKELPALATZET I MÖLNDAL Headquarters
T: +46 (0)31 776 50 51 - F: +46 (0)31 86 39 62
BROMMA - KAKELPALATZET I BROMA AB
T: +46 (0)8 56 487 831 - F: +46 (0)8-988 620
GÖTEBORG - KAKELPALATZET I BÄCKEBOL AB
T: +46 (0)31 571 478 - F: +46 (0)31-571 477
KATRINEHÖLM - KAKELPALATZET I KATRINEHÖLM AB
T: +46 (0)8150-51 740 - F: +46 (0)150-51 775
NYKÖPING - KAKELPALATZET I NYKÖPING AB
T: +46 (0)155 200 999 - F: +46 (0)155-211 244
UDDEVALLA - KAKELPALATZET I UDDEVALLA AB
T: +46 (0)522 64 54 00 - F: +46 (0)0522-64 54
MÄLMÖ - KERMA KAKEL AB
T: +46 403 122 40 - F: +46 403 122 59
ENKÖPING - LHADOS KAKEL AB
T: +46 171 478 090 - F: +46 171 478 099
HÄSLEHOLM - STENMONTÖREN AB
T: +46 451 381 970 - F: +46 451 381 979

SUIZA
AUBONNE - ARGECON SA
T: +41 (0) 21 807 10 10 - F: +41 (0) 21 808 61 02
ARBON - HAMA KERAMIKDESIGN
T: +41 71 446 61 66 - F: +41 71 446 61 65
BASEL - SABAG SA
T: +41 61 337 83 83 - F: +41 61 337 83 88
BASEL - PORCELANOSA BÄLE
T: +4161 693 00 00
BIEL - SABAG SA
T: +41 32 328 28 28 - F: +41 32 328 28 80
CRISSIER - SABAG SA
T: +41 21 633 06 84 - F: +41 21 633 06 85
GENÈVE - SABAG SA
T: +41 22 908 06 90 - F: +41 22 908 06 95
YVERDON-LES-BAINS - SABAG SA
T: +41 24 423 44 30 - F: +41 24 423 44 45
SEVELEN - KAISER AG BAD & PLÄTTLI
T: +41 81 785 2242 - F: +41 81 785 2204

VOLKETSWIL - MPV HANDELS AG
T: +41 (0)43 399 53 00 - F: +41 (0)43 399 53 20
DELÉMONT - SABAG SA
T: +41 32 4 216 216 - F: +41 32 4 216 214
HÄGENDORF - SABAG SA
T: +41 62 209 09 09 - F: +41 62 209 09 00
ROTHENBURG - SABAG SA
T: +41 41 289 72 72 - F: +41 41 289 72 73
ZÜRICH - SABAG SA
T: +41 44 446 17 17 - F: +41 44 446 17 50
RÜTI B. BÜREN - STEIN & KERAMIK
T: +41 32 351 22 44 - F: +41 32 351 25 90
MENDRISO - NEW FORM SWISS SÄGL
T: +41 91 922 7356

SURINAME
PARAMARIBO - NV RONANS TRADING
T: +597 451070 - F: +597 450066

TAILANDIA
BANGKOK - BOONTHAVORN CERAMIC (RATCHADAPISEK)
T: +66 2 275 0029 - F: +66 2 275 2057
BANGKOK - BOONTHAVORN CERAMIC CO. LTD (PINKLÄO)
T: +66 2 441 3075 - F: +66 2 441 4049
BANGKOK - BOONTHAVORN CERAMIC CO. LTD (SUARNABHUMI)
T: +66 2 316 0429 - F: +66 2500682
BANGKOK - BOONTHAVORN CERAMIC CO. LTD (KASET NAVAMIN)
T: +66 2 791 2777 - F: +66 2 943 9058
BANGKOK - BOONTHAVORN CERAMIC CO. LTD (PATTAYA)
T: +66 38 052 222 - F: +66 38 052 221
CHIANGMAI - BOONTHAVORN CERAMIC CO. LTD. (CHIANGMAI)
T: +66 53 105 099 - F: +66 53 105 107
PRACHIJABKRIKUN - BOONTHAVORN CERAMIC CO. LTD (HUAHIN)
T: +66 3252-2555// +668-5488-4144 - F: +66 3252 0141
PATHUMTHANEE - BOONTHAVORN CERAMIC CO. LTD (RANGSIT)
T: +66 2 902 0171 - F: +66 2 902 0184
SAMUTSAKON - BOONTHAVORN CERAMIC CO. LTD
(THONBUREE-PAKHOR)
T: +66 2 896 4471-2 - F: +66 2 896 4473

TAIWÁN
KAOHSIUNG - NEW CENTURY CONSTRUCTIONAL CORP
T: +886 7 384 8834 - F: +886 7 387 1043
TAINAN - NEW CENTURY CONSTRUCTIONAL CORP
T: +886-7-3848834
TAIPEI - NEW CENTURY CONSTRUCTIONAL CORP
T: 73845135
TAICHUNG - NEW CENTURY CONSTRUCTIONAL CORP
T: +886 4 2372 8166 - F: +886 4 2376 2818

TÚNEZ
TÚNEZ - LIFE STYLE
T: +216 71 861 551 - F: +216 71 861 549
TUNIS CEDEX - ABDENNADHER BRICOLAGE CENTER
T: +216 71 725 194 - F: +216 71 760 046
SFAÏX - ABC ABDENNADHER
T: 74 46 80 72 - F: 74 24 48 85
HAMMAM SOUSSE - ABC ABDENNADHER
T: 73 32 44 24 - F: 73 32 44 25
HAMMAMET - ABC ABDENNADHER
T: 72 26 04 77 - F: 72 26 04 77
GABES - ABC ABDENNADHER
T: 75 29 49 10 - F: 74 24 48 85
MENZEL HAYET - ABC ABDENNADHER
T: 73 41 04 16 - F: 73 41 04 01
SOUSSE - ABC ABDENNADHER
T: 73 37 14 76 - F: 73 37 14 75
TÚNEZ - ABC ABDENNADHER
T: 71 72 58 80 / 71 72 57 77 - F: 71 76 00 46
TURKMENISTAN
ASHGABAD - AK TAY
T: +99312 220134

TURQUÍA
ISTAMBÜL - YÜTAS
T: +90 2 1227 44720 - F: +90 2 1227 20874

UCRANIA
KHARKIV - EUROPA
T: (572) 23 59 95
KYIV - SALON MILLENNIUM CONCEPT
T: (044) 279 60 60
LVIV - SALON KARMEN
T: +380 32 244 40 55 - F: +380 32 252 70 94
ODESSA - ITIS GALLERY
T: + 38 (442) 781 910
DONETSK - NAUTILUS
T: 062 387 58 58
DNIPROPETROVSK - EUROPA
T: (0562) 31-27-53

URUGUAY
MONTEVIDEO - ACHER
T: +598 2 487 5630
PUNTA DEL ESTE - ACHER
T: +598 42 248 343 / + 598 42 250 869

UZBEKISTAN
TASHKENT - PREMIUM CONCEPT
T: +998(71) 256 29 05

VENEZUELA
CARACAS - PROSEIN
T: +58 212 239 2911 - F: +58 212 239 9460
CARACAS - PROSEIN EL BOSQUE
T: (+582) 1276 256 01
CARACAS - PROSEIN LA CASTELLANA
T: (+582) 1226 564 19

VIETNAM
HANOI - MILAN ARCHITECTURAL
T: +84 4 3791 3567 - F: +84 4 3791 3568
HANOI - MILAN ARCHITECTURAL
T: +84 432 345 027 - F: +84 432 345 028
HOCHIMINH CITY - MILAN ARCHITECTURAL
T: +84 8 5412 1819 - F: +84 8 5412 1820
HOCHIMINH CITY - CASABELLA CO LTD (HA AN HANH)
T: +84 913237771


YEMEN
SANNA - AL-YAMAMAH GROUP ABO JALAL TAHER
CORPORATION FOR GENERAL TRADE
T: +967 1 470 375 - F: +967 1 405 665

YIBUTI
DJIBOUTI - AL-NEIMA IMMOBILIERE
T: 00253-21356659 - F: 00253-21356289



butech®
PORCELANOSA Grupo

butech building technology, s.a.
Ctra. Vila-real - Puebla de Arenoso (CV-20), Km. 2.5 · Apartado de Correos 297 · 12540 Villarreal, Castellón - ESPAÑA.
Teléfono (+34) 964 53 62 00 · Fax: (+34) 964 53 00 34 · E-mail: butech@butech.es · www.butech.es





BY APPOINTMENT TO
H.R.H. THE PRINCE OF WALES
MANUFACTURER AND DISTRIBUTOR
OF CERAMIC TILES AND BUILDING PRODUCTS.
PORCELANOSA GROUP LIMITED

PORCELANOSA Grupo

butech.